



Hon. Pedro R. Pierluisi Urrutia
Gobernador

Lcda. Karla G. Mercado Rivera
Administradora y Principal Oficial de Compras

ENMIENDA NÚM. 1

SUBASTA FORMAL 22J-11066

PARA LA ADQUISICIÓN DE SERVICIOS DE REPARACIÓN GENERAL DE LA INFRAESTRUCTURA DEL CENTRO SARAFS EN BAYAMÓN, ADSCRITO AL DEPARTAMENTO DE SALUD DEL GOBIERNO DE PUERTO RICO

Asunto: Tabal de Cotizar Enmendada I

Se notifica a los licitadores interesados en participar en la Subasta de referencia la siguiente enmienda:

- I. Se adjunta **Tabla de Cotizar Enmendada I**, la cual tendrán que ser utilizada por los licitadores para presentar su oferta.

Esta Enmienda forma parte del Pliego de Subasta y quienes interesen licitar, tendrán que considerarla al presentar su Oferta. Todos los demás términos, condiciones y especificaciones permanecen sin alterar.



Héctor Ortiz Méndez
Administrador Auxiliar
Área de Adquisiciones



Aura Rosa Vázquez
Oficial de Licitación

Emitido hoy jueves, 6 de octubre de 2022
En San Juan, Puerto Rico





TABLA DE COTIZAR ENMENDADA I
SUBASTA FORMAL 22J-11066

PARA TRABAJOS DE MEJORAS PERMANENTES EN SARAF ADCRITO AL DEPARTAMENTO DE SALUD DEL GOBIERNO DE PUERTO RICO

Partida	Descripción	Costo Materiales	Costo Labor	Total	Garantía	Término de Entrega
Roof Drainage						
1	Remove and replace 8 each of Roof drainage screens, 6 IN wide x 1 FT high.					
Roof Electrical						
2	Remove and replace 1 each of NEMA Type 3R Hinged Electrical panel and supportive frame, 1 FT long x 6 IN wide x 3 FT high.					
3	Remove and replace 930 FT Long of 1 IN PVC Electrical Conduit.					
Exterior HVAC						
4	Remove and replace 13 each of 36000 BTU Air Conditioning Units.					
5	Secure and anchor 3 each of Inverter Air Conditioning Units.					
Exterior Awning						
6	Remove and replace with in kind material, design, color, hardware and workmanship, 120 SF of Aluminum Awning, 10 FT long x 12 FT wide.					
Exterior Fence						
7	Remove and replace with in kind material, design, color, hardware and workmanship, 25 FT Long of Metal Cyclone Fence with 3 strands, 6 FT High.					
Exterior Paint						
8	Prep and paint 500 with in kind material, design, color, hardware and workmanship, SF of Exterior Surfaces.					



TABLA DE COTIZAR ENMENDADA I
SUBASTA FORMAL 22J-11066

PARA TRABAJOS DE MEJORAS PERMANENTES EN SARAF ADCRITO AL DEPARTAMENTO DE SALUD DEL GOBIERNO DE PUERTO RICO

Partida	Descripción	Costo Materiales	Costo Labor	Total	Garantía	Término de Entrega
9	Prep and paint with in kind material, design, color, hardware and workmanship, 750 SF of Exterior Metal Handrail.					
10	Building Exterior with in kind material, design, color, hardware and workmanship, 360 SF of Exterior Walkway Ceiling.					
11	Prep and paint with in kind material, design, color, hardware and workmanship, 308 SF of Exterior Walkway Wall.					
Exterior Plaster						
12	Repair 18 SF of Wall Plaster					
13	Repair 108 SF of Concrete Plaster					
14	Repair 50 SF of Concrete Plaster					
Exterior Water Cistern						
15	Remove and replace with in kind material, design, color, hardware and workmanship, 4 each of Wooden Cistern Doors, 3.75 FT wide x 5.5 FT high.					
16	Remove and replace 1 each of Water Pump.					
Exterior Windows						
17	Remove and replace with in kind material, design, color, hardware and workmanship, 2 each of Jalousie windows (Miami type windows), 3.5 FT wide x 6 FT high.					



TABLA DE COTIZAR ENMENDADA I
SUBASTA FORMAL 22J-11066

PARA TRABAJOS DE MEJORAS PERMANENTES EN SARAF ADCRITO AL DEPARTAMENTO DE SALUD DEL GOBIERNO DE PUERTO RICO

Partida	Descripción	Costo Materiales	Costo Labor	Total	Garantía	Término de Entrega
18	Remove and replace with in kind material, design, color, hardware and workmanship, 1 each of Jalousie window, 3.5 FT wide x 2.75 FT high.					
19	Remove and replace with in kind material, design, color, hardware and workmanship, 3 each of Aluminum Jalousie windows, 3.5 FT wide x 5.5 FT high.					
20	Remove and replace with in kind material, design, color, hardware and workmanship, 1 each of Jalousie window, 3.8 FT wide x 8 FT high.					
Interior HVAC						
21	Remove and replace 1 each of 36000 BTU Air conditioning window unit.					
Interior Lights						
22	Remove and replace 1 each of 2 lamp fluorescent light fixtures, 4 FT long x 1 FT wide.					
23	Remove and replace 1 each of 2 lamp fluorescent light fixture, 4 FT long x 2 FT wide.					
24	Remove and replace 1 each of 2 lamp Fluorescent light fixtures, 1 FT long x 4 FT wide.					
25	Remove and replace 1 each of 4 lamp fluorescent light fixture, 4 FT long.					
Interior Paint						
26	Prep and paint with in kind material, design, color, hardware and workmanship, 100 SF of Surfaces in Room 206.					



PARA TRABAJOS DE MEJORAS PERMANENTES EN SARAF ADCRITO AL DEPARTAMENTO DE SALUD DEL GOBIERNO DE PUERTO RICO

Partida	Descripción	Costo Materiales	Costo Labor	Total	Garantía	Término de Entrega
Asbesto & Lead Based Paint Removal						
27	Asbesto and lead paint removal in compliance with the reports.					
Total Cost						
	Total = \$					
Término de Entrega de la Obra: _____						