Formal Bidding to Contractors for the Restoration of the Historical Heritage of Puerto Rico:

EL CORTIJO

Barranquitas, Puerto Rico

(ASG Num.23J-15905)

(SHPO CODE: 01-14-21-02)

PROJECT TILE: Restoration of the Historical Heritage of Puerto Rico: El Cortijo

PROJECT LOCATION: Barranquitas, Puerto Rico

BACKGROUND: El Cortijo was built in 1939. Used as a summer family residence.

In 2017, due to the impact of hurricane Maria this historical building suffered severe damages.

The objective of this project is to restore and replace, as applicable, elements that were affected by the Hurricane Maria & Irma such as, but not limited to, exterior doors, windows, metal grilles, exterior paint, tiles, a light fixture, railings, balusters, a weathervane, repairs to the freshwater system, and roof tile damage to a condition consistent with their previous state while ensuring to better withstand similar storm events in the future.

SCOPE OF WORK

The Contractor is accountable for the complete project requirements indicated in the Proposal Documents and shall build, furnish, install, and complete all project components. Contractor is responsible to provide all information needed to complete construction permit process and contractor is responsible to expedite and pay any applicable fee for any other permit and/or endorsements. (e.g. lane closure). Contractor is responsible for the payment of all applicable permits and endorsements fees, Department of Transportation and Public Works (DTPW) bonds, agencies contributions (PREPA, PRASA, etc.) and *taxes. Refer to the Uniform General Conditions for Public Works Contracts.

The execution of this project will impact multiple doors, windows, metal railings, balusters, paint works, tile repairs, roof gutters, roof waterproofing, fresh water system repairs, and lead abatement works throughout the building, among others. Please refer to construction drawings and specifications. Due to the historical nature of the building, this task needs to be accomplished with expert personnel, and specific materials and techniques to maintain and preserve the historical aspect.

^{*} This building is historic, therefore it has a 50% discount on municipal construction taxes.

The bidder should review in detail the construction drawings and specifications, where the information of the work to be carried out is detailed. The following is a summary of some important points.

- Drawing sheet A-01 includes instructions for repair works on exterior walls, lamp replacement, and window replacement. This sheet includes the alternate information for the options of including as part of the project the repair of the fireplace facade, kitchen tile replacement, repair of the staircase wall, refinish window grilles, refinish wooden balustrades, install smoke detectors and the painting of interior elements.
- Drawing sheet A-02 includes instructions for the replacement of windows, doors, and metal balustrades. This sheet also includes alternate information for the option of including as part of the project the repair of the staircase wall, refinishing of wooden balustrades, and installation of smoke detectors.
- Drawing sheets A-01.1, A-01.2, A-01.3, A-02.1, A-02.2 and A-03.1 all contain images referencing the work instructed on sheets A-01, A-02 and A-03.
- Roof tile and gutter information is found on sheet A-03. Please note that as an alternate it may be included in the project for the roof to be waterproofed above the existing tiles.
- Drawing sheet P-01 includes the freshwater system works.
- Note that only windows and doors marked G, H, J, L, 33, 38, and 39 are being replaced. Window and door schedule can be found on sheet A-06.
- The Bidding Set includes the "General Restoration Notes", "General Cleaning Notes", "Finish Notes", "Submittal Notes", "Lead-Based Paint General Notes" & "Lead-Based Paint Abatement Notes" on multiple sheets. The G.C. is responsible for reviewing these notes carefully and follow their instructions during the restoration process.
- G.C. may use a substitute product as long as it is equivalent to & matches the characteristics of all specified products on the Bidding Set. G.C. shall submit all proposed substitute products to architect for approval prior to order.
- Elements marked in blue on the drawings means that they are new, and items marked in red mean that they are to be removed. It is important for the G.C. to understand the use of color in the Bidding Set and the possibility of missing instructions if printed in black & white.
- Some sheets contain images of the damages, as referenced on the floor plans, each with restoration instructions.
- This bidding set includes a Door and Window Schedule. The G.C. shall be responsible for carefully reviewing the drawings, information, and notes included on the sheet.
- Alternates are including on the Bidding Set. Alternates depend on the final bid cost and are thus separated from the most necessary works.
- This property has Lead-Based paints in the interior and exterior. G.C. shall consider lead abatement measures as part of the project scope.
- This building is historic, therefore it has a 50% discount on municipal construction taxes.
- If any questions arise regarding the contract or any note, G.C. must ask during bidding process.

^{*} This building is historic, therefore it has a 50% discount on municipal construction taxes.

SITE VISIT

A site visit is a mandatory requirement for all contractors bidding on the project. It is our recommendation the contractor bring their subcontractors to the site visit for their team to have a clear understanding of the project scope. The contractors shall be responsible for reviewing the "Pliego de Subasta Formal 23J-15905 by ASG" for site visit date, time and location.

The site visit will start with a project explanation by the architect, then the contractors will have the opportunity to do a walk-through in the property to observe and familiarize themselves in detail with the project. The contractor must submit, along with the Proposal, the provided PRE-BID SITE VISIT CERTIFICATION FORM.

The bidder shall fully acquaint themselves with conditions relating to construction and labor so that he or she may fully understand the facilities, difficulties, and restrictions attending the execution of the work under the Contract. It shall be assumed that the Bidder has investigated and is satisfied as to the condition of the work to be performed and materials to be furnished and shall base bid on their own opinion of the conditions likely to be encountered, and for the bid price must assume all risk of variance, by whomsoever made, in any computation or statement of amounts or quantities necessary to fully complete the work in strict compliance with the Contract Documents.

Each Bidder shall thoroughly examine and be familiar with the plans and specifications. The failure or omission of any Bidder to receive or examine any form, instrument, addendum, or other documents or to visit the site and acquaint themselves with conditions there, existing shall in no way relieve any Bidder from any obligation with respect to their bid or to the contract. The submission of a bid shall be taken as prima facie evidence of compliance with this document.

No plea of ignorance of conditions that exist or that may hereafter exist, or of conditions or difficulties that may be encountered in the execution of the work under this contract, as a result of failure to make the necessary examinations and investigations, will be accepted as an excuse for any failure or omission on the part of the Contractor to fulfill, in every detail, all of the requirements of Contract Documents, nor will they be accepted as a basis on any claim whatsoever for extra compensation or for an extension of time.

Each Bidder shall be responsible for understanding the extent of lead and asbestos present in the property, if any.

DISCREPANCIES

Should a Bidder find discrepancies or ambiguities in, or omissions from, the Drawings or Specifications, or should they be in doubt as to their meaning, they shall at once notify the Architect during the bidding process.

^{*} This building is historic, therefore it has a 50% discount on municipal construction taxes.

INTERPRETATION OF PLANS

On all drawings the figured dimension shall govern in case of discrepancy between the scales and figures. The Contractor shall take no advantage of any error or omission in the Drawings or of any discrepancy between the Drawings and Specifications. The Architect shall make such interpretations as may be deemed necessary for the fulfillment of the intent of the Drawings and Specifications as construed by the architect, and their decision shall be final. If there is a discrepancy between plans and specifications, the Architect reserves the right to choose at his discrepancy at no cost to the Owner.

INTERPRETATION OF CONTRACT DOCUMENTS PRIOR TO OPENING OF BIDS

If any person contemplating submitting a bid for the proposed contract is in doubt as to the true meaning of any part of the Drawings, Specifications, or other proposed Contract Documents, they may submit to the Architect a written request for an interpretation thereof. The person submitting the request will be responsible for its prompt delivery. Any interpretation of the proposed documents will be made only by addenda duly issued and copies of such addenda will be e-mailed or delivered to each person receiving a set of such documents. Request for interpretations or clarification of the Contract Document must be made in writing following the instructions and date established in the "Pliego de Subasta Formal 23J-15905 by ASG". The Owner will not be responsible for any other explanation or interpretation of the documents.

CONSTRUCTION TIME

The contract period is 167 calendar days. The contractor will have (5 months) 152 calendar days after the Notice to Proceed to achieve the Substantial Completion; for Final Completion the contractor will have 15 calendar days after Substantial Completion. For administrative closing, the agency has 30 calendar days after Final Completion.

The failure to complete the work within the Substantial Completion will be subject to the application of Liquidated Damages as per the Uniform General Conditions for Public Works Contracts.

PROPOSAL

COMPANY INFORMATION

COMPANY RESUME

The bidder must submit a corporate and/or professional resume that includes the following information:

- Name of the Business and/or Firm
- Name of other associated business, firms, and/or professionals
- Name of owner/s and/or principal/s

^{*} This building is historic, therefore it has a 50% discount on municipal construction taxes.

- Office location address
- Type of organization
- Organizational chart of the company and Organization chart for the project
- Description of types of services offered
- Professional licenses and credentials of the Business

ACTUAL ENDEAVORS

At the time of this formal bidding, the bidder must present a list with on-going projects, including their expected completion date. If applicable, federally funded projects must be listed separately or highlighted.

QUALIFICATIONS

REFERENCES

Two (2) written references of firm's efficiency and effectiveness of services. Must include name, address, phone numbers and emails.

PAST PERFORMANCE

The bidder must present 3 similar historic projects completed within the past 10 years, providing information of the name of the architect or designer, location, cost, and reference contact, using the attached Project Fact Sheet. For each project, the contractor must undergo the due diligences to complete and submit the attached Past Performance Questionnaire (PPQ) form. Incomplete Project Fact Sheets and PPQs will not be accepted, and may automatically disqualify the bidder.

KEY PERSONNEL

The bidders must include on their proposal a list of subcontractors that they will use to complete the Work. The subcontractor list must also include their experience in historic restoration.

NARRATIVE & MANAGEMENT APPROACH

The bidders should include as part of their proposal a Management Approach Narrative that indicates the work plan to perform the activities. (Max 2 pages, single space, font 12, Times New Roman). Answer the following:

- Which project management approach(es) will be implemented?
- What is your lead abatement plan?
- What is the proposed method of construction?
- What are the specific stages of your management process for this project?
- Which activities and/or techniques will be used to constitute a work team?
- How will you solve a work team conflict related to the required deliverables?
- How will you maintain a timely submittal of deliverables?

^{*} This building is historic, therefore it has a 50% discount on municipal construction taxes.

TIME SCHEDULE

The bidders will include a time schedule as part of the proposal, must consider materials lead times, drying/curing times, any other additional activities that are necessary and impact the time to complete the work. Bidders must provide specificity of milestones and project deliverables.

PRICE

Bidders shall complete the provided form for all the services to be provided on this project. It is understood that the price shall include prices including all labor, equipment, materials, bailing, incidental work, overhead, profit, insurance, mobilization, demobilization, materials laboratory testing, etc. to cover the desired scope of work. The bidders' quote shall include the cost of construction municipal taxes* and patents ("arbitrios de construcción* y patentes municipales"). (Itemized project budget is needs)

SUBMITTAL OF PROPOSAL

Proposals shall be submitted as per the "Pliego de Subasta Formal 23J-15905 by ASG".

^{*} This building is historic, therefore it has a 50% discount on municipal construction taxes.

PRE-BID SITE VISIT CERTIFICATION FORM

Restoration of the Historical Heritage of Puerto Rico

EL CORTIJO

RD. PR 162 KM 18.5, BARRANQUITAS, 00705

The undersigned, as Bidder, hereby declares that he or she has visited the site of the construction as shown on the drawings and specifications, has familiarized himself/herself in detail with the facilities and has fully acquainted themselves with the work to be done; that he or she has thoroughly examined the drawings, Specifications and all contract Documents pertaining thereto; and has read all Addenda issued prior to the opening of Bids; all as designed under Arquiteg – Architects & Planners. The bidder also certifies that that he or she has received the briefing provided by Arquiteg - Architects & Planners and understands the full scope of the project with respect to the existing conditions on the site.

The bidder shall fully acquaint themselves with conditions relating to construction and labor so that he or she may fully understand the facilities, difficulties, and restrictions attending the execution of the work under the Contract.

The bidder has correlated the information known to the bidders, information and observations obtained from visits to the site, reports and drawings identified in the RFP Documents, and all additional examinations, investigations, explorations, tests, studies, and data with the Conceptual Documents.

CERTIFICATION: I hereby certify that the above information is true and accurate.
Name of Bidder:
Signature of Bidder:
Corporate Seal



TECHNICAL SPECIFICATIONS BOOK FOR

EL CORTIJO

CARR. PR 162 KM 18.3 BARRANQUITAS, PUERTO RICO

ISSUE FOR BIDDING NOT FOR CONSTRUCTION

UPDATED - JUNE 19, 2023





ARCH. VICTOR M. VILLEGAS D. C.A.A.P.P.R. / S.C.A. / A.I.A

AVE. FERNANDEZ JUNCOS 751- MIRAMAR HISTÓRICO - SAN JUAN, P.R. 00907 OFICINA (787) 723-2031 - FAX (787) 722-5031

EMAIL: arquitectospr@arquiteg.com

TECHNICAL SPECIFICATIONS FOR

EL CORTIJO

CARR. PR 162 KM 18.3 BARRANQUITAS, PUERTO RICO

TABLE OF CONTENTS

DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

Section	00 01 01	Project Title Page
Section	00 01 10	Table of Contents

DIVISION 01 – GENERAL REQUIREMENTS

Section	01 00 00	General Specifications
Section	01 31 00	Project Management and Coordination
Section	01 33 00	Submittals Procedures
Section	01 50 00	Temporary Facilities
Section	01 71 00	Cleaning up
Section	01 77 00	Closeout Procedures

DIVISION 02 - EXISTING CONDITIONS

Section	02 05 00	Demolitions and Alterations
Section	02 26 23	Asbestos Assessment
Section	02 26 26	Lead Assessment
Section	02 82 13	Asbestos Abatement
Section	02 83 19	Lead-Based Paint Abatement

DIVISION 06 – WOODS, PLASTICS, AND COMPOSITES

Section	06 20 00	Carpentry
Section	06 05 73	Pressure Treated Wood
Section	06 30 00	Epoxy Repair for Deterioration and Decay in
		Wooden Members

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

Section 07 10 00 Damp proofing and Waterproof

DIVISION 08 - OPENINGS

Section 08 14 00 Interior Wood Doors

DIVISION 09 – FINISHES

Section	09 30 00	Tiling
Section	09 90 00	Interior and Exterior Paints and Coatings
Section	09 91 00	Painting
Section	09 94 10	Field Painting

DIVISION 10 - SPECIALITIES

Section 10 82 13 Exterior Grilles and Screens

END OF TABLE OF CONTENTS

SECTION 01 00 00

GENERAL SPECIFICATIONS

DEFINITIONS

Wherever the words defined in this section or pronouns used in their stead occur in the Contract Documents, they shall have the meanings herein given.

AS DIRECTED, AS REQUIRED, ETC.

Wherever in the Contract Documents, or on the Drawings, the words "as directed," "as ordered," "as requested," "as required," "as permitted," or words of like import are used, it shall be understood that the direction, order, requirement, or permission of the Architect is intended. Similarly, the words "approved," "acceptable," "suitable," "satisfactory," and words of like import shall mean approved by, acceptable to, suitable to, or satisfactory to the Architect.

ELEVATION

The figures given on the Drawings or in the other Contract Documents after the word "elevation" or abbreviation of it shall mean the distance in feet above the datum adopted by the Architect.

ROCK

The word "rock", wherever used as the name of an excavated material or material to be excavated, shall mean only boulders and pieces of concrete or masonry exceeding 1 cu. yd. in volume, or solid ledge rock which, in the opinion of the Architect, requires, for its removal, drilling and blasting, wedging, sledging, barring, or breaking up with a power-operated tool. No soft or disintegrated rock which can be removed with a hand pick or power-operated excavator or shovel, no loose, shaken, or previously blasted rock or broken stone in rock fillings or elsewhere, and no rock exterior to the maximum limits of measurement allowed, which may fall into the excavation, will be measured or allowed as "rock."

EARTH

The word "earth", wherever used as the name of an excavated material or material to be excavated, shall mean all kinds of material other than rock as above defined.

2. ABBREVIATIONS AND CLARIFICATIONS

Where any of the following abbreviations are used in the Contract Documents, they shall have the meaning set forth opposite each.

AASHTO American Association of State

Highway and Transportation

Officials

ACI American Concrete Institute

AISC American Institute of Steel Construction

ANS American National Standard

ANSI American National Standards Institute

ASCE American Society of Civil Architects

ASTM American Society for Testing and Materials

AWWA American Water Works Association

Fed. Spec. Federal Specifications issued by the

Federal Supply Service of the General Services Administration, Washington,

D. C.

125-lb. ANS American National Standard for Cast-iron 250-1b. ANS

Pipe Flanges and Flanged Fittings, Designation B16.1-1975, for the

appropriate class

AWG American or Brown and Sharpe Wire

Gage NPT National Pipe Thread

OS&Y Outside screw and yoke

Stl. WG U. S. Steel Wire, Washburn and Moen, American Steel and Wire or Roebling

Gage

USS Gage United States Standard Gage

WOG Water, Oil, Gas

WSP Working steam pressure

3. HANDLING AND DISTRIBUTION

The Contractor shall handle, haul, and distribute all materials and all surplus materials on the different portions of the Work, as necessary or required; shall provide suitable and adequate storage room for materials and equipment during the progress of the Work, and be responsible for the protection, loss of, or damage to materials and equipment furnished by him, until the final completion and acceptance of the Work.

Storage and demurrage charges by transportation companies and vendors shall be borne by the Contractor.

4. MATERIALS - SAMPLES - INSPECTION

Unless otherwise expressly provided on the Drawings or in any of the other Contract Documents, only new materials and equipment shall be incorporated in the Work. All materials and equipment furnished by the Contractor to be incorporated in the Work shall be subject to the inspection of the Architect. No material shall be processed or fabricated for the Work or delivered to the Work site without prior concurrence of the

Architect.

As soon as possible after execution of the AGREEMENT, the Contractor shall submit to the Architect the names and addresses of the manufacturers and suppliers of all materials and equipment he proposes to incorporate into the Work. When shop and working drawings are required as specified below, the Contractor shall submit prior to the submission of such drawings, data in sufficient detail to enable the Architect to determine whether the manufacturer and/or the supplier have the ability to furnish a product meeting the Specifications. As requested, the Contractor shall also submit data relating to the materials and equipment he proposes to incorporate into the Work in sufficient detail to enable the Architect to identify and evaluate the particular product and to determine whether it conforms to the Contract requirements. Such data shall be submitted in a manner similar to that specified for submission of shop and working drawings.

Facilities and labor for storage, handling, and inspection of all materials and equipment, shall be furnished by the Contractor. Defective materials and equipment shall be removed immediately from the site of the Work.

If the Architect so requires, either prior to or after commencement of the Work, the Contractor shall submit samples of materials for such special tests as the Architect deems necessary to demonstrate that they conform to the Specifications. Such samples, including concrete test cylinders, shall be furnished, taken, stored, packed, and shipped by the Contractor as directed. The Contractor shall furnish suitable molds for making concrete test cylinders. Except as otherwise expressly specified, the Owner representatives shall make arrangements for, and pay for, the tests.

All samples shall be packed so as to reach their destination in good condition, and shall be labeled to indicate the material represented, the name of the building or work and location for which the material is intended, and the name of the Contractor submitting the sample. To ensure consideration of samples, the Contractor shall notify the Architect by letter that the samples have been shipped and shall properly describe the samples in the letter. The letter of notification shall be sent separate from and should not be enclosed with the samples.

The Contractor shall submit data and samples, or place his orders, sufficiently early to permit consideration, inspection and testing before the materials and equipment are needed for incorporation in the Work. The consequences of his failure to do so shall be the Contractor's sole responsibility.

In order to demonstrate the proficiency of workmen, or to facilitate the choice among several textures, types, finishes, surfaces, etc., the Contractor shall provide such samples of workmanship of wall, floor, finish, etc., as may be required.

When required, the Contractor shall furnish to the Architect triplicate sworn copies of manufacturer's shop or mill tests (or reports from independent testing laboratories) relative to materials, equipment performance ratings, and concrete data.

After review of the samples, data, etc., the materials and equipment used on the Work shall in all respects conform therewith.

5. INSPECTION OF WORK AWAY FROM THE SITE

If work to be done away from the construction site is to be inspected on behalf of the Owner representatives during its fabrication, manufacture, or testing, or before shipment, the Contractor shall give notice to the Architect of the place and time where such fabrication, manufacture, testing, or shipping is to be done. Such notice shall be in writing and delivered to the Architect in ample time so that the necessary arrangements for the

inspection can be made.

6. CONTRACTOR'S SHOP AND WORKING DRAWINGS

The Contractor shall submit (in reproducible transparency form unless otherwise specified) shop and working drawings of concrete reinforcement, structural details, piping layout, wiring, materials fabricated especially for the Contract, and materials and equipment for which such drawings are specifically requested.

Such drawings shall show the principal dimensions, weight, structural and operating features, space required, clearances, type and/or brand of finish or shop coat, grease fittings, etc., depending on the subject of the drawing. When it is customary to do so, when the dimensions are of particular importance, or when so specified, the drawings shall be certified by the manufacturer or fabricator as correct for the Contract.

When so specified or if considered by the Architect to be acceptable manufacturer's specifications, catalog data, descriptive matter, illustrations, etc., may be submitted in place of shop and working drawings. In such case the requirements shall be as specified for shop and working drawings, insofar as applicable, except that the submission shall be in quadruplicate.

The Contractor shall be responsible for the prompt and timely submittal of all shop and working drawings so that there shall be no delay to the Work due to the absence of such drawings. Prior to the submittal of any shop drawings, the Contractor shall submit a schedule of proposed shop drawing transmittals. The schedule shall identify the subject matter of each transmittal the corresponding specification section number and the proposed date of submission. During the progress of the Work the schedule shall be revised and resubmitted as necessary.

No material or equipment shall be purchased or fabricated especially for the Contract until the required shop and working drawings have been submitted as herein above provided and reviewed for conformance to the Contract requirements. All such materials and equipment and the work involved in their installation or incorporation into the Work shall then be as shown in and represented by said drawings.

Until the necessary review has been made, the Contractor shall not proceed with any portion of the Work (such as the construction of foundations), the design or details of which are dependent upon the design or details of work, materials, equipment or other features for which review is required.

All shop and working drawings shall be submitted to the Architect by and/or through the Contractor, who shall be responsible for obtaining shop and working drawings from his subcontractors and returning reviewed drawings to them. All shop and working drawings shall be prepared on standard size, 24-in. by 36-in. sheets, except for those made by changing the existing standard shop or working drawings. All drawings shall be clearly marked with the names of the Owner representatives, Contractor, and building, equipment, or structure to which the drawing applies, and shall be suitably numbered. Each shipment of drawings shall be accompanied by a letter of transmittal giving a list of the drawing numbers and the names mentioned above.

Only drawings which have been checked and corrected by the fabricator, should be submitted to the Contractor by his subcontractors and vendors. Prior to submitting drawings to the Architect, the Contractor shall check thoroughly all such drawings to satisfy him-self, that the subject matter thereof conforms to the Drawings and Specifications in all respects. All drawings, which are correct, shall be marked with the date, checker's name, and indication of the Contractor's approval, and then shall be submitted to the Architect; other drawings shall be returned for correction.

If a shop drawing shows any deviation from the Contract requirements, the Contractor shall make specific mention of the deviations in his letter of transmittal.

The review of shop and working drawings hereunder will be general only, and nothing contained in this GENERAL SPECIFICATION shall relieve, diminish or alter in any respect the responsibilities of the Contractor under the Contract Documents and in particular, the specific responsibility of the Contractor for details of design and dimensions necessary for proper fitting and construction of the work as required by the Contract and for achieving the result and performance specified thereunder.

Should the Contractor submit equipment that requires modifications to the structures, piping, electrical conduit, wires and appurtenances, layout, etc., detailed on the Drawings, he shall also submit details of the proposed modifications. If such equipment and modifications are accepted, the Contractor, at no additional cost to the Owner representatives, shall do all work necessary to make such modifications.

The marked-up reproducible of the shop and working drawings or one marked-up copy of catalog cuts will be returned to the Contractor. The Contractor shall furnish additional copies of such drawings or catalog cuts when so requested.

7. OCCUPYING PRIVATE LAND

The Contractor shall not (except after written consent from the proper parties) enter or occupy with men, tools, materials, or equipment, any land outside the rights-of-way or property of the Owner representatives. A copy of the written consent shall be given to the Architect.

INTERFERENCE WITH AND PROTECTION OF STREETS

The Contractor shall not close or obstruct any portion of a street, road, or private way without obtaining permits therefor from the proper authorities. If any street, road or private way shall be rendered unsafe by the Contractor's operations, he shall make such repairs or provide such temporary ways or guards as shall be acceptable to the proper authorities.

Streets, roads, private ways, and sidewalks, not closed, shall be maintained passable and safe by the Contractor, who shall assume and have full responsibility for the adequacy and safety of provisions made therefor.

The Contractor shall, at least 24 hours in advance, notify the Police and Fire Departments in writing, with a copy to the Architect, if the closure of a street or road is necessary. He shall cooperate with the Police Department in the establishment of alternate routes and shall provide adequate detour signs, plainly marked and well lighted, in order to minimize confusion.

STORAGE OF MATERIALS AND EQUIPMENT

All excavated materials and equipment to be incorporated in the Work shall be placed so as not to injure any part of the Work or existing facilities and so that free access can be had at all times to all parts of the Work and to all public utility installations in the vicinity of the Work. Materials and equipment shall be kept neatly piled and compactly stored in such locations as will cause a minimum of inconvenience to public travel and adjoining owner representativess, tenants and occupants.

10. SAFETY

The Contractor shall take all necessary precautions and provide all necessary safeguards to prevent personal injury and property damage. The Contractor shall provide protection for all persons including but not limited to his employees and employees of other contractors or subcontractors; members of the public; and employees, agents, and representatives of the Owner representatives, the Architect, and regulatory agencies that may be on or about the Work. The Contractor shall provide protection for all public and private property including but not limited to structures, pipes, and utilities, above and below ground.

The Contractor shall provide and maintain all necessary safety equipment such as fences, barriers, signs, lights, walkways, guards and fire prevention and fire-fighting equipment and shall take such other action as is required to fulfill his obligations under this subsection.

The Contractor shall comply with all applicable Federal, State and local laws, ordinances, rules and regulations and lawful orders of all authorities having jurisdiction for the safety of persons and protection of property.

The Contractor shall designate a responsible member of his organization at the site whose duty shall be the prevention of accidents. This responsible person shall have the authority to take immediate action to correct unsafe or hazardous conditions and to enforce safety precautions and programs.

11. SANITARY REGULATIONS

The Contractor shall provide adequate sanitary facilities for the use of those employed on the Work. Such facilities shall be made available when the first employees arrive on the site of the Work, shall be properly secluded from public observation, and shall be constructed and maintained during the progress of the Work in suitable numbers and at such points and in such manner as may be required.

The Contractor shall maintain the sanitary facilities in a satisfactory and sanitary condition at all times and shall enforce their use. He shall rigorously prohibit the committing of nuisances on the site of the Work, on the lands of the Owner representatives, or on adjacent property.

12. LINES, GRADES AND MEASUREMENTS

The Contractor shall employ a competent civil Architect, registered within Puerto Rico as a Professional Architect or Land Surveyor. The Contractor shall require said Architect to establish all lines, elevations, reference marks, batter boards, etc., needed by the Contractor during the progress of the Work, and from time to time to verify such marks by instrument or other appropriate means.

The Architect shall be permitted at all times to check the lines, elevations, reference marks, batter boards, etc., set by the Contractor, who shall correct any errors in lines, elevations, reference marks, batter boards, etc., disclosed by such check. Such a check shall not be construed to be an approval of the Contractor's work and shall not relieve or diminish in any way the responsibility of the Contractor for the accurate and satisfactory construction and completion of the entire Work.

The Contractor shall make, check, and be responsible for all measurements and dimensions necessary for the proper construction of and the prevention of misfittings in the Work.

13. DIMENSIONS OF EXISTING STRUCTURES

Where the dimensions and locations of existing structures are of importance in the installation or connection of any part of the Work, the Contractor shall verify such dimensions and locations in the field before the fabrication of any material or equipment which is dependent on the correctness of such

information.

14. WORK TO CONFORM

During its progress and on its completion, the Work shall conform truly to the lines, levels, and grades indicated on the Drawings or given by the Architect and shall be built in a thoroughly substantial and skillfully and competent manner, in strict accordance with the Drawings, Specifications, and other Contract Documents and the directions given from time to time by the Architect.

All work done without instructions having been given therefor by the Architect, without proper lines or levels, or performed during the absence of the Architect, will not be estimated or paid for except when such work is authorized by the Architect in writing. Work so done may be ordered uncovered or taken down, removed, and replaced at the Contractor's expense.

15. PIPE LOCATION

Exterior pipelines will be located substantially as indicated on the Drawings, but the right is reserved to the Owner representatives, acting through the Architect, to make such modifications in location as may be found desirable to avoid interference with existing structures or for other reasons. Where fittings, etc., are noted on the Drawings, such notation is for the Contractor's convenience and does not relieve him from laying and jointing different or additional items where required.

Small interior piping is indicated diagrammatically on the Drawings, and the exact location is to be determined in the field. Piping shall be arranged in a neat, compact, and skillfully and competent manner, with a minimum of crossing and interlacing, so as not to interfere with equipment or access ways, and, in general, without diagonal runs.

16. PLANNING AND PROGRESS SCHEDULES

Before starting the Work and from time to time during its progress, as the Architect may request, the Contractor shall submit to the Architect a written description of the methods he plans to use in doing the Work and the various steps he intends to take.

Within 15 days after the date of formal execution of the AGREEMENT, the Contractor shall prepare and submit to the Architect (a) a written schedule fixing the dates on which additional drawings, if any, will be needed by the Contractor and (b) a written schedule fixing the respective dates for the start and completion of various parts of the Work. Each such schedule shall be subject to review from time to time during the progress of the Work.

17. PRECAUTIONS DURING ADVERSE WEATHER

During adverse weather and against the possibility thereof, the Contractor shall take all necessary precautions so that the Work may be properly done and satisfactory in all respects. When required, protection shall be provided by use of tarpaulins, wood and building-paper shelters, or other suitable means.

During cold weather, materials shall be preheated if required, and the materials and adjacent structure into which they are to be incorporated shall be made and kept sufficiently warm so that a proper bond will take place and a proper curing, aging, or drying will result. Protected spaces shall be artificially heated by suitable means, which will result in a moist or a dry atmosphere according to the particular requirements of the work being protected. Ingredients for concrete and mortar shall be sufficiently heated so that the mixture will be warm throughout when used.

20. ELECTRICAL ENERGY

The Contractor shall make all necessary applications and arrangements and pay all fees and charges for electrical energy for power and light necessary for the proper completion of the Work and during its entire progress. The Contractor shall provide and pay for all temporary wiring, switches, connections, and meters.

The Contractor shall provide sufficient electric lighting so that all work may be done in a skillfully and competent manner when there is not sufficient daylight.

24. CUTTING AND PATCHING

The Contractor shall not cut or alter the work of any subcontractor or any other contractor, nor permit any of his subcontractors to cut or alter the work of any other contractor or subcontractor, except with the written consent of the contractor or subcontractor whose work is to be cut or altered with the written consent of the Architect. All cutting and patching or repairing made necessary by the negligence, carelessness, or incompetence of the Contractor or any of his subcontractors shall be done by or at the expense of the Contractor and shall be the responsibility of the Contractor.

* * *

DIVISION 1 – GENERAL REQUIREMENTS

SECTION 01 31 00 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. General project coordination procedures.
 - 2. Coordination Drawings.
 - 3. Administrative and supervisory personnel.
 - 4. Project meetings.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 1 Section "Construction Progress Documentation" for preparing and submitting the Contractor's Construction Schedule.
 - 2. Division 1 Section "Execution Requirements" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
 - 3. Division 1 Section "Closeout Procedures" for coordinating Contract closeout.

1.3 COORDINATION

- A. Coordination: Coordinate construction operations included in various Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.

- 2. Coordinate installation of different components with other contractors to ensure maximum accessibility for required maintenance, service, and repair.
- 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. If necessary, prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
 - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
 - 1. Preparation of Contractor's Construction Schedule.
 - 2. Preparation of the Schedule of Values.
 - 3. Installation and removal of temporary facilities and controls.
 - 4. Delivery and processing of submittals.
 - 5. Progress meetings.
 - 6. Preinstallation conferences.
 - 7. Project closeout activities.

1.4 SUBMITTALS

- A. Coordination Drawings: Prepare Coordination Drawings if limited space availability necessitates maximum utilization of space for efficient installation of different components or if coordination is required for installation of products and materials fabricated by separate entities.
 - 1. Indicate relationship of components shown on separate Shop Drawings.
 - 2. Indicate required installation sequences.
 - 3. Refer to Division 23 "Heating, Ventilating and Air-Condition" and Division 26 Section 26 00 00 "Basic Electrical Materials and Methods" for specific Coordination Drawing requirements for mechanical and electrical installations.
- B. Staff Names: Within 15 days of starting construction operations, submit a list of principal staff assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home and office telephone numbers. Provide names, addresses, and telephone numbers of individuals assigned as standbys in the absence of individuals assigned to Project.

1. Post copies of list in Project meeting room, in temporary field office, and by each temporary telephone.

1.5 ADMINISTRATIVE AND SUPERVISORY PERSONNEL

- A. General: In addition to Project superintendent, provide other administrative and supervisory personnel as required for proper performance of the Work.
 - 1. Include special personnel required for coordination of operations with other contractors.

1.6 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site, unless otherwise indicated.
 - 1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
 - 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
 - 3. Minutes: Record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within 3 days of the meeting.
- B. Preconstruction Conference: Schedule a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement. Hold the conference at Project site or another convenient location. Conduct the meeting to review responsibilities and personnel assignments.
 - Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; manufacturers; suppliers; and other concerned parties shall attend the conference. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 2. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Tentative construction schedule.
 - b. Phasing.
 - c. Critical work sequencing.
 - d. Sustainable products, processes, and documentation.
 - e. Designation of responsible personnel.
 - f. Procedures for processing field decisions and Change Orders.
 - g. Procedures for processing Applications for Payment.

- h. Distribution of the Contract Documents.
- i. Submittal procedures.
- j. Preparation of Record Documents.
- k. Use of the premises.
- I. Responsibility for temporary facilities and controls.
- m. Parking availability.
- n. Office, work, and storage areas.
- o. Equipment deliveries and priorities.
- p. First aid.
- q. Security.
- r. Progress cleaning.
- s. Working hours.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
 - Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
 - 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
 - a. Contract Documents.
 - b. Options.
 - c. Related Change Orders.
 - d. Purchases.
 - e. Deliveries.
 - f. Submittals.
 - g. Review of mockups.
 - h. Possible conflicts.
 - i. Compatibility problems.
 - j. Time schedules.
 - k. Weather limitations.
 - I. Manufacturer's written recommendations.
 - m. Warranty requirements.
 - n. Compatibility of materials.
 - o. Acceptability of substrates.
 - p. Temporary facilities and controls.
 - q. Space and access limitations.
 - r. Regulations of authorities having jurisdiction.
 - s. Testing and inspecting requirements.
 - t. Required performance results.
 - u. Protection of construction and personnel.

- Record significant conference discussions, agreements, and disagreements.
- 4. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Progress Meetings: Conduct progress meetings at regular intervals. Coordinate dates of meetings with preparation of payment requests.
 - Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's Construction Schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - Status of submittals.
 - 4) Status of recycling and waste disposal.
 - 5) Deliveries.
 - 6) Off-site fabrication.
 - 7) Access.
 - 8) Site utilization.
 - 9) Temporary facilities and controls.
 - 10) Work hours.
 - 11) Hazards and risks.
 - 12) Progress cleaning.
 - 13) Quality and work standards.
 - 14) Change Orders.
 - 15) Documentation of information for payment requests.

- 3. Reporting: Distribute minutes of the meeting to each party present and to parties who should have been present. Include a brief summary, in narrative form, of progress since the previous meeting and report.
 - a. Schedule Updating: Revise Contractor's Construction Schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 31 00

DIVISION 1 – GENERAL REQUIREMENTS

SECTION 01 33 00 - SUBMITTALS PROCEDURES

PART 1 GENERAL

1.1 SUBMITTAL FORM AND LOG

- A. The Contractor shall use the submittal form and log at the end of this section or use alternates acceptable to the Owner.
- B. Architect will return submittals without processing if they do not contain Contractor's stamp, if they are not initialed or signed by authorized person, if they are not dated, or if it becomes evident that they have not been properly reviewed. Delays resulting there from are the responsibility of the Contractor.
- C. Contractor shall maintain in field office a copy of submittal schedule and log of submittals indicating current status of each item.
- D. Contractor shall allot time in construction scheduling for liaison with Architect for review of submittals. Except for special submittals, such as those with design calculations and/or detailed shop drawings, submittals will be reviewed in an average time of ten (10) working days.

1.2 REQUEST FOR INFORMATION (RFI) FORM AND LOG

- A. The Contractor shall use the RFI form at the end of this section or use an alternate form acceptable to the Owner.
- B. Contractor shall carefully study and compare Contract Documents before proceeding with fabrication and installation of Work. Promptly advise Architect of any error, inconsistency, omission, or apparent discrepancy discovered.
- C. Contractor shall allot time in construction scheduling for liaison with Architect for handling queries and clarifications.
- D. If Architect is able to respond to a request for information by making specific reference to Drawing sheet or Specification Section, the Owner retains the right to require the Contractor to reimburse Owner for charges of Architect and Architect's Consultants for performing review services for the Contractor.
- E. Contractor shall maintain in field office a copy of the log of RFIs indicating current status of each item.

1.3 SHOP DRAWINGS

A. Contractor shall bind in complete sets. Transmit reproducible transparencies in roll form to eliminate folding. Folding of prints is acceptable.

- B. Contractor shall allot time in construction scheduling for liaison with Architect for review of shop drawings. Except for special submittals, such as those with design calculations and/or detailed shop drawings, submittals will be reviewed in an average time of ten (10) working days.
- C. Contractor shall present in clear and thorough manner. Title each drawing with Project name and number; identify each element of drawings by reference to sheet number and detail, schedule, or room number of Contract Documents.
- D. Contractor shall show detail, materials, dimensions, thickness, methods of assembly, attachments, relation to adjoining work, and other pertinent data and information.
- E. Contractor shall verify dimensions and field conditions. Clearly indicate field dimensions and field conditions.
- F. Contractor shall not use Contract Drawings for shop drawings. Provide original shop drawings with changes from Contract Drawings clearly indicated.
- G. Identification: Place a permanent label or title block on each submittal for identification.
 - 1. Indicate name of firm or entity that prepared each submittal on label or title block.
 - Provide a space approximately 4 by 5 inches on label or beside title block to record Contractor's review and approval markings and action taken by Architect.
 - 3. Include the following information on label for processing and recording action taken:
 - A. Project name
 - B. Date
 - C. Name and address of Contractor
 - D. Name and address of supplier
 - E. Name of manufacturer
 - F. Unique identifier, including revision number
 - G. Drawing number and detail references, as appropriate
- H. Deviations: Highlight, encircle, or otherwise identify deviations from the Contract Documents on submittals.
- Transmittal: Package each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Architect will discard submittals received from sources other than Contractor.

1.4 PARTIAL SUBMITTALS

Architect will not review partial or incomplete submittals. Complete submittals for each item are required. Submittals will not be considered official until it is complete in every respect. Delays resulting from partial submittals are the responsibility of the Contractor.

1.5 RESUBMITTALS

- A. Make resubmittals under procedures specified for initial submittals; identify changes made since previous submittal.
- B. Architect will record time required to review resubmittals after original submittal and first resubmittal. Owner retains the right to require the Contractor to reimburse Owner for charges to Architect and Architect's Consultants for reviewing submittal more than 2 times.

1.6 DISTRIBUTION

- A. Duplicate and distribute reproductions of shop drawings, product data, samples, and other submittals which bear Architect's stamp of approval to the Project record documents file, the Project site file, subcontractors, suppliers, other affected contractors, and other entities requiring information.
- B. Provide each testing and inspection agency one set of approved submittals for their exclusive use in providing specified quality control testing and inspection services; refer to Section 01 40 00.
- C. The Owner is to receive two copies of all approved submittals, shop drawings and product data.

SUBMITTAL Contractor:	FORM (Submit sep	parate form for each	product) Project:	
TRANSMITT	A To: Contractor		_Date:	Submittal No:
L A	From: Subcontract	or	_By:	Resubmission 🗇
Quantity	Reference Number	Title/Description/ Manufacturer	Specification S Drawing Detail	ection Title, Paragraph / Reference
7 0 b	I for Day'r and Arra		7 0 b c c c	ale ale de O belli l'es Bressel
	d for Review and App tted for Review and A		Substitutio Attached	n Involved - Substitution Request
Complies	with Contract Requir	rements	If Substitut	ion involved, Submission
	ailable to meet const	ruction schedule construction schedule	includes full po	ont by parative data or Preliminary
	s on above submission		details	•
			Items inclusion ordered	ided in Submission will be
				ely upon receipt of approval
TRANSMITT	To: A/E - Attention			by Contractor:
В	From: Contractor _		_Date Transmitt	ed by Contractor:
Reviewed, Coordinated, and Approved by Contractor		submission:		One copy retained by sender
	A To: Contractor			Date Received:
c	From: A/E 🗖 Oth			Dated Returned:
□ Not subje□ SubmissiResubmit□ Received□ Full point data	I as noted ved / Resubmit ect to review on Incomplete; ; No Action Required by point comparative	Copy with corrections identified Reproducible copies only returned		pove submission:One copy retaine
process	to complete approval			
TRANSMITT	A To: Subcontractor			Date Received:
D	From: Contractor	Signed		Dated Returned:
Copies Remarks on a	☐ University above:			☐One copy retained by sen

Include GC Section 24 required stamp here

END OF SECTION

SECTION 01 50 00 TEMPORARY FACILITIES

1. GENERAL

The Contractor shall provide all temporary facilities necessary for the proper completion of the work, as necessary and as specified.

The Contractor's attention is directed to the requirements of the GENERAL SPECIFICATIONS specified under "Sanitary Regulations", "Precautions During Adverse Weather", and "Electrical Energy".

WATER SUPPLY

The Contractor shall make arrangements and pay for all water necessary for completion of construction operations under this contract.

PROJECT SIGN

The Contractor shall construct a sign having an area of approximately 96 sq. ft. identifying the project, officials representing the Owner representatives, the Architects, etc. The sign shall be erected in a location selected by the Architect. The Contractor shall maintain the sign throughout the duration of the project. The sign shall be worded as directed by the Architect. See sign details on drawing sheets inside the drawings.

4. CONTRACTOR'S FIELD OFFICE

The Contractor shall maintain a temporary field office near the work for his own use during the period of construction at which readily accessible copies of all contract documents shall be kept. The office shall be located where it will not interfere with the progress of the work. In charge of this office there shall be a competent superintendent of the Contractor as specified under "Supervision of Work" in the AGREEMENT.

OFFICE FOR ARCHITECT.

Promptly after starting work at the site, the Contractor shall provide and equip a suitable area in the Contractor's trailer (at least 100 sq. ft. of floor area) for the exclusive use of the Architect, and the Contractor shall maintain this office thereafter until the completion of the work to be done under this contract. The office for the Architect shall be a separate room which can be locked. A key to the trailer and the office for the Architect shall be furnished to the Architect.

The office, furniture, equipment, supplies and services necessary shall be satisfactory to the

Architect. The Contractor shall furnish the following furniture, equipment, supplies, and

services:

- One plan table or sloping plan shelf, about 3 ft. by 5 ft., with reasonable smooth top, and one suitable swivel stool.
- Two additional chairs.
- c. Four-drawer, legal size, vertical metal filing cabinet with lock

- d. Desk for general office use, about 2.5 ft. by 5 ft., with desk chair of the armchair swivel type.
- e. Telephone extension on desk.
- f. Calculating machine, electric or electronic.
- g. Air conditioning unit of adequate capacity to maintain a minimum temperature differential of 20 deg. F from ambient under the most serious conditions.
- h. Sanitary facility separate from, but in the immediate vicinity of the Architects office.
- i. Drinking water either through a refrigerated fountain connected to potable water supply or ice water furnished daily for the Architect office.

SECTION 01 71 00

CLEANING UP

1. GENERAL

During its progress the work and the adjacent areas affected thereby shall be kept cleaned up and all rubbish, surplus materials, and unneeded construction equipment shall be removed and all damage repaired so that the public and property owner representatives will be inconvenienced as little as possible.

Where material or debris has washed or flowed into or been placed in existing watercourses, ditches, gutters, drains, pipes structures, work done under this contract, or elsewhere during the course of the Contractor's operations, such material or debris shall be entirely removed and satisfactorily disposed of during the progress of the work, and the ditches, channels, drains, pipes, structures, and work, etc., shall, upon completion of the work, be left in a clean and neat condition.

On or before the completion of the work, the Contractor shall, unless otherwise especially directed or permitted in writing, tear down and remove all temporary buildings and structures built by him; shall remove all temporary works, tools, and machinery or other construction equipment furnished by him; shall remove, acceptably disinfect, and cover all organic matter and material containing organic matter in, under, and around privies, houses, and other buildings used by him; shall remove all rubbish from any grounds which he has occupied; and shall leave the roads and all parts of the premises and adjacent property affected by his operations in a neat and satisfactory condition.

The Contractor shall thoroughly clean all materials and equipment installed by him and his subcontractors, and on completion of the work shall deliver it undamaged and in fresh and new-appearing condition. All mechanical equipment shall be left fully charged with lubricant and ready for operation.

The Contractor shall restore or replace, when and as directed, any public or private property damaged by his work, equipment, or employees, to a condition at least equal to that existing immediately prior to the beginning of operations. To this end the Contractor shall do as required all necessary highway or driveway, walk, and landscaping work. Suitable materials, equipment, and methods shall be used for such restoration. The restoration of existing property or structures shall be done as promptly as practicable as work progresses and shall not be left until the end of the contract period.

* * *

DIVISION 1 – GENERAL REQUIREMENTS

SECTION 01 77 00 CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Inspection procedures.
 - 2. Project Record Documents.
 - 3. Operation and maintenance manuals.
 - 4. Warranties.
 - 5. Instruction of Owner's personnel.
 - Final cleaning.

B. Related Sections include the following:

- 1. Division 1 Section "Payment Procedures" for requirements for Applications for Payment for Substantial and Final Completion.
- 2. Division 1 Section "Construction Photographs" for submitting Final Completion construction photographs and negatives.
- 3. Division 1 Section "Execution Requirements" for progress cleaning of Project site.
- 4. Divisions 2 through 16 Sections for specific closeout and special cleaning requirements for products of those Sections.

1.3 SUBSTANTIAL COMPLETION

- A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request.
 - 1. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
 - 2. Advise Owner of pending insurance changeover requirements.

- 3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
- 4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
- 5. Prepare and submit Project Record Documents, operation and maintenance manuals, Final Completion construction photographs, damage or settlement surveys, property surveys, and similar final record information.
- 6. Deliver tools, spare parts, extra materials, and similar items to location designated by Owner. Label with manufacturer's name and model number where applicable.
- 7. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
- 8. Complete startup testing of systems.
- 9. Submit test/adjust/balance records.
- 10. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
- 11. Advise Owner of changeover in heat and other utilities.
- 12. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
- 13. Complete final cleaning requirements, including touchup painting.
- 14. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- B. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.
 - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
 - 2. Results of completed inspection will form the basis of requirements for Final Completion.

1.4 FINAL COMPLETION

- A. Preliminary Procedures: Before requesting final inspection for determining date of Final Completion, complete the following:
 - 1. Submit a final Application for Payment according to Division 1 Section "Payment Procedures."
 - 2. Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by

- Architect. The certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
- 3. Submit evidence of final, continuing insurance coverage complying with insurance requirements.
- 4. Submit pest-control final inspection report and warranty.
- 5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems.
- B. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
 - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.5 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Preparation: Submit three copies of list. Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
 - 1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor.
 - 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
 - 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Contractor.
 - e. Page number.

1.6 PROJECT RECORD DOCUMENTS

- A. General: Do not use Project Record Documents for construction purposes. Protect Project Record Documents from deterioration and loss. Provide access to Project Record Documents for Architect's reference during normal working hours.
- B. Record Drawings: Maintain and submit one set of blue- or black-line white prints of Contract Drawings and Shop Drawings.

- 1. Mark Record Prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to prepare the marked-up Record Prints.
 - a. Give particular attention to information on concealed elements that cannot be readily identified and recorded later.
 - b. Accurately record information in an understandable drawing technique.
 - c. Record data as soon as possible after obtaining it. Record and check the markup before enclosing concealed installations.
 - d. Mark Contract Drawings or Shop Drawings, whichever is most capable of showing actual physical conditions, completely and accurately. Where Shop Drawings are marked, show cross-reference on Contract Drawings.
- 2. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at the same location.
- 3. Mark important additional information that was either shown schematically or omitted from original Drawings.
- 4. Note Construction Change Directive numbers, Change Order numbers, alternate numbers, and similar identification where applicable.
- 5. Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location. Organize into manageable sets; bind each set with durable paper cover sheets. Include identification on cover sheets.
- C. Record Specifications: Submit one copy of Project's Specifications, including addenda and contract modifications. Mark copy to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
 - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 - 3. Note related Change Orders, Record Drawings, and Product Data, where applicable.
- D. Record Product Data: Submit one copy of each Product Data submittal. Mark one set to indicate the actual product installation where installation varies substantially from that indicated in Product Data.
 - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.

- 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
- 3. Note related Change Orders, Record Drawings, and Record Specifications, where applicable.
- E. Miscellaneous Record Submittals: Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.

1.7 OPERATION AND MAINTENANCE MANUALS

A. Assemble a complete set of operation and maintenance data indicating the operation and maintenance of each system, subsystem, and piece of equipment not part of a system. Include operation and maintenance data required in individual Specification Sections and as follows:

1. Operation Data:

- a. Emergency instructions and procedures.
- b. System, subsystem, and equipment descriptions, including operating standards.
- c. Operating procedures, including startup, shutdown, seasonal, and weekend operations.
- d. Description of controls and sequence of operations.
- e. Piping diagrams.

2. Maintenance Data:

- a. Manufacturer's information, including list of spare parts.
- b. Name, address, and telephone number of Installer or supplier.
- c. Maintenance procedures.
- d. Maintenance and service schedules for preventive and routine maintenance.
- e. Maintenance record forms.
- f. Sources of spare parts and maintenance materials.
- g. Copies of maintenance service agreements.
- h. Copies of warranties and bonds.
- B. Organize operation and maintenance manuals into suitable sets of manageable size. Bind and index data in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, with pocket inside the covers to receive folded oversized sheets. Identify each binder on front and spine with the printed title "OPERATION AND MAINTENANCE MANUAL," Project name, and subject matter of contents.

1.8 WARRANTIES

- A. Submittal Time: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated.
- B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.
- C. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
 - 1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
 - 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
 - 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
- D. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 DEMONSTRATION AND TRAINING

A. Instruction: Instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.

- 1. Provide instructors experienced in operation and maintenance procedures. Incorporate nontoxic cleaning methods and sustainable maintenance.
- 2. Provide instruction at mutually agreed-on times. For equipment that requires seasonal operation, provide similar instruction at the start of each season.
- 3. Schedule training with Owner, through Architect, with at least seven days' advance notice.
- 4. Coordinate instructors, including providing notification of dates, times, length of instruction, and course content.
- B. Program Structure: Develop an instruction program that includes individual training modules for each system and equipment not part of a system, as required by individual Specification Sections. For each training module, develop a learning objective and teaching outline. Include instruction for the following:
 - 1. System design and operational philosophy.
 - 2. Review of documentation.
 - 3. Operations.
 - 4. Adjustments.
 - 5. Troubleshooting.
 - 6. Maintenance.
 - 7. Repair.
 - 8. Recycling.

3.2 FINAL CLEANING

- A. General: Provide final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and anti-pollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.

- c. Rake grounds that are neither planted nor paved to a smooth, eventextured surface.
- d. Remove tools, construction equipment, machinery, and surplus material from Project site.
- e. Remove snow and ice to provide safe access to building.
- f. Clean exposed exterior and interior hard-surfaced finishes to a dirtfree condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
- g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
- h. Sweep concrete floors broom clean in unoccupied spaces.
- i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; shampoo if visible soil or stains remain.
- j. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, visionobscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
- k. Remove labels that are not permanent.
- Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.
 - 1) Do not paint over "UL" and similar labels, including mechanical and electrical nameplates.
- m. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
- n. Replace parts subject to unusual operating conditions.
- o. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
- p. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
- q. Clean ducts, blowers, and coils if units were operated without filters during construction.
- r. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burned-out bulbs, and those noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.
- s. Leave Project clean and ready for occupancy.
- C. Comply with safety and environmental standards for cleaning. Do not burn waste materials. Do not bury debris or excess materials on Owner's property.

Do not discharge volatile, harmful, or dangerous materials into drainage systems. Remove waste materials from Project site and dispose of lawfully. Use non-toxic and low-VOC cleaning products to the extent possible while complying with manufacturer's recommendations.

END OF SECTION

PART 2 - PRODUCTS

2.1 INSECTICIDE SOLUTIONS

- A. General: Use an insecticide, specially formulated to prevent insect infestation. Submit Manufacturer's Label, material Safety Data Sheet and certification of compliance & approval of Local, State and Federal Agencies having jurisdiction.
- B. Products: Subject to Owner's approval, Submit proposed list with all relating documents for approval.
- C. Mix chemicals to concentration level recommended by manufacturer.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Crack and Crevice Treatment:
 - 1. Insecticides are o be applied to crack and crevices only, unless otherwise allowed by label instructions for specific circumstances, ie. void treatment.
- B. Spot and Space Treatment:
 - 1. Areas, such as voids and perimeters may be treated as label allows. Use only those insecticides labeled for this purpose.
- C. Application Rates: Apply insecticides according to label specifications.

PART 4 - RODENTS

4.1 RODENTICIDES

- A. Use only those rodenticides specifically formulated to control rodents in structures.
- B. Submit all label data and msds sheets for rodenticides to be used.

4.2 APPLICATION

A. Rodenticides are to be placed within water resistant, tamperproof bait stations.

END OF SECTION

SECTION 02 05 00 DEMOLITION AND ALTERATIONS

PART 1 - GENERAL

1.01 DESCRIPTION:

 Demolition and alterations of existing facilities as indicated on drawings, as specified and directed by Architect.

1.02 QUALITY ASSURANCE:

- A. Accomplish demolition and removal of existing construction, utilities, equipment, and appurtenances without damaging integrity of existing structures, equipment, and appurtenances that are to remain.
- B. Store equipment to be salvaged for relocation where directed by Architect, and if necessary, protect from damage during work.
- C. Repair or remove items that are damaged. Repair and installation of damaged items at no additional compensation and to condition at least equal to that which existed prior to start of work.
- D. Exercise all necessary precautions for fire prevention. Acceptable fire extinguishers made available at all times in areas where demolition work by burning torches is being done. Burning of demolition debris not permitted on or near site.
- E. Provide protection of persons and property throughout progress of work. Proceed in such manner as to minimize spread of dust and flying particles and to provide safe working conditions for personnel.
- F. Maintain circulation of traffic within area at all times during demolition operations.
- G. Obtain permission from Architect before abandoning or removing any existing structures, materials, equipment and appurtenances.
- H. Arrange with and perform work required by utility companies and municipal departments for discontinuance or interruption of utility services due to demolition work.

1.03 SUBMITTALS:

Submit demolition plan to Architect for review, describing proposed sequence, methods, and equipment for demolition and disposal of each structure.

PART 2 - PRODUCTS (NOT

APPLICABLE) PART 3 -

EXECUTION

3.01 DEMOLITION:

- A. Confine apparatus, storage of material, demolition work, new construction, and operations of workmen to areas that will not interfere with continued use and operation of entire facility. Provide and maintain lights, barriers, and temporary passageways for free and safe access.
- B. Wet down work during demolition operations to prevent dust from arising. Provide maximum practicable protection from inclement weather for materials, equipment, and personnel located in partially dismantled structures. Provide shoring or bracing where necessary to prevent settlement or displacement of existing or new structures. Do not overload floors. Complete demolition work on upper levels before disturbing supporting members on lower levels.

3.02 SALVAGE:

A. Materials, equipment, and appurtenances removed, that are not designated for relocation, become property of Contractor and hauled from site and disposed of at no additional compensation.

* * *



Asbestos Containing Building Materials Inspection Report

Project:

El Cortijo, Km 18.5, C. PR-162 Barranquitas, Puerto Rico



Client: Arquiteg – Architects & Planners

ZEM-22225December 2022

Prepared By:

Zimmetry Environmental Management, Corp. www.zimmetry.com info@zimmetry.com

ZIMMETRY ENVIRONMENTAL MANAGEMENT CORP.
Asbestos Containing Materials Inspection
El Cortijo,
Barranquitas, Puerto Rico
Project No. ZEM-22225

TABLE OF CONTENT

SECTION	1: Executive Summary	1
1.1	Introduction	1
1.2	Summary of Property Evaluation	1
SECTION	2: Asbestos Containing Building Materials Inspection Report	2
2.1	Overview of the Evaluation	2
2.2	Conditions and Limitations	2
2.3	Environmental Assessment Report Certification	3
SECTION	3: Appendices	4
App	endix A: Certifications, Licenses, and Accreditations	5
App	endix B: Certification of No Presence of Asbestos (Form PGC-009)	6

SECTION 1: EXECUTIVE SUMMARY

1.1 INTRODUCTION

An Asbestos Containing Building Materials (ACBM) inspection was conducted on December 9, 2022 at El Cortijo, located in Km 18.5, C. PR-162 at the municipality of Barranquitas, Puerto Rico. The asbestos containing building materials sampling was performed to identify material that contains asbestos fibers above allowable levels and to assist with the compliance of local, state and federal regulations.

1.2 SUMMARY OF PROPERTY EVALUATION

The project consisted in the evaluation of the areas of the aforementioned property. The evaluation found that **no** asbestos containing materials were identified during the inspection of the areas.

SECTION 2: ASBESTOS CONTAINING MATERIALS SURVEY REPORT

2.1 OVERVIEW OF THE EVALUATION

This asbestos containing materials (ACM) survey is an inspection to identify the location of any ACM that exist within. Throughout the inspection no asbestos containing materials were identified at the assessed areas.

The inspection was conducted by the Department of Natural and Environmental Resources (DRNA) of Puerto Rico and United States Environmental Protection Agency (USEPA) accredited Inspectors qualified by experience, education and training in the recognition of potential ACM and approved bulk sampling techniques. Some areas may not have been directly accessible due to the physical hazards encountered within. In these areas, assumptions based on findings in other areas were made whenever possible. These assumptions are duly noted as such in this report.

The inspection was performed in accordance with Environmental Protection Agency recommended procedures found in EPA-450/2-78-014 (Parts I and II), EPA 560/5-85-024, and 40 CFR 763. These procedures call for the visual inspection of the building for suspect friable material and collection and analysis of representative samples of suspect material.

2.2 CONDITIONS AND LIMITATIONS—DISCLAIMER

Zimmetry Environmental Management Corp. has performed this asbestos containing building materials inspection in a thorough and professional manner consistent with commonly accepted industry standards. The Preparer cannot guarantee and does not warrant that this evaluation has identified all adverse environmental factors and/or conditions affecting this property on the date of the evaluation.

The results reported and conclusions reached by the Preparer are solely for the benefit of the Owner and occupants. The results and opinions in this report, based solely on the conditions found at the property on the date of the evaluation, are valid only on that date. The Preparer assumes no obligation to advise the client of any changes in any real or potential asbestos hazards at this structure beyond the date of the property evaluation.

The Asbestos Containing Building Materials inspection was performed to ready accessible components and surfaces. If suspected components that could contain asbestos are encountered, they shall be managed as containing asbestos until the appropriate laboratory analysis is performed.

ZIMMETRY ENVIRONMENTAL MANAGEMENT CORP.
Asbestos Containing Materials Inspection
El Cortijo,
Barranquitas, Puerto Rico
Project No. ZEM-22225

2.3 ENVIRONMENTAL ASSESSMENT REPORT CERTIFICATION

Zimmetry Environmental Management Corp. has performed this asbestos containing building materials inspection in a thorough and professional manner consistent with commonly accepted industry standards. The inspection was conducted on December 9, 2022 by Isamar Rivera, state-certified inspector ASB-0822-0285-SI, qualified by experience, education and training in the recognition of asbestos containing materials and approved sampling techniques.

Isamar Rivera, MSEM

Environmental Asbestos Inspector

SECTION 3: APPENDICES

Appendix A: Certifications, Licenses, and Accreditations

Appendix B: Certification of No Presence of Asbestos (Form PGC-009)

Barranquitas, Puerto Rico Project No. ZEM-22225

APPENDIX A: CERTIFICATIONS, LICENSES, AND ACCREDITATIONS



ASB-0822-0285-SI Número de Registro 31-jul-2023

Fecha de vencimiento

TARJETA DE REGISTRO PARA LA REMOCION DE ASBESTO

Esta tarjeta autoriza a:

Isamar Rivera Lugo

Inspector

A trabajar en la remoción de asbesto en P.R. Esta persona NO es un empleado del DRNA.

Firma Autorizada - Departamento Recursos Naturales y Ambientales

ZIMMETRY ENVIRONMENTAL MANAGEMENT CORP.
Asbestos Containing Materials Inspection
El Cortijo,
Barranquitas, Puerto Rico
Project No. ZEM-22225

APPENDIX B: CERTIFICATION OF NO PRESENCE OF ASBESTOS (FORM PGC-009)



GOBIERNO DE PUERTO RICO OFICINA DEL GOBERNADOR JUNTA DE CALIDAD AMBIENTAL



PGC-

Área de Calidad de Agua

Forma PGC-009

CERTIFICACION DE NO PRESENCIA DE ASBESTO EN ESTRUCTURAS A DEMOLERSE

(Deberá completarse en letra de molde o impresa)

	PARA USO OFICIAL
Yo, Isamar Rivera , mayor de edad, <u>casada</u> , y vecino de (Nombre) (Estado Civil)	leBayamón (Municipio)
Dirección Postal PO Box 3545 Bayamón 00958 (Pueblo) (Zip Code)	
Teléfonos: Residencial (<u>787</u>) <u>550</u> - <u>2061</u> Oficina (<u>787</u>) <u>995</u> - <u>00</u>	005 Ext
Certifico que:	
La estructura localizada en <u>Restauration of El Cortijo, located in Km 18.5, Cortigo, located in K</u>	C, la cual será objeto de una rto Rico
La información antes indicada es cierta y correcta.	
3. Afirmo y reconozco las consecuencias de incluir y someter información falsa en	este documento.
4. Para que así conste, firmo la presente certificación en Bayamón hoy día 29 de diciembre de 2022	de Puerto Rico,
Firma y Sello del Profesional o Firma del Inspector de Asbesto registrado por la JCA (Original)

Nota: Ingenieros o Arquitectos deberán someter evidencia de que se encuentra al día en el pago de sus cuotas de colegiación e Inspectores de Asbesto deberán someter evidencia de la tarjeta de registro provista por la JCA.

Dirección Física: Ave. Ponce de León 1308, Carr. Estatal 8838, Sector el Cinco, Río Piedras, PR 00926

Dirección Postal: Apartado 11488, Santurce, PR 00910-1488

Tel. (787) 767-8181 • Fax (787) 767-1962



CERTIFICATION



ASB-0822-0285-SI Número de Registro 31-jul-2023

Fecha de vencimiento

TARJETA DE REGISTRO PARA LA REMOCION DE ASBESTO

Esta tarjeta autoriza a:

Isamar Rivera Lugo

Inspector

A trabajar en la remoción de asbesto en P.R. Esta persona NO es un empleado del DRNA.

Firma Autorizada - Departamento Recursos Naturales y Ambientales



Lead Based Paint Inspection Report

Project:

El Cortijo, Km 18.5, C. PR-162 Barranquitas, Puerto Rico



Client: Arquiteg – Architects & Planners

ZEM-22225December 2022

Prepared By:

Zimmetry Environmental Management, Corp. www.zimmetry.com info@zimmetry.com

TABLE OF CONTENT

SECTION :	1: EXECUTIVE SUMMARY1
1.1	Introduction1
1.2	Summary of Property Evaluation1
1.3	Property Locations of Building Components with Lead Based Paint1
Table	1-1 Summary of Building Components with Lead Based Paint2
SECTION 2	2: LEAD-BASED PAINT INSPECTION REPORT6
2.1	Overview of the Evaluation6
2.2	Sampling Procedure
2.3	Results Presentation
	2.3.1 Specific Findings
	2.3.2 Homogeneous Areas with Special Considerations
	2.3.3 Inaccessible Areas Presumed to be Lead-Based Painted
2.4	Lead Regulatory Levels8
2.5	Conditions and Limitations8
2.6	Abatement Conditions8
2.7	Recommendations9
2.8	Environmental Assessment Report Certification9
SECTION :	3: APPENDICES10
Appei	ndix A: Certifications, Licenses, and Accreditations11
Appei	ndix B: XRF Sampling Data14
Appei	ndix C: XRF's Performance Characteristics Sheet24
Appei	ndix D: Photographic Record28
Appei	ndix E: Location of Positive Materials80

SECTION 1: EXECUTIVE SUMMARY

1.1 INTRODUCTION

A Lead-Based Paint inspection was conducted on December 9, 2022 at El Cortijo, located in Km 18.5, C. PR-162 at the municipality of Barranquitas, Puerto Rico. The lead-based paint inspection was performed to identify paint that contains lead above allowable levels and to assist with the compliance of local, state and federal regulations.

1.2 SUMMARY OF PROPERTY EVALUATION

The project consisted of the evaluation of the interior and exterior areas of the aforementioned property. The evaluation found that lead based paint was present in selective components and surfaces through the property on the date of the inspection. Table 1-1 identifies the components positive for lead. Table 2-1 identifies lead-based paint as defined by the U.S. Environmental Protection Agency (EPA) and the Department of Natural and Environmental Resources (DRNA) of Puerto Rico. For specific locations and additional detail on the location of lead-reference Sections 2 and 3.

1.3 PROPERTY LOCATIONS OF BUILDING COMPONENTS WITH LEAD-BASED PAINT

Table 1-1 summarizes the site components and surfaces coated with lead-based paint. Details that identify positive lead-based paint findings within specific areas and on surfaces were provided in the lead-based paint inspection report. The "substrate" is the building component material directly beneath the painted surface. Photographic documentation is for reference purposes and doesn't necessarily include all the surfaces with lead-based paint and/or components containing lead. The quantification of positives materials presented in this table is only an estimate. If an abatement of the materials will be conducted, the Contractors shall estimate the amount of materials to be abated.

If homogeneous materials that were not accounted for are identified in areas that are not describe in this report or inaccessible areas described in Section 2.3.3, they shall be managed as containing lead. If suspected components that could contain lead are encountered underneath current installed tiles or other construction material, they shall be managed as containing lead until the appropriate test is performed. Refer to Appendix E: Location of Positive Materials for specific location.

Tal	ole 1-1: Summary o	f Components C	ontaining Lead	
Area	Component	Color	Substrate	Approximate Amount
	Wall Surfaces	White	Concrete	468 Ft ²
4-1	Ceiling	White	Concrete	169 Ft ²
4-1	Curb	White	Concrete	10 Ft ²
	Railing Cap	Black	Metal	1 Unit
Doloony	Wall Surfaces	White	Concrete	225 Ft ²
Balcony -	Railing Cap	Black	Metal	1 Unit
Stairway 4 th Floor - 3 rd Floor	Wall Surfaces	White	Concrete	235 Ft ²
3 11001	Column	White	Concrete	50 Ft ²
2nd Elean Hellerer	Wall Surfaces	White	Concrete	118 Ft ²
3rd Floor Hallway	Ceiling	White	Concrete	33 Ft ²
3-1	Walls A & D	Cream	Concrete	161 Ft ²
3-1	Ceiling	Gray	Concrete	130 Ft ²
	Ceiling	White	Concrete	35 Ft ²
Stairway 3 rd Floor - 2 nd Floor	Wall Surfaces	White	Concrete	275 Ft ²
2 11001	Column	White	Concrete	55 Ft ²
	Partition	White	Concrete	40 Ft ²
2-1	Ceiling	White	Concrete	300 Ft ²
2.2	Wall Surfaces	Cream	Concrete	200 Ft ²
2-2	Ceiling	White	Concrete	48 Ft ²
2.2	Wall Surfaces ²	White	Concrete	112 Ft ²
2-3	Ceiling ²	White	Concrete	15 Ft ²
	Wall Tiles			140 Ft ²
	Floor Tiles			25 Ft ²
2-4	Bathtub	Pink	Ceramic	1 Unit
	Toilet			1 Unit
	Lavatory			1 Unit
	Wall Tiles	Multicolor	Ceramic	40 Ft ²
2-5	Mosaic	Multicolor Ceramic		50 Ft ²
	Railing	Black	Metal	30 Ft ²

Table	1-1: Summary of Cor	nponents Conta	ining Lead (co	nt.)
Area	Component	Color	Substrate	Approximate Amount
2-6	Ceiling	White	Concrete	324 Ft ²
2-0	Mosaic	Multicolor	Ceramic	324 Ft ²
2-7	Mosaic	Multicolor	Ceramic	140 Ft ²
2-8	Wall Surfaces	White	Concrete	52 Ft ²
2-0	Mosaic	Multicolor	Ceramic	35 Ft ²
	Wall Surfaces	Yellow	Concrete	275 Ft ²
	Wall Tiles & Mosaic	Multicolor	Ceramic	220 Ft ²
	Ceiling	White	Concrete	72 Ft ²
2-9	Floor Tiles			78 Ft ²
2-9	Toilet			1 Unit
	Bathtub	Blue	Ceramic	1 Unit
	Urinal			1 Unit
	Lavatory			1 Unit
2.10	Wall A & D	Cream	Concrete	159 Ft ²
2-10	Ceiling	White	Concrete	69 Ft ²
	Wall Tiles	Multicolor	Ceramic	216 Ft ²
2-11	Riser	Multicolor	Ceramic	42 Ft ²
	Railing	Black	Metal	63 Ft ²
	Wall A	Cream	Concrete	40 Ft ²
2-12	Railing	Black	Metal	36 Ft ²
	Railing Cap	Black	Metal	1 Unit
1-1	Wall Tiles & Mosaic	Multicolor	Ceramic	200 Ft ²
1-1	Gate	Black	Metal	24 Ft ²
	Wall Tiles	Multicolor	Ceramic	200 Ft ²
1-3	Mosaic	Multicolor	Ceramic	250 Ft ²
	Gate	Black	Metal	1 Unit
1-4	Floor Tiles	Brown	Ceramic	468 Ft ²
1-4	Baseboard	Brown	Ceramic	78 LnFt
1-6	Wall Surfaces	Cream	Concrete	588 Ft ²
1-0	Ceiling	Cream	Concrete	297 Ft ²

Table	1-1: Summary of Co	omponents Conta	ining Lead (co	nt.)
Area	Component	Color	Substrate	Approximate Amount
1.7	Floor Tiles	Black & Green	Ceramic	315 Ft ²
1-7	Wall Tiles	Multicolor	Ceramic	255 Ft ²
1-8	Wall A	Cream	Concrete	40 Ft ²
1-8	Ceiling	Cream	Concrete	18 Ft ²
1-9	Wall Surfaces	Cream	Concrete	166 Ft ²
1-9	Ceiling	Cream	Concrete	110 Ft ²
	Wall Surfaces	Blue	Concrete	185 Ft ²
1-10	Wall Tiles	White & Black	Ceramic	216 Ft ²
1-10	Ceiling	White	Concrete	130 Ft ²
	Cabinet Top	White	Metal	1 Unit
	Wall Tiles	White & Black	Ceramic	258 Ft ²
1-11	Wall Surfaces	Blue	Concrete	664 Ft ²
1-11	Ceiling	White	Concrete	182 Ft ²
	Counter Top	White	Metal	1 Unit
1-12	Wall Surfaces	Cream	Concrete	200 Ft ²
1-12	Ceiling	Cream	Concrete	45 Ft ²
1-13	Wall Surfaces	Cream	Concrete	507 Ft ²
1-13	Ceiling	Cream	Concrete	140 Ft ²
	Wall Tiles	Black	Concrete	16.5 Ft ²
1-14	Toilet	White	Ceramic	1 Unit
	Lavatory	White	Ceramic	1 Unit
1-15	Wall Surfaces	Cream	Concrete	267 Ft ²
1-13	Ceiling	Cream	Concrete	37 Ft ²
	Wall Tiles	Cream & Purple	Ceramic	125 Ft ²
	Floor Tiles	Cream	Ceramic	25 Ft ²
1-16	Bathtub	Purple	Ceramic	1 Unit
	Toilet	Purple	Ceramic	1 Unit
	Lavatory	Purple	Ceramic	1 Unit
	Wall Surfaces	Cream	Concrete	600 Ft ²
1-18	Wall Tiles & Mosaic	Multicolor	Ceramic	160 Ft ²
	Ceiling	Cream	Concrete	200 Ft ²

Table 1-1: Summary of Components Containing Lead (cont.)							
Area	Component	Color	Substrate	Approximate Amount			
	Wall Surfaces	Cream	Concrete	5, 550 Ft ²			
	Overhang	Cream	Concrete	190 Ft ²			
	Wall Tiles	Cream	Ceramic	22 Ft ²			
	Column	Cream	Concrete	160 Ft ²			
Exterior Areas	Floor Tiles	Multicolor	Ceramic	5 Ft ²			
	Chimney	Cream	Concrete	425 Ft ²			
	Railing Cap	Brown	Concrete	40 Ft ²			
	Fascia	White	Concrete	300 Ft ²			

Note:

- 1. The quantification of positives materials presented in this table is only an estimate. If an abatement of the materials will be conducted, the Contractors shall estimate the amount of materials to be abated.
- 2. Some concrete walls are covering by wood panels; therefore, the concrete surfaces are presumed to be LBP.

SECTION 2: LEAD-BASED PAINT INSPECTION REPORT

2.1 OVERVIEW OF THE EVALUATION

This lead-based paint inspection is an investigation to identify all lead-based paint on a surface-by-surface basis. A lead-based paint inspection conforming to HUD guidelines was performed at the aforementioned property.

Averages of 448 samples were taken at identified surfaces of the evaluated areas using X-ray fluorescence (XRF) analyzer. The evaluation found that lead-based paint was present in selective components and surfaces through the property on the date of the assessment (See Table 1-1).

Some of the remaining XRF test locations exhibited lead-in-paint levels below the level that EPA identifies as lead-based paint, namely 1.0 mg/cm². Such surfaces could create dust-lead or soil-lead hazards if the paint is turned into dust by abrasion, scraping, or sanding. Should these or any lead containing components or surfaces be disturbed in any manner that generates dust, care should be taken to limit its spread.

Testing was performed by Harry Peña, state-certified risk assessor LBPRA-20322-197 and Dilia Rosado, state-certified risk assessor LBPRA-20322-195, using the Niton XLp-300A XRF, SN-101222 and the Niton XLp-300A XRF, SN-18574, respectively. The credentials are provided in Section 3, Appendix A: Certifications, Licenses, and Accreditations. The XRF analyzer is designed to measure the lead content of surface coatings on a variety of building surfaces, substrates, and components. The measurement is rapid and nondestructive and, according to the manufacturer, is capable of detecting lead concentrations that occur within numerous layers of various surface coatings.

Please refer to the XRF Testing Results Section 3, Appendix B: XRF Sampling Data for the detailed analytical testing results for each distinct area inspected. The reports provide a complete testing data.

2.2 SAMPLING PROCEDURE

The Lead Based Paint Sampling Procedure was design to evaluate and document all the data obtained form the inspection in a sequential method that provided confidence at the moment of the results presentation.

The survey was performed following the methodology established in the HUD Guidelines for the Evaluation and Control of Lead Based Paint in Housing (2012 revision) and the Department of Natural and Environmental Resources (DRNA) of Puerto Rico Regulation 9098: Regulation for Proper Management of Lead-Based Paint Activities. The surfaces evaluation was performed as follows:

• If the lead concentration measured by the XRF Spectrum Analyzer is less than 1.0 mg/cm² it is considered negative.

ZIMMETRY ENVIRONMENTAL MANAGEMENT CORP.

Lead Based Paint Inspection
El Cortijo,
Barranquitas, Puerto Rico
Project No. ZEM-22225

Wall Tiles

• If the lead concentration measured by the XRF Spectrum Analyzer is equal or greater than 1.0 mg/cm² it is considered positive.

To each functional space of the property a name was assigned according to the use of that space. If no name could be assigned then a code letter or number was assigned.

Each wall surface was named with letters beginning with wall A the wall facing the main entrance direction. The wall at your left will be wall B, the wall at front wall C and the wall at you right will be wall D.

2.3 RESULTS PRESENTATION

This section describes the property components and surfaces coated with lead-based paint (LBP), which were observed in the inspection. Please note that the recommendations given are always the minimum action, which in our professional judgment should be taken.

According to the DRNA lead regulations, prior to the demolishing of a structure containing lead-based paint, the contaminated surfaces or substrates must be abated or removed. The firm providing the abatement services must be certified as an abatement firm by the DRNA.

2.3.1 SPECIFIC FINDINGS

The following LBP were found to contain more than 1.0 mg/cm² for what Department of Natural and Environmental Resources (DRNA) of Puerto Rico identifies as lead-based paint or materials containing lead:

Baseboard
 Lavatory

Bathtub
 Mosaic Floor & Wall Tiles

Cabinet Top
 Overhang

CeilingPartition

• Chimney • Railing

Column • Railing Cap

• Counter Top • Riser

• Curb • Sink

Cuio Silik

Fascia • Toilet
Floor Tiles • Urinal

Gate
 Wall Surfaces

2.3.2 HOMOGENEOUS AREAS WITH SPECIAL CONSIDERATIONS

NONE

2.3.3 INACCESSIBLE AREAS PRESUMED TO BE LEAD-BASED PAINTED

NONE

2.4 LEAD REGULATORY LEVELS

The lead regulatory levels provided below are those used when preparing this lead-based paint evaluation or when evaluating data collected. The EPA regulatory levels are the same as the state regulatory levels provided in the following table.

TABLE 2-1: LEAD REGULATORY LEVELS					
EPA/DRNA Levels					
Lead-Based Paint	1.0 mg/cm ² or 0.5% by weight (or 5,000 ppm)				

2.5 CONDITIONS AND LIMITATIONS—DISCLAIMER

Zimmetry Environmental Management Corp. has performed this lead-based paint inspection in a thorough and professional manner consistent with commonly accepted industry standards. The Preparer cannot guarantee and does not warrant that this evaluation has identified all adverse environmental factors and/or conditions affecting this property on the date of the evaluation.

The results reported and conclusions reached by the Preparer are solely for the benefit of the Owner. The results and opinions in this report, based solely on the conditions found at the property on the date of the evaluation, are valid only on that date. The Preparer assumes no obligation to advise the client of any changes in any real or potential lead-based paint hazards at this property beyond the date of the evaluation.

The lead inspection was performed to ready accessible components and surfaces. If suspected components that could contain lead are encountered underneath current installed tiles or other construction material, they shall be managed as containing lead until the appropriate test is performed.

2.6 ABATEMENT CONDITIONS

Abatement, as defined by HUD and the Department of Natural and Environmental Resources (DRNA) of Puerto Rico, means any set of measures designed to eliminate lead-based paint and/or lead-based paint hazards permanently. The people providing these services must to be trained in accordance with the DRNA licensing/certification requirements. The product manufacturer and/or contractor must warrant abatement methods to last a minimum of 20 years, or these methods must have a design life of at least 20 years.

- onsite or offsite removal of lead-based paint from substrates and components
- replacement of components or fixtures painted with lead-based paint
- permanent enclosure of lead-based paint with construction materials mechanically-fastened to the substrate

ZIMMETRY ENVIRONMENTAL MANAGEMENT CORP.

Lead Based Paint Inspection
El Cortijo,
Barranquitas, Puerto Rico
Project No. ZEM-22225

- encapsulation of lead-based paint with specially designed encapsulant products
- removal or permanent covering (concrete or asphalt) of soil-lead-based paint hazards

If enclosure or encapsulation is conducted as an abatement method, the lead-based paint remains on the property, so ongoing lead-based paint maintenance is required.

2.7 **RECOMMENDATIONS**

According to the DRNA lead regulations, prior to the demolishing of a structure containing lead-based paint, the contaminated surfaces or substrates must be abated or removed. The waste generated has to be characterized to determine if the waste generated is hazardous or non-hazardous waste. The firm providing the abatement services must be certified as an abatement firm by the DRNA. Workers conducting abatement must be trained and certified as abatement workers by a training provider accredited by the DRNA.

2.8 ENVIRONMENTAL ASSESSMENT REPORT CERTIFICATION

Zimmetry Environmental Management Corp. has performed this lead-based paint inspection in a thorough and professional manner consistent with commonly accepted industry standards. The inspection was conducted on December 9, 2022 by Harry Peña, state-certified risk assessor LBPRA-20322-197 and Dilia Rosado, state-certified risk assessor LBPRA-20322-195, both qualified by experience, education and training in the recognition of lead-based paint and approved sampling techniques using the Niton XLp-300A XRF, SN-101222 and the Niton XLp-300A XRF, SN-18574, respectively.

Harry Pena, MSEM

Environmental Risk Assessor

Dilia Rosado, MEM

Environmental Risk Assessor

SECTION 3: APPENDICES

Appendix A: Certifications, Licenses, and Accreditations

Appendix B: XRF Sampling Data

Appendix C: XRF's Performance Characteristics Sheet

Appendix D: Photographic Record

Appendix E: Location of Positive Materials

Barranquitas, Puerto Rico Project No. ZEM-22225

APPENDIX A: CERTIFICATIONS, LICENSES, AND ACCREDITATIONS




APPENDIX A: CERTIFICATIONS, LICENSES, AND ACCREDITATIONS



Thermo Scientific Niton XRF Analyzer Operator's Training Certificate This is to certify that

Harry Pena

has successfully completed the Thermo Fisher Scientific Niton XRF Analyzer Operational Training Course. The topics of this course include device configuration, sample preparation, safe operation and analysis, interpretation of results, and routine maintenance of the Thermo Scientific Niton XRF Analyzer.



Project No. ZEM-22225

APPENDIX A: CERTIFICATIONS, LICENSES, AND ACCREDITATIONS





Thermo Scientific Niton XRF Analyzer Operator's Training Certificate

This is to certify that

Dilia Rosado

has successfully completed the Thermo Fisher Scientific Niton XLp 300 XRF Analyzer Operational Training Course. The topics of this course include device configuration, sample preparation, safe operation and analysis, interpretation of results, and routine maintenance of the Thermo Scientific Niton XRF Analyzer.

Course date: July 12, 2018

Course teaches by: Thermo Fisher Portable Analytycal Inc.



Juan C. Cruz Regional Sales Manager Latin America & the Caribbean

Part of Thermo Fisher Scientific

I hermo

APPENDIX B: XRF SAMPLING DATA

	El Cortijo at Km 18.5, C. PR-162 in Barranquitas, Puerto Rico		CLIENT: Arquiteg - Architects & Planners LBP Inspector: Dilia Rosado				
DATE:	12/9/2022		I	LBP Inspec		ado	
Sample ID.	Functional Space	Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
1	Calibration				1.00		
2	Calibration				1.00		
3	Calibration	*** 11 A	****		1.00	D :::	
4	Area 4-1	Wall A Wall B	White White	Concrete	1.70 2.00	Positive	
5	Area 4-1 Area 4-1	Wall C	White	Concrete Concrete	1.50	Positive Positive	
7	Area 4-1	Wall D	White	Concrete	2.10	Positive	
8	Area 4-1	Door	Varnish	Wood	0.00	Negative	
9	Area 4-1	Door Casing	Varnish	Wood	0.00	Negative	
10	Area 4-1	Door	Varnish	Wood	0.00	Negative	
11	Area 4-1	Door Casing	Varnish	Wood	0.00	Negative	
12	Area 4-1	Window	Varnish	Wood	0.00	Negative	
13	Area 4-1	Floor Tile	Cream	Ceramic	0.00	Negative	
14	Area 4-1	Baseboard Ceiling	Cream White	Ceramic Concrete	0.00 2.30	Negative	
15 16	Area 4-1	Beam	Brown	Wood	0.00	Positive Negative	
17	Area 4-1 Area 4-1	Railing Cap	Black	Metal	22.00	Positive	
18	Area 4-1	Balluster	Black	Metal	0.00	Negative	
19	Area 4-1	Curb	White	Concrete	1.10	Positive	
20	Balcony	Wall A	White	Concrete	1.00	Positive	
21	Balcony	Wall B	White	Concrete	1.01	Positive	
22	Balcony	Wall C	White	Concrete	1.00	Positive	
23	Balcony	Wall D	White	Concrete	1.00	Positive	
24	Balcony	Railing Cap	Black	Metal	1.00	Positive	
25	Balcony	Overhang	White	Concrete	0.00	Negative	
26	Balcony	Balluster	Black	Metal	0.00	Negative	
27 28	Stairway 4th Floor - 3rd Floor	Wall A Wall B	White White	Concrete	1.60 1.60	Positive Positive	
29	Stairway 4th Floor - 3rd Floor	Wall C	White	Concrete Concrete	1.60	Positive	
30	Stairway 4th Floor - 3rd Floor Stairway 4th Floor - 3rd Floor	Wall D	White	Concrete	1.60	Positive	
31	Stairway 4th Floor - 3rd Floor	Floor	Black	Concrete	0.00	Negative	
32	Stairway 4th Floor - 3rd Floor	Column	White	Concrete	1.60	Positive	
33	3rd Floor Hallway	Wall A	White	Concrete	1.90	Positive	
34	3rd Floor Hallway	Wall B	White	Concrete	1.70	Positive	
35	3rd Floor Hallway	Wall C	White	Concrete	3.10	Positive	
36	3rd Floor Hallway	Wall D	White	Concrete	2.10	Positive	
37	3rd Floor Hallway	Ceiling	White	Concrete	1.00	Positive	
38	3rd Floor Hallway	Floor Tile	Cream	Ceramic	0.00	Negative	
39 40	Area 3-1	Wall A Wall B	Cream	Concrete	1.30 0.40	Positive	
41	Area 3-1 Area 3-1	Wall C	Cream Cream	Concrete Concrete	0.40	Negative Negative	
42	Area 3-1	Wall D	Cream	Concrete	1.30	Positive	
43	Area 3-1	Ceiling	Gray	Concrete	1.20	Positive	
44	Area 3-1	Baseboard	Brown	Wood	0.00	Negative	
45	Area 3-1	Window	Brown	Wood	0.00	Negative	
46	Stairway 3rd Floor - 2nd Floor	Ceiling	White	Concrete	2.50	Positive	
47	Stairway 3rd Floor - 2nd Floor	Upper Wall A	White	Concrete	1.60	Positive	
48	Stairway 3rd Floor - 2nd Floor	Wall B	White	Concrete	1.80	Positive	
49	Stairway 3rd Floor - 2nd Floor	Wall C Wall D	White	Concrete	2.70	Positive	
50 51	Stairway 3rd Floor - 2nd Floor	Column	White White	Concrete Concrete	1.00	Positive Positive	
52	Stairway 3rd Floor - 2nd Floor Stairway 3rd Floor - 2nd Floor	Partition	White	Concrete	1.80	Positive	
53	Stairway 3rd Floor - 2nd Floor Stairway 3rd Floor - 2nd Floor	Door	Varnish	Wood	0.00	Negative	
54	Stairway 3rd Floor - 2nd Floor Stairway 3rd Floor - 2nd Floor	Door Casing	Varnish	Wood	0.00	Negative	
55	Area 2-1	Window	Brown	Wood	0.00	Negative	
56	Area 2-1	Wall A	White	Concrete	0.20	Negative	
57	Area 2-1	Floor Tile	Cream	Ceramic	0.00	Negative	
58	Area 2-1	Baseboard	Cream	Ceramic	0.00	Negative	
59	Area 2-1	Wall B	White	Concrete	0.16	Negative	
60	Area 2-1	Window	Brown	Wood	0.00	Negative	

	El Cortijo at Km 18.5, C. PR-162 in Barranquitas, Puerto Rico			CLIENT: Arquiteg - Architects & Planners			
ATE:	12/9/2022	LBP Inspector: Dilia Rosado					
Sample ID.	Functional Space	Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
61	Area 2-1	Ceiling	White	Concrete	2.40	Positive	
62 63	Area 2-1	Beam Wall C	Brown White	Wood	0.00	Negative	
64	Area 2-1 Area 2-1	Wall D	White	Concrete Concrete	0.09	Negative Negative	
65	Area 2-1 Area 2-2	Door	Brown	Wood	0.19	Negative	
66	Area 2-2	Door Casing	Brown	Wood	0.00	Negative	
67	Area 2-2	Floor Tile	Cream	Ceramic	0.00	Negative	
68	Area 2-2	Baseboard	Cream	Ceramic	0.00	Negative	
69	Area 2-2	Wall A	Cream	Concrete	3.50	Positive	
70	Area 2-2	Wall B	Cream	Concrete	5.20	Positive	
71	Area 2-2	Wall C	Cream	Concrete	3.50	Positive	
72	Area 2-2	Wall D	Cream	Concrete	1.00	Positive	
73	Area 2-2	Ceiling	White	Concrete	1.00	Positive	
74	Area 2-2	Beam	Brown	Wood	0.00	Negative	
75 76	Area 2-2	Handrail Window Molding	White White	Concrete Concrete	0.00	Negative Negative	
77	Area 2-2 Area 2-3	Window Molding Wall A	Varnish	Wood	0.00	Negative	
78	Area 2-3	Wall B	Varnish	Wood	0.00	Negative	
79	Area 2-3	Wall C	Varnish	Wood	0.00	Negative	
80	Area 2-3	Wall D	Varnish	Wood	0.00	Negative	
81	Area 2-3	Door	Varnish	Wood	0.00	Negative	
82	Area 2-3	Door Casing	Varnish	Wood	0.00	Negative	
83	Area 2-3	Ceiling	Varnish	Wood	0.00	Negative	
84	Area 2-3	Shelve	Varnish	Wood	0.00	Negative	
85	Area 2-4	Wall A	White	Concrete	0.04	Negative	
86	Area 2-4	Wall B	White	Concrete	0.02	Negative	
87	Area 2-4	Wall C	White	Concrete	0.03	Negative	
88	Area 2-4	Wall D	White	Concrete	0.01	Negative	
89 90	Area 2-4	Window Door	Brown	Wood Wood	0.00	Negative	
91	Area 2-4	Door Casing	Brown Brown	Wood	0.00	Negative Negative	
92	Area 2-4 Area 2-4	Wall Tile	Pink	Ceramic	6.10	Positive	
93	Area 2-4	Wall Tile	Pink	Ceramic	6.40	Positive	
94	Area 2-4	Floor Tile	Pink	Ceramic	6.50	Positive	
95	Area 2-4	Bathtub	Pink	Ceramic	35.00	Positive	
96	Area 2-4	Toilet	Pink	Ceramic	7.60	Positive	
97	Area 2-4	Lavartory	Pink	Ceramic	8.60	Positive	
98	Area 2-4	Ceiling	White	Concrete	0.00	Negative	
99	Area 2-5	Wall B	White	Concrete	0.00	Negative	
100	Area 2-5	Wall C	White	Concrete	0.00	Negative	
101 102	Area 2-5	Wall D Wall Tile	White	Concrete	0.00 16.20	Negative Positive	
102	Area 2-5 Area 2-5	Wall Tile	Multicolor Multicolor	Ceramic Ceramic	28.00	Positive	
103	Area 2-5	Floor Tile	Brown	Ceramic	0.00	Negative	
105	Area 2-5	Ceiling	White	Concrete	0.04	Negative	
106	Area 2-5	Mosaic	Multicolor	Ceramic	1.00	Positive	
107	Area 2-5	Mosaic	Multicolor	Ceramic	0.00	Negative	
108	Area 2-5	Mosaic	Multicolor	Ceramic	0.00	Negative	
109	Area 2-5	Mosaic	Multicolor	Ceramic	0.00	Negative	
110	Area 2-5	Beam	Brown	Wood	0.00	Negative	
111	Area 2-5	Railing Cap	Brown	Wood	0.00	Negative	
112	Area 2-5	Railing	Black	Metal	1.60	Positive	
113	Area 2-5	Railing	Black	Metal	18.10	Positive	
114	Area 2-5	Door Coging	Varnish	Wood	0.00	Negative	
115 116	Area 2-5	Door Casing Door	Varnish Brown	Wood Wood	0.00	Negative Negative	
117	Area 2-6 Area 2-6	Door Casing	Brown	Wood	0.00	Negative	
118	Area 2-6	Door	Brown	Wood	0.00	Negative	
119	Area 2-6	Door Casing	Brown	Wood	0.00	Negative	
120	Area 2-6	Wall A	White	Concrete	0.00	Negative	

Sample ID. 121 122 123	12/9/2022 Functional Space			LBP Inspec	tor: Dilia Ros	ado	
ID. 121 122 123	Functional Space		T	EBT Inspec		addo	
122 123		Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
123	Area 2-6	Wall B	White	Concrete	0.00	Negative	
	Area 2-6	Wall C	White	Concrete	0.00	Negative	
124	Area 2-6	Wall D	White	Concrete	0.00	Negative	
	Area 2-6	Arc Ceiling	Varnish White	Wood Concrete	0.00 1.00	Negative Positive	
	Area 2-6 Area 2-6	Beam	Brown	Wood	0.00	Negative	
	Area 2-6	Floor Tile	Brown	Ceramic	0.00	Negative	
	Area 2-6	Baseboard	Brown	Ceramic	0.00	Negative	
129	Area 2-6	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-6	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-6	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-6	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-6	Mosaic Wall A	Multicolor	Ceramic Concrete	1.00 0.00	Positive	
	Area 2-7 Area 2-7	Wall A Wall B	White White	Concrete	0.00	Negative Negative	
	Area 2-7	Wall C	White	Concrete	0.00	Negative	
	Area 2-7	Wall D	White	Concrete	0.00	Negative	
	Area 2-7	Floor Tile	Brown	Ceramic	0.00	Negative	
	Area 2-7	Baseboard	Brown	Ceramic	0.00	Negative	
	Area 2-7	Mosaic	Multicolor	Ceramic	1.01	Positive	
	Area 2-7	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-7	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-7	Mosaic Mosaic	Multicolor Multicolor	Ceramic Ceramic	1.00	Positive Positive	
	Area 2-7 Area 2-7	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-7	Closet Door	Varnish	Wood	0.00	Negative	
	Area 2-7	Window	Brown	Wood	0.00	Negative	
	Area 2-7	Ceiling	White	Concrete	0.50	Negative	
	Area 2-7	Beam	Brown	Wood	0.00	Negative	
	Area 2-7	Wall A	Varnish	Wood	0.00	Negative	
	Area 2-7	Wall B	Varnish	Wood	0.00	Negative	
	Area 2-7	Wall C Wall D	Varnish	Wood	0.00	Negative	
	Area 2-7 Area 2-8	Wall A	Varnish White	Wood Concrete	0.00	Negative Negative	
	Area 2-8	Wall B	White	Concrete	0.00	Negative	
	Area 2-8	Wall C	White	Concrete	0.00	Negative	
	Area 2-8	Wall D	White	Concrete	0.00	Negative	
	Area 2-8	Ceiling	White	Concrete	0.18	Negative	
	Area 2-8	Floor Tile	Brown	Ceramic	0.00	Negative	
	Area 2-8	Baseboard	Brown	Ceramic	0.00	Negative	
	Area 2-8	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-8	Mosaic Mosaic	Multicolor Multicolor	Ceramic Ceramic	1.00	Positive Positive	
	Area 2-8 Area 2-8	Mosaic	Multicolor	Ceramic	1.00	Positive	
	Area 2-8	Closet Door	Brown	Wood	0.00	Negative	
	Area 2-8	Closet Door Casing	Brown	Wood	0.00	Negative	
	Area 2-8	Closet Ceiling	White	Concrete	1.12	Positive	
168	Area 2-8	Arc	Brown	Wood	0.00	Negative	
	Area 2-8	Wall A	White	Concrete	1.70	Positive	
	Area 2-8	Wall B	White	Concrete	1.70	Positive	
	Area 2-8	Wall C	White	Concrete	1.70	Positive	
	Area 2-8	Wall D	White	Concrete	1.70	Positive	
	Area 2-9	Wall A Wall B	Yellow Yellow	Concrete Concrete	1.20 1.20	Positive Positive	
	Area 2-9 Area 2-9	Wall C	Yellow	Concrete	1.10	Positive	
	Area 2-9	Wall D	Yellow	Concrete	1.10	Positive	
	Area 2-9	Wall Tile	Blue	Ceramic	5.70	Positive	
	Area 2-9	Wall Tile	Yellow	Ceramic	4.80	Positive	
178	Area 2-9	Mosaic	Multicolor	Ceramic	1.00	Positive	

		PR-162 in Barranquitas, P			rquiteg - Arc		
ATE:	12/9/2022		T	LBP Inspec	tor: Dilia Ros	ado	
Sample ID.	Functional Space	Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
181	Area 2-9	Ceiling	White	Concrete	1.51	Positive	
182 183	Area 2-9	Toilet	Blue	Ceramic	3.72 27.00	Positive	
184	Area 2-9 Area 2-9	Bathtub Urinal	Blue Blue	Ceramic Ceramic	4.70	Positive Positive	
185	Area 2-9	Lavartory	Blue	Ceramic	4.90	Positive	
186	Area 2-9	Window	Brown	Wood	0.00	Negative	
187	Area 2-9	Wall A	Yellow	Concrete	0.00	Negative	
188	Area 2-9	Wall B	Yellow	Concrete	0.00	Negative	
189	Area 2-9	Wall C	Yellow	Concrete	0.00	Negative	
190 191	Area 2-9	Wall D Wall A	Yellow	Concrete	0.00 3.10	Negative Positive	
191	Area 2-10 Area 2-10	Railing	Cream Brown	Concrete Wood	0.00	Negative	
193	Area 2-10 Area 2-10	Railing Cap	Brown	Wood	0.00	Negative	
194	Area 2-10	Column	Brown	Wood	0.00	Negative	
195	Area 2-10	Beam	Brown	Wood	0.03	Negative	
196	Area 2-10	Ceiling	White	Concrete	2.80	Positive	
197	Area 2-10	Door	Brown	Wood	0.00	Negative	
198	Area 2-10	Door Casing	Brown	Wood	0.00	Negative	
199	Area 2-10	Wall D	Cream	Concrete	3.50	Positive	
200 201	Area 2-10 Area 2-10	Door Door Casing	Brown Brown	Wood Wood	0.00	Negative Negative	
202	Area 2-10 Area 2-10	Floor Tile	Brown	Ceramic	0.00	Negative	
203	Area 2-11	Wall A	White	Concrete	0.05	Negative	
204	Area 2-11	Wall B	White	Concrete	0.01	Negative	
205	Area 2-11	Wall D	White	Concrete	0.27	Negative	
206	Area 2-11	Door	Brown	Wood	0.00	Negative	
207	Area 2-11	Door Casing	Brown	Wood	0.00	Negative	
208	Area 2-11	Window	Brown	Wood	0.00	Negative	
209 210	Area 2-11	Wall Tile Riser	Multicolor	Ceramic	1.00	Positive Positive	
211	Area 2-11 Area 2-11	Wall Tile	Multicolor Multicolor	Ceramic Ceramic	1.00	Positive	
212	Area 2-11 Area 2-11	Floor Tile	Brown	Ceramic	0.00	Negative	
213	Area 2-11	Railing	Black	Metal	1.68	Positive	
214	Area 2-11	Railing Cap	Brown	Wood	0.00	Negative	
215	Area 2-11	Ceiling	White	Concrete	0.00	Negative	
216	Area 2-11	Beam	Brown	Wood	0.00	Negative	
217	Area 2-12	Overhang	Cream	Concrete	0.00	Negative	
218 219	Area 2-12 Area 2-12	Wall A Railing Cap	Cream Black	Concrete Metal	1.11	Positive Positive	
220	Area 2-12 Area 2-12	Railing	Black	Metal	1.43	Positive	
221	Area 2-12	Door Molding	Brown	Concrete	0.00	Negative	
222	Area 2-12	Floor Tile	Brown	Ceramic	0.00	Negative	
223	Area 1-1	Wall Tile	Multicolor	Ceramic	1.00	Positive	
224	Area 1-1	Wall Tile	Brown	Ceramic	6.10	Positive	
225	Area 1-1	Understair	White	Concrete	0.00	Negative	
226	Area 1-1	Wall B	White	Concrete	0.00	Negative	
227 228	Area 1-1	Wall C Wall D	White White	Concrete Concrete	0.00	Negative Negative	
229	Area 1-1 Area 1-1	Beam	White	Concrete	0.00	Negative	
230	Area 1-1	Ceiling	White	Concrete	0.00	Negative	
231	Area 1-1	Floor Tile	Brown	Ceramic	0.00	Negative	
232	Area 1-1	Baseboard	Brown	Ceramic	0.00	Negative	
233	Area 1-1	Mosaic	Multicolor	Ceramic	59.10	Positive	
234	Area 1-1	Gate	Brown	Metal	2.20	Positive	
235	Area 1-2	Door	Brown	Wood	0.00	Negative	
236	Area 1-2	Door Casing	Brown	Wood	0.00	Negative	
237 238	Area 1-2	Wall A Wall B	Blue Blue	Concrete	0.00	Negative Negative	
239	Area 1-2 Area 1-2	Wall D	Blue	Concrete Concrete	0.00	Negative	
240	Area 1-2	Ceiling	Brown	Wood	0.00	Negative	

PROJECT:	El Cortijo at Km 18.5, C. Pl	R-162 in Barranquitas, P	uerto Rico	CLIENT: A	rquiteg - Arcl	hitects & Plan	nners
DATE:	12/9/2022			LBP Inspec	tor: Dilia Ros	sado	
Sample ID.	Functional Space	Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
241	Area 1-2	Ceiling	White	Concrete	0.00	Negative	
242	Area 1-2	Understair	White	Concrete	0.00	Negative	
243 244	Area 1-3	Wall A Wall B	White White	Concrete Concrete	0.00 0.00	Negative Negative	
245	Area 1-3 Area 1-3	Door	Brown	Wood	0.00	Negative	
246	Area 1-3	Door Casing	Brown	Wood	0.00	Negative	
	Area 1-3	Wall C	White	Concrete	0.00	Negative	
248	Area 1-3	Wall D	White	Concrete	0.00	Negative	
249	Area 1-3	Window	Brown	Wood	0.00	Negative	
	Area 1-3	Floor Tile	Brown	Ceramic	0.00	Negative	
251	Area 1-3	Baseboard	Brown	Ceramic	0.00	Negative	
252	Area 1-3	Wall Tile	Multicolor	Ceramic	15.30	Positive	
253	Area 1-3	Wall Tile	Brown	Ceramic	1.78	Positive	
254	Area 1-3	Door	Brown	Wood	0.00	Negative	
255	Area 1-3	Door Casing	Brown	Wood	0.00	Negative	
256	Area 1-3	Ceiling	White	Concrete	0.00	Negative	
257 258	Area 1-3	Beam Mosaic	Brown Multicolor	Wood Ceramic	0.00 23.70	Negative Positive	
258	Area 1-3 Area 1-3	Gate	Black	Metal	1.00	Positive	
260	Calibration	Gaic	Diack	Wictai	1.00	1 OSITIVE	
261	Calibration				1.00		
262	Calibration				1.00		
-	Currerunen						
		1					
		+					
		 					
							-
		1	Ī			Ī	

	El corrijo de Rin 10.5, C. 1	PR-162 in Barranquitas, P	uerto Kico	CLIENT. A	rquiteg - Arc	intects & Fran	iicis
DATE:	12/9/2022			LBP Inspec	tor: Harry Pe	ña	
Sample ID.	Functional Space	Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
263	Calibration				1.00		
264	Calibration				1.00		
265	Calibration	D	77 1	XX7 1	1.00	N T .:	
266	Area 1-4	Door Coging	Varnish	Wood Wood	0.00	Negative	
267 268	Area 1-4 Area 1-4	Door Casing Wall A	Varnish White	Concrete	0.00	Negative Negative	
269	Area 1-4	Wall B	White	Concrete	0.00	Negative	
270	Area 1-4	Wall C	White	Concrete	0.00	Negative	
271	Area 1-4	Wall D	White	Concrete	0.00	Negative	
272	Area 1-4	Floor Tile	Brown	Concrete	29.10	Positive	
273	Area 1-4	Window	Varnish	Wood	0.00	Negative	
274	Area 1-4	Window Casing	Varnish	Wood	0.00	Negative	
275	Area 1-4	Ceiling	White	Concrete	0.06	Negative	
276	Area 1-4	Beam	Brown	Wood	0.02	Negative	
277	Area 1-4	Transversal Beam	Brown	Wood Wood	0.01	Negative	
278 279	Area 1-4 Area 1-4	Beam Support Baseboard	Brown Brown	Concrete	0.10 32.00	Negative Positive	
280	Area 1-4 Area 1-5	Wall A	White	Concrete	0.12	Negative	
281	Area 1-5	Wall B	White	Concrete	0.12	Negative	
282	Area 1-5	Wall C	White	Concrete	0.03	Negative	
283	Area 1-5	Wall D	White	Concrete	0.10	Negative	
284	Area 1-5	Ceiling	White	Concrete	0.02	Negative	
285	Area 1-5	Beam	Brown	Wood	0.01	Negative	
286	Area 1-5	Window	Varnish	Wood	0.00	Negative	
287	Area 1-5	Window Casing	Varnish	Wood	0.00	Negative	
288	Area 1-5	Door	Varnish	Wood	0.00	Negative	
289	Area 1-5	Door Casing	Varnish	Wood	0.00	Negative	
290	Area 1-5	Floor Tile	Brown	Concrete	0.02	Negative	
291 292	Area 1-6	Wall A Wall B	Cream	Concrete Concrete	3.10 2.20	Positive	
292	Area 1-6 Area 1-6	Wall C	Cream Cream	Concrete	4.00	Positive Positive	
294	Area 1-6	Wall D	Cream	Concrete	3.20	Positive	
295	Area 1-6	Ceiling	Cream	Concrete	2.50	Positive	
296	Area 1-6	Beam	Brown	Wood	0.00	Negative	
297	Area 1-6	Window Grille	Black	Metal	0.00	Negative	
298	Area 1-6	Floor Tile	Brown	Concrete	0.00	Negative	
299	Area 1-7	Door	Varnish	Wood	0.00	Negative	
300	Area 1-7	Door Casing	Varnish	Wood	0.00	Negative	
301	Area 1-7	Floor Tile	Blue	Concrete	32.00	Positive	
302	Area 1-7	Floor Tile	Green	Concrete	38.00	Positive	
303 304	Area 1-7	Wall A Wall B	White White	Concrete Concrete	0.30 0.50	Negative	
304	Area 1-7	Wall C	White	Concrete	0.50	Negative Negative	
306	Area 1-7 Area 1-7	Wall D	White	Concrete	0.30	Negative	
307	Area 1-7	Wall Tile	Multicolor	Concrete	28.00	Positive	
308	Area 1-7	Ceiling	Brown	Wood	0.00	Negative	
309	Area 1-7	Beam	Brown	Wood	0.00	Negative	
310	Area 1-8	Door	Cream	Wood	0.00	Negative	
311	Area 1-8	Door Casing	Cream	Wood	0.00	Negative	
312	Area 1-8	Floor Tile	Brown	Ceramic	0.00	Negative	
313	Area 1-8	Baluster	Brown	Wood	0.00	Negative	
314	Area 1-8	Wall A	Cream	Concrete	3.30	Positive	
315	Area 1-8	Ceiling	Cream	Concrete	2.60	Positive	
316	Area 1-9	Wall A Wall B	Cream	Concrete	3.50	Positive	
317 318	Area 1-9	Wall C	Cream Cream	Concrete Concrete	3.10 3.20	Positive Positive	
319	Area 1-9 Area 1-9	Wall D	Cream	Concrete	1.20	Positive	
320	Area 1-9 Area 1-9	Ceiling	Cream	Concrete	3.50	Positive	
321	Area 1-9 Area 1-9	Beam	Brown	Wood	0.00	Negative	
322	Area 1-9	Railing Cap	Brown	Wood	0.00	Negative	

	El corrijo di Rili 10.5, C. 1	PR-162 in Barranquitas, P	uerto Rico	CLIENT: A	rquiteg - Arc	hitects & Plani	ners
ATE:	12/9/2022			LBP Inspec	tor: Harry Pe	ña	
Sample ID.	Functional Space	Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
323	Area 1-9	Baluster	Brown	Wood	0.00	Negative	
324 325	Area 1-9	Floor Tile Door	Brown Varnish	Ceramic Wood	0.00	Negative Negative	
326	Area 1-10 Area 1-10	Door Casing	Varnish	Wood	0.00	Negative	
327	Area 1-10	Wall A	Blue	Concrete	1.90	Positive	
328	Area 1-10	Wall B	Blue	Concrete	1.60	Positive	
329	Area 1-10	Wall C	Blue	Concrete	2.00	Positive	
330	Area 1-10	Wall D	Blue	Concrete	3.50	Positive	
331	Area 1-10	Wall Tile	White	Ceramic	5.00	Positive	
332	Area 1-10	Wall Tile	Blue	Ceramic	14.00	Positive	
333	Area 1-10	Floor Tile	White	Ceramic	0.70	Negative	
334	Area 1-10	Ceiling	White	Concrete	1.20	Positive	
335 336	Area 1-10	Cabinet Top Cabinet Door	White White	Metal Metal	1.70 0.00	Positive	
337	Area 1-10 Area 1-11	Wall Tile	White	Ceramic	3.10	Negative Positive	
338	Area 1-11	Wall Tile	Blue	Ceramic	1.80	Positive	
339	Area 1-11	Floor Tile	White	Ceramic	0.20	Negative	
340	Area 1-11	Wall A	Blue	Concrete	1.10	Positive	
341	Area 1-11	Wall B	Blue	Concrete	1.30	Positive	
342	Area 1-11	Wall C	Blue	Concrete	1.40	Positive	
343	Area 1-11	Wall D	Blue	Concrete	1.70	Positive	
344	Area 1-11	Ceiling	White	Concrete	1.80	Positive	
345	Area 1-11	Counter Top	White	Metal	1.80	Positive	
346	Area 1-11	Door	Varnish	Wood	0.00	Negative	
347 348	Area 1-11	Door Casing	Varnish	Wood	0.00	Negative	
348	Area 1-12 Area 1-12	Wall A Wall B	Cream Cream	Concrete Concrete	1.90 3.00	Positive Positive	
350	Area 1-12	Wall C	Cream	Concrete	2.50	Positive	
351	Area 1-12	Wall D	Cream	Concrete	4.10	Positive	
352	Area 1-12	Ceiling	Cream	Concrete	3.50	Positive	
353	Area 1-12	Beam	Brown	Wood	0.00	Negative	
354	Area 1-12	Floor Tile	Brown	Concrete	0.00	Negative	
355	Area 1-13	Wall A	Cream	Concrete	2.10	Positive	
356	Area 1-13	Wall B	Cream	Concrete	3.10	Positive	
357	Area 1-13	Wall C	Cream	Concrete	3.00	Positive	
358 359	Area 1-13	Wall D	Cream Cream	Concrete Concrete	1.90 2.30	Positive Positive	
360	Area 1-13 Area 1-13	Ceiling Floor Tile	Cream	Ceramic	0.00	Negative	
361	Area 1-13	Door	Varnish	Wood	0.00	Negative	
362	Area 1-13	Door Casing	Varnish	Wood	0.00	Negative	
363	Area 1-13	Window	Varnish	Wood	0.00	Negative	
364	Area 1-13	Window Casing	Varnish	Wood	0.00	Negative	
365	Area 1-14	Door	Varnish	Wood	0.00	Negative	
366	Area 1-14	Door Casing	Varnish	Wood	0.00	Negative	
367	Area 1-14	Wall A	Pink	Concrete	0.10	Negative	
368 369	Area 1-14	Wall B Wall C	Pink Pink	Concrete Concrete	0.30 0.20	Negative Negative	
370	Area 1-14 Area 1-14	Wall D	Pink	Concrete	0.20	Negative	
371	Area 1-14	Ceiling	White	Concrete	0.70	Negative	
372	Area 1-14	Wall Tile	White	Ceramic	0.06	Negative	
373	Area 1-14	Wall Tile	Black	Ceramic	17.90	Positive	
374	Area 1-14	Floor Tile	White	Ceramic	0.00	Negative	
375	Area 1-14	Floor Tile	Black	Ceramic	0.00	Negative	
376	Area 1-14	Toilet	White	Ceramic	6.70	Positive	
377	Area 1-14	Lavatory	White	Ceramic	33.40	Positive	
378	Area 1-15	Door Cosing	Varnish	Wood	0.00	Negative	
379	Area 1-15	Door Casing	Varnish	Wood	0.00	Negative Positive	
	A 1 1.5	\\/\all_A					
380 381	Area 1-15 Area 1-15	Wall A Wall B	Cream Cream	Concrete Concrete	1.40 1.20	Positive	

		R-162 in Barranquitas, P			1 0	nitects & Plan	
ATE:	12/9/2022		1	LBP Inspec	tor: Harry Pe	ňa	
Sample ID.	Functional Space	Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
383	Area 1-15	Wall D	Cream	Concrete	1.80	Positive	
384	Area 1-15	Ceiling	Cream	Concrete	1.20	Positive	
385 386	Area 1-16	Door Door Casing	Varnish Varnish	Wood Wood	0.00	Negative Negative	
387	Area 1-16 Area 1-16	Wall Tile	Cream	Ceramic	4.00	Positive	
388	Area 1-16	Wall Tile	Purple	Ceramic	26.00	Positive	
389	Area 1-16	Wall A	Cream	Concrete	0.21	Negative	
390	Area 1-16	Wall B	Cream	Concrete	0.40	Negative	
391	Area 1-16	Wall C	Cream	Concrete	0.17	Negative	
392	Area 1-16	Wall D	Cream	Concrete	0.30	Negative	
393	Area 1-16	Ceiling	White	Concrete	0.50	Negative	
394 395	Area 1-16	Floor Tile Lavatory	Cream Purple	Ceramic Ceramic	3.50 6.90	Positive Positive	
393	Area 1-16 Area 1-16	Toilet	Purple	Ceramic	8.30	Positive	
397	Area 1-16	Bathtub	Purple	Ceramic	29.00	Positive	
398	Area 1-16	Window	Varnish	Wood	0.00	Negative	
399	Area 1-16	Window Casing	Varnish	Wood	0.00	Negative	
400	Area 1-17	Door	Varnish	Wood	0.00	Negative	
401	Area 1-17	Door Casing	Varnish	Wood	0.00	Negative	
402	Area 1-17	Window	Varnish	Wood	0.00	Negative	
403	Area 1-17	Window Casing	Varnish	Wood	0.00	Negative	
404	Area 1-17 Area 1-17	Wall A Wall B	Cream Cream	Concrete Concrete	0.00	Negative Negative	
406	Area 1-17	Wall C	Cream	Concrete	0.00	Negative	
407	Area 1-17	Wall D	Cream	Concrete	0.00	Negative	
408	Area 1-17	Ceiling	Cream	Concrete	0.00	Negative	
409	Area 1-17	Beam	Brown	Wood	0.00	Negative	
410	Area 1-17	Floor Tile	Brown	Ceramic	0.00	Negative	
411	Area 1-18	Ceiling	Cream	Concrete	2.60	Positive	
412	Area 1-18	Wall A Wall B	Cream	Concrete	2.80 2.70	Positive	
414	Area 1-18 Area 1-18	Wall C	Cream Cream	Concrete Concrete	3.60	Positive Positive	
415	Area 1-18	Wall D	Cream	Concrete	3.30	Positive	
416	Area 1-18	Wall Tile	Multicolor	Ceramic	38.60	Positive	
417	Area 1-18	Floor Tile	Brown	Ceramic	0.00	Negative	
418	Area 1-18	Mosaic	Multicolor	Ceramic	8.90	Positive	
419	Area 1-18	Beam	Brown	Wood	0.50	Negative	
420	Area 1-18	Column	White	Concrete	0.19	Negative	
421	Area 1-18	Grille	Black	Metal	0.00	Negative	
422 423	Exterior Area Exterior Area	Wall A Column	Cream White	Concrete Concrete	1.60 0.10	Positive Negative	
424	Exterior Area	Wall A	Cream	Concrete	1.70	Positive	
425	Exterior Area	Grille	Black	Metal	0.20	Negative	
426	Exterior Area	Overhang	Cream	Concrete	1.30	Positive	
427	Exterior Area	Wall Tile	Cream	Ceramic	2.10	Positive	
428	Exterior Area	Column	Cream	Concrete	2.10	Positive	
429	Exterior Area	Wall B	Cream	Concrete	1.20	Positive	
430	Exterior Area	Wall B	Cream	Concrete	2.20	Positive	
431	Exterior Area	Wall C Wall C	Cream Cream	Concrete Concrete	3.20 4.10	Positive Positive	
432	Exterior Area Exterior Area	Floor Tile	Brown	Ceramic	0.00	Negative	
434	Exterior Area	Floor Tile	Multicolor	Ceramic	22.50	Positive	
435	Exterior Area	Chimney	Cream	Concrete	1.10	Positive	
436	Exterior Area	Railing Cap	Brown	Metal	10.50	Positive	
437	Exterior Area	Baluster	Brown	Metal	0.00	Negative	
438	Exterior Area	Balcony Wall	Cream	Concrete	0.60	Negative	
439	Exterior Area	Wall C	Cream	Concrete	1.10	Positive	
440	Exterior Area	Wall C	Cream	Concrete	1.20	Positive	
441	Exterior Area	Fascia	White	Concrete	1.20	Positive	
442	Exterior Area	Wall D	Cream	Concrete	1.30	Positive	

PROJECT:	El Cortijo at Km 18.5, C. P.	R-162 in Barranquitas, P	uerto Rico	CLIENT: A	rquiteg - Arc	hitects & Planı	ners
DATE:	12/9/2022			LBP Inspec	tor: Harry Pe	ña	
Sample ID.	Functional Space	Location	Color	Subst.	XRF Reading	Pos/Neg	Comments
443	Exterior Area	Wall D	Cream	Concrete	1.20	Positive	
444	Exterior Area	Fascia	White	Concrete	1.30	Positive	
445	Exterior Area	Overhang	Cream	Concrete	1.20	Positive	
446	Calibration				1.00		
447	Calibration				1.00		
448	Calibration				1.00		
				1			
				1			
				1			

ZIMMETRY ENVIRONMENTAL MANAGEMENT CORP.

Lead Based Paint Inspection
El Cortijo,
Barranquitas, Puerto Rico
Project No. ZEM-22225

APPENDIX C: XRF's PERFORMANCE CHARACTERISTICS SHEET

Performance Characteristic Sheet

EFFECTIVE DATE: September 24, 2004 EDITION NO.: 1

MANUFACTURER AND MODEL:

Make: Niton LLC
Tested Model: XLp 300
Source: 109Cd

Note: This PCS is also applicable to the equivalent model variations indicated

below, for the Lead-in-Paint K+L variable reading time mode, in the XLi and

XLp series:

XLi 300A, XLi 301A, XLi 302A and XLi 303A. XLp 300A, XLp 301A, XLp 302A and XLp 303A. XLi 700A, XLi 701A, XLi 702A and XLi 703A. XLp 700A, XLp 701A, XLp 702A, and XLp 703A.

Note: The XLi and XLp versions refer to the shape of the handle part of the instrument. The differences in the model numbers reflect other modes available, in addition to Lead-in-Paint modes. The manufacturer states that specifications for these instruments are identical for the source, detector, and detector electronics relative to the Lead-in-Paint mode.

FIELD OPERATION GUIDANCE

OPERATING PARAMETERS:

Lead-in-Paint K+L variable reading time mode.

XRF CALIBRATION CHECK LIMITS:

0.8 to 1.2 mg/cm² (inclusive)

The calibration of the XRF instrument should be checked using the paint film nearest 1.0 mg/cm² in the NIST Standard Reference Material (SRM) used (e.g., for NIST SRM 2579, use the 1.02 mg/cm² film).

If readings are outside the acceptable calibration check range, follow the manufacturer's instructions to bring the instruments into control before XRF testing proceeds.

SUBSTRATE CORRECTION:

For XRF results using Lead-in-Paint K+L variable reading time mode, substrate correction is <u>not</u> needed for: Brick, Concrete, Drywall, Metal, Plaster, and Wood

INCONCLUSIVE RANGE OR THRESHOLD:

K+L MODE READING DESCRIPTION	SUBSTRATE	THRESHOLD (mg/cm²)
Results not corrected for substrate bias on any	Brick	1.0
substrate	Concrete	1.0
	Drywall	1.0
	Metal	1.0
	Plaster	1.0
	Wood	1.0

BACKGROUND INFORMATION

EVALUATION DATA SOURCE AND DATE:

This sheet is supplemental information to be used in conjunction with Chapter 7 of the HUD *Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing* ("HUD Guidelines"). Performance parameters shown on this sheet are calculated from the EPA/HUD evaluation using archived building components. Testing was conducted in August 2004 on 133 testing combinations. The instruments that were used to perform the testing had new sources; one instrument's was installed in November 2003 with 40 mCi initial strength, and the other's was installed June 2004 with 40 mCi initial strength.

OPERATING PARAMETERS:

Performance parameters shown in this sheet are applicable only when properly operating the instrument using the manufacturer's instructions and procedures described in Chapter 7 of the HUD Guidelines.

SUBSTRATE CORRECTION VALUE COMPUTATION:

Substrate correction is not needed for brick, concrete, drywall, metal, plaster or wood when using Lead-in-Paint K+L variable reading time mode, the normal operating mode for these instruments. If substrate correction is desired, refer to Chapter 7 of the HUD Guidelines for guidance on correcting XRF results for substrate bias.

EVALUATING THE QUALITY OF XRF TESTING:

Randomly select ten testing combinations for retesting from each house or from two randomly selected units in multifamily housing. Use the K+L variable time mode readings.

Conduct XRF retesting at the ten testing combinations selected for retesting.

Determine if the XRF testing in the units or house passed or failed the test by applying the steps below.

Compute the Retest Tolerance Limit by the following steps:

Determine XRF results for the original and retest XRF readings. Do not correct the original or retest results for substrate bias. In single-family housing a result is defined as the average of three readings. In multifamily housing, a result is a single reading. Therefore, there will be ten original and ten retest XRF results for each house or for the two selected units.

Calculate the average of the original XRF result and retest XRF result for each testing combination.

Square the average for each testing combination.

Add the ten squared averages together. Call this quantity C.

Multiply the number C by 0.0072. Call this quantity D.

Add the number 0.032 to D. Call this quantity E.

Take the square root of E. Call this quantity F.

Multiply F by 1.645. The result is the Retest Tolerance Limit.

Compute the average of all ten original XRF results.

Compute the average of all ten re-test XRF results.

Find the absolute difference of the two averages.

If the difference is less than the Retest Tolerance Limit, the inspection has passed the retest. If the difference of the overall averages equals or exceeds the Retest Tolerance Limit, this procedure should be repeated with ten new testing combinations. If the difference of the overall averages is equal to or greater than the Retest Tolerance Limit a second time, then the inspection should be considered deficient.

Use of this procedure is estimated to produce a spurious result approximately 1% of the time. That is, results of this procedure will call for further examination when no examination is warranted in approximately 1 out of 100 dwelling units tested.

TESTING TIMES:

For the Lead-in-Paint K+L variable reading time mode, the instrument continues to read until it is moved away from the testing surface, terminated by the user, or the instrument software indicates the reading is complete. The following table provides testing time information for this testing mode. The times have been adjusted for source decay, normalized to the initial source strengths as noted above. Source strength and type of substrate will affect actual testing times. At the time of testing, the instruments had source strengths of 26.6 and 36.6 mCi.

	Tes	ting Times Usi	ng K+L Readin	g Mode (Seco	nds)			
		All Data			Median for laboratory-measured lead levels (mg/cm²)			
Substrate	25 th Percentile	Median	75 th Percentile	Pb < 0.25	0.25 <u><</u> Pb<1.0	1.0 <u><</u> Pb		
Wood Drywall	4	11	19	11	15	11		
Metal	4	12	18	9	12	14		
Brick Concrete Plaster	8	16	22	15	18	16		

CLASSIFICATION RESULTS:

XRF results are classified as positive if they are greater than or equal to the threshold, and negative if they are less than the threshold.

DOCUMENTATION:

A document titled *Methodology for XRF Performance Characteristic Sheets* provides an explanation of the statistical methodology used to construct the data in the sheets, and provides empirical results from using the recommended inconclusive ranges or thresholds for specific XRF instruments. For a copy of this document call the National Lead Information Center Clearinghouse at 1-800-424-LEAD.

This XRF Performance Characteristic Sheet was developed by the Midwest Research Institute (MRI) and QuanTech, Inc., under a contract between MRI and the XRF manufacturer. HUD has determined that the information provided here is acceptable when used as guidance in conjunction with Chapter 7, Lead-Based Paint Inspection, of HUD's *Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing*.

 Photo No.
 Date:

 2419
 12/9/2022

Description:

Area 4-1

Lead-based painted concrete wall surfaces.



Photo No. Date: 2420 12/9/2022

Description:

Area 4-1

Lead-based painted concrete wall surfaces.



Photo No. 2422	Date: 12/9/2022	
Description: Area 4-1 Lead-based paint surfaces.		
Photo No. 2423	Date: 12/9/2022	
Description: Area 4-1 Lead-based paint surfaces.		

Photo No. 2424	Date: 12/9/2022	
Description: Area 4-1 Lead-based paint cap.	ted metal railing	
Photo No. 2425	Date: 12/9/2022	
Description: Area 4-1 Lead-based paint curb.		

Photo No.	Date:	
2426	12/9/2022	
Description: Area 4-1 Lead-based paint ceiling.	ted concrete	
Photo No.	Date:	
2427	12/9/2022	
Description: Balcony Lead-based paint cap.	ted metal railing	

Photo No. 2429	Date: 12/9/2022	
Description: Stairway 4th Flate Lead-based paint column & wall st		
Photo No. 2433	Date: 12/9/2022	
Description: 3rd Floor Hallw Lead-based paint surfaces.		

Photo No.	Date:	
2434	12/9/2022	
Description: 3rd Floor Hallw Lead-based paint ceiling.	ay	
Photo No.	Date:	
2435	12/9/2022	
Description: Area 3-1 Lead-based paint surfaces.	ed concrete wall	

Photo No.	Date:	
2436	12/9/2022	

Description:

Area 3-1 Lead-based painted concrete wall surfaces.



Photo No.	Date:
2437	12/9/2022

Description:

Area 3-1 Lead-based painted concrete ceiling.



Photo No. 2439	Date: 12/9/2022	
Description: Stairway 3rd Fl Lead-based paint upper wall surface	oor - 2nd Floor ed concrete	
Photo No.	Date: 12/9/2022	
Description: Stairway 3rd Floor - 2nd Floor Lead-based painted concrete wall surfaces & partition.		

Photo No. 2443	Date: 12/9/2022	
Description: Stairway 3rd Fl Lead-based paint surfaces & colum	oor - 2nd Floor ted concrete wall nn.	
Photo No. 2446	Date: 12/9/2022	
Description: Area 2-1 Lead-based paint ceiling.		

Photo No. 2449	Date: 12/9/2022	
Description: Area 2-2 Lead-based paint surfaces.		
Photo No.	Date:	
2450	12/9/2022	
Description: Area 2-2 Lead-based paint surfaces.	ed concrete wall	

Photo No.	Date:	
Description: Area 2-2 Lead-based pain ceiling.	ted concrete	
Photo No.	Date:	
Description: Area 2-3 Lead-based pain walls (covered by panels).	ted concrete by wooden	

Photo No. 2455	Date: 12/9/2022	
Description: Area 2-4 Lead containing		
Photo No. 2456	Date: 12/9/2022	
Description: Area 2-4 Lead containing tiles.		

Photo No. 2458	Date: 12/9/2022	
Description: Area 2-4 Lead containing lavatory.	ceramic	
Photo No. 2459	Date: 12/9/2022	
Description: Area 2-4 Lead containing		

Photo No.	Date:	
Description: Area 2-4 Lead containing tiles.	ceramic floor	
Photo No. 2463	Date: 12/9/2022	
Description:	ted metal railing.	

Photo No. 2464	Date: 12/9/2022	
Description: Area 2-5 Lead containing floor tiles.		
Photo No.	Date:	
2466	12/9/2022	
Description: Area 2-5 Lead containing tiles.	ceramic wall	

Photo No. 2468	Date: 12/9/2022	
Description: Area 2-6 Lead containing floor tiles.		
Photo No. 2467	Date: 12/9/2022	
Description: Area 2-6 Lead containing floor tiles.		

Photo No. 2473	Date: 12/9/2022	
Description: Area 2-9 Lead containing lavatory.		
Photo No.	Date:	
Description: Area 2-9 Lead containing	ceramic bathtub.	

Photo No.	Date:	
Description: Area 2-9 Lead-based paint surfaces.	ted concrete wall	
Photo No.	Date:	
2479	12/9/2022	
Description: Area 2-9 Lead-based paint ceiling.	red concrete	

Photo No.	Date:	
Description: Area 2-9 Lead containing tiles, toilet and u	ceramic floor urinal.	
Photo No. 2481	Date: 12/9/2022	
Description: Area 2-9 Lead containing wall tiles.	ceramic mosaic	

Lead-based painted concrete wall

surfaces.

Photo No. 2482	Date: 12/9/2022		
Description: Area 2-8 Lead-based painted concrete ceiling.			
Photo No. 2483	Date: 12/9/2022		
Description: Area 2-10			

Photo No.	Date:	
2484	12/9/2022	
Description: Area 2-10 Lead-based paint surfaces.		
Photo No.	Date:	
2485	12/9/2022	
Description: Area 2-10 Lead-based paint ceiling.		

Photo No.	Date:	
2488	12/9/2022	
Description: Area 2-11 Lead containing tiles.	ceramic wall	
Photo No.	Date:	T
2491	12/9/2022	
Description: Area 2-11 Lead containing	ceramic raiser.	

Photo No. 2490	Date: 12/9/2022	
Description: Area 2-11 Lead containing tiles.		
Photo No.	Date:	
Description: Area 1-1 Lead containing floor tiles.	ceramic mosaic	

Photo No.	Date:	
2494	12/9/2022	
Description: Area 1-1 Lead containing tiles.		
Photo No.	Date:	
2495	12/9/2022	
Description: Area 1-1 Lead-bases paint	ed metal gate.	

Photo No. 2496	Date: 12/9/2022	
Description: Area 1-1 Lead containing tiles.		
Photo No. 2497	Date: 12/9/2022	
Description: Area 1-3 Lead containing ceramic wall tiles.		

Photo No. 2499	Date: 12/9/2022	
Description: Area 1-3 Lead containing floor tiles.		
Photo No.	Date:	
Description: Area 1-4 Lead containing baseboard.	12/9/2022 ceramic	

Photo No. 2503	Date: 12/9/2022	
Description: Area 1-6	ited concrete wall	
Photo No. 2504	Date: 12/9/2022	
Description: Area 1-6	ated concrete wall	

Photo No.	Date:	
Description: Area 1-6 Lead-based painted concrete wall surfaces.		
Photo No. 2507	Date: 12/9/2022	
Description: Area 1-6 Lead-based painted concrete wall surfaces.		

Photo No. 2508	Date: 12/9/2022	
Description: Area 1-7 Lead containing tiles.		
Photo No. 2509	Date: 12/9/2022	
Description: Area 1-7 Lead containing ceramic wall tiles.		

Photo No. 2510	Date: 12/9/2022	
Description: Area 1-8 Lead-based paint ceiling.		
Photo No.	Date:	
2514	12/9/2022	
Description: Area 1-9 Lead-based paint surfaces.	ted concrete wall	

Photo No.	Date:	
Description: Area 1-10 Lead containing tiles.	12/9/2022	
Photo No. 2516	Date: 12/9/2022	
Description: Area 1-10 Lead-based paint top.		

Photo No.	Date:		
2518	12/9/2022		
Description:		200	
Description.			
			ACC.
Area 1-10			Air Cool
	inted concrete wall		
surfaces.			
Surfaces.		66	

Photo No. Date: 2521 12/9/2022

Description:

Area 1-10 Lead-based painted concrete wall surfaces.



Photo No. 2526	Date: 12/9/2022	
Description: Area 1-11 Lead-based paint surfaces.		
Photo No. 2527	Date: 12/9/2022	
Description:	ted concrete wall	

Photo No.	Date:	
Photo No. 2529 Date: 12/9/2022 Description: Area 1-11 Lead-based painted metal counter top.		
Photo No. 2530	Date: 12/9/2022	
Description:	ted concrete wall	

Photo No.	Date:	
2531	12/9/2022	
Description: Area 1-12 Lead-based painted concrete wall surfaces.		
DI 4 N	T D .	
Photo No. 2533	Date: 12/9/2022	
Description:	ted concrete wall	

Photo No. 2534	Date: 12/9/2022		
Description: Area 1-12 Lead-based paint surfaces.			
Photo No. 2536	Date: 12/9/2022		
Description: Area 1-13 Lead-based paint surfaces.			

Photo No.	Date:	
2538	12/9/2022	
Description: Area 1-13 Lead-based paint surfaces.	ed concrete wall	
Photo No.	Date:	
2540	12/9/2022	
Description: Area 1-13 Lead-based paint ceiling.		

Photo No. 2541	Date: 12/9/2022	
Description: Area 1-14 Lead containing tiles.		

Photo No. Date: 2542 12/9/2022

Description:

Area 1-13 Lead-based painted concrete wall surfaces.



Photo No. 2544	Date: 12/9/2022	
Description: Area 1-14 Lead containing	ceramic sink.	
Photo No.	Date:	
Description: Area 1-14 Lead containing	ceramic toilet.	

Photo No. 2547	Date: 12/9/2022	
Description: Area 1-14 Lead containing tiles.		
Photo No. 2548	Date: 12/9/2022	
Description:	ted concrete wall	

Photo No. 2551	Date: 12/9/2022		
Description: Area 1-15 Lead-based paint surfaces.	ted concrete wall		
Photo No. 2552	Date: 12/9/2022		
Description: Area 1-15 Lead-based paint ceiling & wall su			

Photo No. 2553	Date: 12/9/2022	
Description: Area 1-16 Lead containing ceramic toilet.		
Photo No.	Date:	
2554	12/9/2022	
Description: Area 1-16 Lead containing ceramic sink.		

Photo No.	Date:	
2556	12/9/2022	
Description: Area 1-16 Lead containing		
Photo No.	Date:	
2557	12/9/2022	
Description: Area 1-16 Lead containing tiles.	ceramic wall	

Photo No.	Date:	
Photo No. 2560 Date: 12/9/2022 Description: Area 1-16 Lead containing ceramic floor tiles.		
Photo No. 2561	Date: 12/9/2022	
Description: Area 1-16 Lead containing tiles.		

Photo No.	Date:	
Description: Area 1-18 Lead containing and wall tiles.	ceramic mosaic	
Photo No.	Date:	
2564	12/9/2022	
Description: Area 1-18 Lead-based paint surfaces.	ted concrete wall	

Photo No. 2565	Date: 12/9/2022	
Description: Area 1-18 Lead-based painted concrete wall surfaces.		
Photo No.	Date:	
2566	12/9/2022	
Description: Area 1-18 Lead-based painted concrete wall surfaces.		

Photo No. 2568	Date: 12/9/2022	

Description:

Area 1-18 Lead-based painted concrete ceiling.



Photo No.	Date:	
2569	12/9/2022	

Description:

Exterior Areas

Lead-based painted concrete wall surfaces & overhang.



Photo No. 2570	Date: 12/9/2022	
Description: Exterior Areas Lead-based paint surfaces.		
Photo No.	Date:	
2571	12/9/2022	
Description: Exterior Areas Lead-based paint surfaces.		

Photo No.	Date:	
Photo No. 2573 Date: 12/9/2022 Description: Exterior Areas Lead-based painted concrete wall surfaces & overhang.		
Photo No.	Date:	
2572	12/9/2022	
Description: Exterior Areas Lead containing ceramic wall tiles.		

Photo No. 2581	Date: 12/9/2022	
Description: Exterior Areas Lead-based pain cap.		

Photo No. Date: 2582 12/9/2022

Description:

Exterior Areas

Lead-based painted concrete wall surfaces.



Photo No.	Date:
2583	12/9/2022

Description:

Exterior Areas

Lead-based painted concrete wall surfaces & chimney.




Photo No.	Date:
2584	12/9/2022

Description:

Exterior Areas


Lead-based painted concrete wall surfaces.






ZIMMETRY ENVIRONMENTAL MANAGEMENT CORP. Lead Based Paint Inspection El Cortijo, Barranquitas, Puerto Rico Project No. ZEM-22225

APPENDIX E: LOCATION OF POSITIVE MATERIALS





DIVISION 02 – EXISTING CONDITIONS

SECTION 02 82 13 - ASBESTOS ABATEMENT

1. INTRODUCTION

- 1.1 The Contractor shall perform all planning, administration, execution, and cleaning necessary to safely remove asbestos-containing or contaminated materials.
- 1.2 The Contractor shall obtain the following permits from the Department of Natural Resources and Environment (DNRE) in order to proceed with contract work.
 - 1.2.1 Asbestos Containing Materials General Permit
- 1.3 No architectural, engineering, or structural demolition or renovation work shall be executed before the asbestos-containing materials have been removed if the materials will be disturbed during such activities.
- 1.4 The Contractor and suppliers are responsible to comply with all the strictest, updated regulations/standards and codes and any changes that may occur during the contracted construction performance period.

DESCRIPTION OF THE ABATEMENT WORK

- 2.1 The asbestos abatement shall also include, but not be limited to the following:
 - (a) Notification to regulatory agencies
 - (b) Regulatory permits, licenses, and approvals
 - (c) Worker health and safety program
 - (d) Air monitoring
 - (e) Construction of temporary containment barrier/decontamination enclosures
 - (f) Preparation for abatement operations
 - (g) Removal of existing asbestos-containing material
 - (h) Transport and disposal of asbestos-containing material
 - (i) Decontamination and cleaning
 - (j) Application of lockdown encapsulants
 - (k) Removal of temporary containment barrier/decontamination enclosures
 - (1) Final job close-out

3. PERFORMANCE OF WORK

- 3.1 The Contractor shall be an Asbestos Hazard Control Contractor licensed to perform asbestos abatement work by the DNRE and shall meet the following requirements:
- 3.2 Maintain on-site one Superintendent, to remain on-site at all times that work is in progress. The superintendent shall be a Competent Person as defined in the Specifications and as required by OSHA.
 - 3.2.1 Use only trained and experienced asbestos abatement workers to perform the Work. All asbestos abatement workers assigned to tasks within this project shall be DNRE asbestos abatement workers/supervisors and shall have successfully completed training through an EPA-accredited curriculum.
- 3.3 The abatement shall be considered similar to an OSHA Class 2 asbestos abatement work, which includes the removal, packaging, and disposal of asbestos-containing materials related to the materials to be removed.
- 3.4 The Contractor and/or Environmental Sub-Contractor (s) shall perform the Work in accordance with 29 CFR 1926.11 01, 40 CFR 61-SUBPART A; 40 CFR 61SUBPART M, A.S.H.A.R.A. (Asbestos School Hazard Reauthorization Act) Rule 422 of the Atmospheric Air Control Regulation of Puerto Rico, Federal Department of Transportation (D.O.T.), Public Commission Service of Puerto Rico ("CSP"), rule 644 of the Non-Hazardous Waste Regulation of Puerto Rico and the requirements specified herein, as well as any other updated applicable federal, state or local government laws and regulations.
- 3.5 All other work described in the Specifications shall be performed according to applicable codes and standards, federal, state, and local regulations, and the Specifications and Drawings.

4. DEFINITIONS

- 4.1 <u>Abatement</u>: Procedures to control or eliminate fiber release from asbestos containing building materials including encapsulation, enclosure, and removal.
- 4.2 <u>Abatement Work Area (regulated area)</u>: An area established by the employer to demarcate areas where Class I, II, III, and IV asbestos work is conducted, and any adjoining area where debris and waste from such

- asbestos work accumulate; and a work area within which airborne concentrations of asbestos, exceed or there is a reasonable possibility they may exceed the permissible exposure limit.
- 4.3 <u>Air Filtration Units</u>: A local exhaust unit, utilizing HEPA filtration and capable of maintaining a minimum negative pressure differential of 0.05 mm of water within the containment barrier with respect to that of the environment surrounding the containment barrier.
- 4.4 <u>Airlock</u>: Two curtained doorways spaced a minimum of one meter apart from an airlock in the abatement worker/equipment decontamination and waste load-out enclosures.
- 4.5 <u>Air Monitoring:</u> The process of measuring the fiber content of a specific air volume during a stated period.
- 4.6 <u>Air Pressure Monitoring</u>: The process of measuring the air pressure differential between the containment barrier and the surrounding area using a micromanometer unit.
- 4.7 <u>Amended Water</u>: Water to which a surfactant (wetting agent) has been added to increase the ability of the liquid to penetrate ACM.
- 4.8 <u>Asbestos</u>: Asbestiform varieties of chrysotile, amosite, crocidolite, tremolite, anthophyllite, and actinolite.
- 4.9 <u>Asbestos-Containing Material (ACM)</u>: Any material containing more than 1% asbestos by volume of any type or mixture of types.
- 4.10 <u>Clean Room</u>: An uncontaminated area or room which is part of the abatement worker/equipment decontamination enclosure, with provisions for the storage of workers' or visitors' street clothing, protective equipment, and uncontaminated materials and equipment.
- 4.11 Competent Person: In addition to the definition in 29 CFR 1926.32 (f), one who is capable of identifying existing asbestos hazards in the workplace and selecting the appropriate control strategy for asbestos exposure, who has the authority to take prompt corrective measures to eliminate them, as specified in 29 CFR 1926.32 (f). In addition, the competent person shall have successfully completed training for Class I, Class II, Class III, and Class IV projects meeting the criteria set forth in the EPA Model Accreditation Plan (40 CFR 763) for project designer or supervisor, and operations and maintenance training.

- 4.12 <u>Containment Barrier</u>: A temporary enclosure constructed with fire-retardant plastic sheeting, suitable framing, duct tape, and other adhesives within the abatement work area.
- 4.13 <u>Critical Barrier:</u> Those portions of the containment barrier which represent the minimum structural components necessary to maintain the asbestos removal area in airtight isolation from the surrounding areas.
- 4.14 <u>Decontamination Enclosure</u>: A series of connected rooms with curtained doorways between each room, for the decontamination of the abatement workers and equipment/materials.
- 4.15 <u>Encapsulant</u>: A material applied after the removal of ACM or to the ACM-edges of partially abated substrates that surround or embeds residual asbestos fibers in an adhesive matrix to prevent their release into the atmosphere.
- 4.16 <u>Enclosure:</u> Procedures necessary to completely enclose material containing asbestos behind airtight, impermeable, permanent barriers.
- 4.17 <u>Engineering Controls:</u> Physical measures which are put into place at the work site to insure containment and control and/or the reduction of asbestos dust and fume exposure.
- 4.18 EPA: United States Environmental Protection Agency.
- 4.19 <u>DNRE</u>: Department of Natural Resources and Environment.
- 4.20 <u>Exposure Monitoring:</u> The personal air monitoring of an employee's breathing zone to determine the amount or level of containment (e.g. asbestos) to which the individual is exposed.
- 4.21 <u>Fiber</u>: A particulate form of asbestos, 5 micrometers or longer, with a length-to width ratio of at least 3 to 1.
- 4.22 <u>Final Clearance Inspection:</u> An inspection by an A.H.E.R.A. trained and DNRE certified Contractor/Supervisor or Certified Industrial Hygienist (CIH) to determine whether abatement and clean up are complete and that units tested pass the final clearance standards as set forth herein. All testing has to be done by an independent NVLAP or AIHA Air Sampling Monitoring accredited environmental laboratory for the purpose of any sampling related

- to this asbestos abatement project. The final clearance shall be 0.005 f/cc utilizing NIOSH 7400 method.
- 4.23 <u>HEPA Filter</u>: A High-Efficiency Particulate Air (HEPA) filter capable of trapping and retaining 99.97% of all mono-dispersed particles 0.3 micrometers in diameter or larger.
- 4.24 <u>Manifest:</u> To be originated and signed by the Owner's representatives. The shipping document, EPA form 8700-22, or the DNRE applicable form used for identifying the quantity, composition, origin, routing, and destination of hazardous waste during its transportation from the point of generation to the point of treatment, storage, or disposal.
- 4.25 NESHAP: National Emissions Standard for Hazardous Air Pollutants.
- 4.26 NIOSH: National Institute for Occupational Safety and Health.
- 4.27 <u>Non-friable Asbestos Material:</u> Material that contains asbestos in which the fibers have been locked in by a bonding agent, coating, binder, or other material so that the asbestos is well bound and may not release fibers in excess of the asbestos permissible exposure limit during any appropriate use, handling, storing, transporting, or processing.
- 4.28 OSHA: Occupational Safety and Health Administration.
- 4.29 PEL: Permissible Exposure Limit.
- 4.30 <u>Personal Monitoring</u>: Sampling of asbestos fiber concentrations within the breathing zone of an employee.
- 4.31 <u>Personal Protective Equipment</u>: Equipment may consist of coveralls, shoes, gloves, helmets, goggles, and respirators used for protection against asbestos exposure.
- 4.32 <u>Plastic Sheeting:</u> Fire retardant Polyethylene sheet material of specified thickness used for protection of walls, floors, etc., and critical barriers in the abatement work area.
- 4.33 <u>Regulated Area</u>: A perimeter established to demarcate areas where airborne concentrations of asbestos exceed or can reasonably be expected to exceed the Action Level.

- 4.34 Resource Conservation and Recovery Act (RCRA): The primary federal statute governing waste management from generation to disposal
- 4.35 <u>Respirator</u>: A device designed to protect the wearer from the inhalation of harmful atmospheres and approved by NIOSH or MSHA for a specific category of use.
- 4.36 <u>Warning Labels and Signs</u>: As required by OSHA regulations 29 CFR 1910.1001 and 1926.58.

5. ACCESS TO THE WORK AREA

- 5.1 Access to the abatement work area shall be restricted to the contractor's workers and authorized visitors.
- 5.2 Authorized visitors shall have access to the work site at all times following notification to the Owner or its Representative. The contractor shall supply protective clothing and equipment for visitors as necessary, except for respirators which are to be provided by the visitor.
- 5.3 Contractor shall prominently post signs at all potential entry points to the abatement work area which clearly states: "Restricted Area Under Construction Admittance by Special Permission Only Protective Clothing Required Beyond This Point". Immediately inside the entry point and outside critical barriers post a warning sign meeting specifications of OSHA 29 CFR 1910 and 1926. The suggested format is a sign of minimum size 508 mm by 356 mm displaying the following legend:

DANGER

ASBESTOS

CANCER AND LUNG DISEASE HAZARD

AUTHORIZED PERSONNEL ONLY

RESPIRATORS AND PROTECTIVE CLOTHING ARE REQUIRED IN THIS AREA

5.4 Contractor shall maintain a daily job site personnel log listing names and social security numbers of individuals who entered the abatement work area, and the times of entering and leaving the area.

6. POST REMOVAL

Cleaning and Clearance

- 6.1 Provide general clean-up of the abatement work area concurrent with the removal of all asbestos-containing materials. Do not perform dry dusting or dry sweeping.
- 6.2 Final Air Clearance Testing.
 - (a) Final clearance P.C.M. Air Monitoring testing will be performed by the Contractor's Industrial Hygienist. The Final clearance P.C.M. Air Monitoring testing shall be performed by the NVLAP, AIHA, or A2LA accredited Environmental Laboratory for Asbestos Air Monitoring.
- 6.3 Consider abatement work areas and all other decontaminated and cleaned areas clean when:
 - (a) All phases of clean-up have been completed and the level of cleanliness is approved.
 - (b) All air samples obtained indicate airborne fiber concentrations of 0.005 f/cc of air or less for final cleaning.

7. AIR MONITORING AND CLEARANCE LEVEL

- 7.1 <u>Analytical Methods</u>: The following methods will be used by the Contractor's industrial hygienist in analyzing filters used to collect air samples.
 - 7.1.2 <u>Phase Contrast Microscopy (PCM)</u> will be performed using the OSHA Reference Method, Appendix A to 29 CFR 1926.1101, or NIOSH Method 7400.
 - 7.1.2 <u>Transmission Electron Microscopy (TEM)</u> will be performed using the analysis method set forth in the AHERA regulation 40 CFR Part 763 Appendix A, or NIOSH Method 7402, whichever is deemed more appropriate by Owner industrial hygienist in each case.

- 7.2 <u>Before Start of Work</u>: The Contractor's industrial hygienist will secure abatement work area air samples to establish a baseline fiber level in each homogeneous abatement work area before the start of work.
- 7.3 <u>Daily</u>: From the start of abatement work through project decontamination, the Contractor industrial hygienist laboratory will be taking samples on a daily basis inside and outside each abatement work area.
- 7.4 <u>All Clearance Air Samples</u> will be collected by the Contractor's Industrial Hygienist Laboratory.
- 7.5 <u>Abatement Work Area Final Clearance Levels</u>: The Owner standard for abatement work area final clearance for removing the containment and reoccupancy is: less than 0.005 f/cc by PCM or 70 structures per mm² by TEM. All final air samples will meet this criteria.

8. INITIAL ISOLATION OF THE WORK AREA

- 8.1 Contractor shall completely separate the abatement work area from other portions of the building by sealing all openings (windows, doorways, corridor entrances, drains, ducts, grill, diffusers, skylights, etc.) with barriers of 6 mil. polyethylene sheeting and tape, or by sealing cracks leading out of the abatement work area.
- 8.2 Arrange for the abatement work area to be locked during non-work hours. Install temporary doors with entrance-type locksets that are key-lockable from the outside and always unlocked and operable from the inside.

PREPARATION OF ABATEMENT WORK AREA AND TEMPORARY ENCLOSURES

- 9.1 The Contractor shall perform abatement work without damage or contamination of adjacent work areas, buildings, and sites. Where such buildings or work areas are damaged or contaminated, the Contractor shall restore to the original condition at no additional cost to the Owner.
- 9.2 Clean all contaminated furniture, equipment, and supplies with a HEPA-filtered vacuum cleaner or by wet wiping, prior to being moved or covered.
- 10. CONSTRUCTION OF WORKER/EQUIPMENT DECONTAMINATION AND WASTE LOAD OUT ENCLOSURES

- 10.1 The Contractor shall construct a worker/equipment decontamination enclosure consisting of at least a clean room, a shower room, and an equipment room, each separated by 36 in. air locks.
- 10.2 <u>Waste Load-Out Enclosure</u>: Asbestos-contaminated waste that has been containerized shall be transported out of the abatement work area either through the personnel/equipment decontamination enclosure or through a separate waste load-out enclosure.

11. REMOVAL OF ASBESTOS CONTAINING MATERIALS (ACM) - General

- 11.1 The following work shall be done only after the decontamination facilities have been constructed, the area has been isolated and as specified in the previous section, pre-abatement background sampling has been conducted, and arrangements have been made for disposing of waste at an acceptable site.
- 11.2 <u>Wet Removal</u>: Prior to stripping and/or tooling, the asbestos material shall be sprayed using an airless pump and wetting agents (amended water or removal encapsulant) to enhance penetration and reduce fiber dispersal into the air.
 - 11.2.1 A fine spray of amended water shall be applied to reduce fiber release preceding the removal of the asbestos material. The material shall be sufficiently saturated to prevent the emission of excessive airborne fibers.
 - 11.2.2 Spray material repeatedly during the abatement work process to maintain a continuously wet condition. If a removal encapsulant is used, apply it in strict accordance with the manufacturer's instructions.
- 11.3 Gross removal of dust and debris from contaminated material, material containers, and equipment shall be accomplished in the containment barrier before removal to the equipment decontamination room for wet sponging before leaving the abatement work site.
- 12. POST REMOVAL: Cleaning and Clearance
 - 12.1 Do not perform dry dusting or dry sweeping.
 - 12.2 Initial Phase Cleanup Sequence

- (a) Remove all visible accumulations of asbestos-containing material and debris.
- (b) Wet clean and HEPA-vacuum all surfaces in the abatement work area.
- (c) Clean all equipment (excluding that which will be needed for further cleaning phases) used in the abatement work area and remove from abatement work area via the Equipment Decontamination Enclosure.
- (d) Remove the top layer (secondary barrier) of plastic sheeting, change all air filtration system pre-filters, and proceed with the second cleaning.
- (e) Replace all HEPA-filters and pre-filters in air filtration air machines with clean filters. Clean all air filtration machines.

12.3 Final Air Clearance Testing.

- (a) Final clearance P.C.M. Air Monitoring testing will be performed by the Contractor's Industrial Hygienist and the amount of clearance samples will be determined by the Owner or its Representatives in compliance with applicable Local, State and Federal regulations. The Final clearance P.C.M. Air Monitoring testing shall be performed by the NVLAP, AIHA or A2LA accredited Environmental Laboratory for Asbestos Air Monitoring.
- (b) After area passes final air clearance dismantle Decontamination Enclosure Systems and thoroughly HEPA-vacuum and wet clean immediate areas.
- (c) Dispose of debris from removal operation, used cleaning materials, unsalvageable materials used for sturdy barriers, and any other remaining materials. Consider the materials to be contaminated, and dispose of accordingly.
- 12.4 Consider abatement work areas and all other decontaminated and cleaned areas clean when:
 - (a) All phases of clean-up have been completed and the level of cleanliness is approved by the Owner or its Representative.

(b) All air samples obtained indicate airborne fiber concentrations of 0.005 f/cc of air or less for final cleaning.

13. WASTE DISPOSAL

- 7.1 Bulk and containerized asbestos waste shall be packed, labeled, and transported according to DOT Regulations 49 CFR 173.216 and 49 CFR 173.240. All removed ACM, plastic sheeting, tape, cleaning material, clothing, and all other disposable material or items used in the abatement work area shall be packed into double-bagged sealable 6 mil. plastic bags or double containerized with one bag and/or drum. The bags shall be marked with the labels required by OSHA 29 CFR 1910.1001 and/or 1910.1200, and 1926.1101. The Contractor shall transport the approved sealed container and/or drums to an approved waste disposal site.
- 7.2 The Contractor shall remove from the site all other debris and garbage resulting from removal and disposal operations and the temporary construction of containment barriers and enclosures.

END OF SECTION

DIVISION 02 - EXISTING CONDITIONS

SECTION 02 83 19 – LEAD-BASED PAINT ABATEMENT

1. INTRODUCTION

- 1.1 The Contractor shall perform all planning, administration, execution, and cleaning necessary to safely perform the abatement of the lead-based paint (LBP) and/or lead-based paint hazards.
- 1.2 The Contractor shall obtain the following permits from the Department of Natural Resources in order to proceed with contract work:
 - 1.2.1 Lead-Based Paint Abatement General Permit
- 1.3 No architectural, engineering or structural demolition work shall be executed before the lead-based paint and components have been removed, stabilized, and/or encapsulated if the materials will be disturbed during such activities.
- 1.4 The Contractor and suppliers are responsible to comply with all the strictest, updated regulations/standards and codes and any changes that may occur during the contracted construction performance period.

DESCRIPTION OF THE ABATEMENT WORK

- 2.1 Abatement of lead-based paint and lead-based paint hazards include, but are not necessarily limited to:
 - (a) Notification to regulatory agencies
 - (b) Regulatory permits, licenses, and approvals
 - (c) Worker health and safety program
 - (d) Establishing engineering controls to prevent migration of lead in air from the work area
 - (e) Preparation for abatement operations
 - (f) Personal air monitoring as required by regulatory agencies for the safety of its employees
 - (g) Abatement of existing lead-based paint
 - (h) Transport and disposal of lead-containing or lead-contaminated material
 - (i) Performance of incidental mechanical and electrical work necessary for conducting the Work

- (j) Decontamination and cleaning
- (k) Removal of engineering controls, including teardown of containment and decontamination unit
- (l) Final job close-out

3. PERFORMANCE OF WORK

- 3.1 The Contractor or subcontractor to perform the Work shall be a Lead Hazard Control Contractor licensed to perform lead hazard control work by the Department of Natural Resources and Enironment and shall meet the following requirements:
- 3.2 Maintain on site one Superintendent, to remain on site at all times that work is in progress. Superintendent shall be a Competent Person as defined in the Specifications and as required by OSHA.
- 3.3 The Contractor shall comply with the applicable hazardous and non-hazardous waste regulations as specified in Chapter 10 of the Guidelines for Evaluation and Control of Lead Based Paint Hazards in Housing as stated by HUD, as any other material disposal process required by EPA, the Department of Natural Resources approved work plan and the Puerto Rico Solid Waste Administration requirements.
- 3.4 All other work described in the Specifications shall be performed according to applicable codes and standards, federal, state, and local regulations, and the Specifications and Drawings.

4. **DEFINITIONS**

- 4.1 <u>Abatement</u>: A measure or set of measures designed to permanently eliminate lead-based paint or lead-based paint hazards. Abatement strategies include the removal of lead-based paint, the enclosure or encapsulation of lead-based paint, the removal and replacement of building components coated with leadbased paint, and the removal of lead-contaminated soil or overlaying of soil with a durable covering such as asphalt.
- 4.2 <u>Action Level</u>: The level above which several OSHA requirements is initiated, including, but not limited to: personnel exposure monitoring, medical surveillance, and lead training and education; set by OSHA at 30 micrograms per cubic meter (g/m³).

- 4.3 Air Filtration Unit: A local exhaust unit, utilizing HEPA filtration and capable of maintaining a minimum negative pressure differential of 0.5 mm of water gage pressure within the containment with respect to that of the surrounding areas.
- 4.4 <u>Air Monitoring</u>: The process of measuring the airborne lead content of a specific volume of air during a stated period of time.
- 4.5 <u>Airborne Lead Dust Contamination:</u> Any interior condition following abatement in which an appropriate air monitoring test indicates eighthour time weighted average of greater than 15 micrograms of lead per cubic meter (15 ug/m³) of air.
- 4.6 <u>Chewable Surface:</u> All chewable protruding painted surfaces up to five feet from the floor or ground, which are readily accessible to children under seven years of age i.e., protruding corners, windows sills and frames, doors and frames, linen and pantry closet shelves, kitchen wall, base cabinets and other protruding painted surfaces.
- 4.7 <u>Clean Room</u>: An uncontaminated area or room which is part of the decontamination unit, with provisions for storage of worker's or authorized visitor's street clothing and protective equipment, and other uncontaminated materials and equipment.
- 4.8 <u>Clearance Standards for Original Bare Soil and Floors:</u> The following is the standard by which lead content for the original bare soil clearance shall be below in order to be accepted for the abatement are reutilization:
 - Original Bare Soil 400 ug/g, floor dust wipes 40 ug/ft², window sill 250 ug/ft². (These are the Puerto Rico lead standards as specified in the DNR's <u>Lead Based Paint Abatement Activities Control Regulation</u> clearance level after the demolition/abatement is finished and accepted by the OWNER and its representatives.
- 4.9 <u>Competent Person</u>: An agent of the Contractor (i.e., the on-site Superintendent) who is a Competent Person as defined by OSHA regulations. This person must be capable of identifying existing and predictable lead hazards and have the authorization by the Contractor to take prompt corrective actions to eliminate them. The Competent Person shall remain on site at all times during the Work.
- 4.10 <u>Containment</u>: A temporary enclosure constructed with 6 mil thick plastic sheeting, suitable framing, and duct tape and other adhesives within the work area. The containment serves to confine the lead-based paint

- abatement, and decontamination work, and to contain the release of airborne lead dust and debris through the action of pressure differential ventilation and air filtration units when required by these Specifications.
- 4.11 <u>Critical Barrier</u>: Those portions of the containment which represent the minimum structural components necessary to maintain the work area in airtight isolation from the surrounding areas.
- 4.12 <u>Decontamination Unit</u>: A series of connected rooms with curtained doorways between each room, for the decontamination of the abatement workers, equipment and materials. The system is constructed of an airtight, impermeable, temporary barrier.
- 4.13 <u>DOT</u>: The United States Department of Transportation.
- 4.14 <u>Elevated Blood Lead Level (EBL):</u> Excessive absorption of lead (Pb), which is a confirmed concentration of lead (Pb) in whole blood as determined by the whole blood lead (Pb) method, utilizing Vena-Puncture technique.
- 4.15 <u>Encapsulation</u>: Any covering or coating (encapsulant) that acts as a barrier between existing lead-based paint and the environment, the durability of which relies on adhesion and the integrity of the existing bonds between multiple layers of paint, and between the paint and the substrate.
- 4.16 <u>Enclosure</u>: The use of rigid, durable construction materials that are mechanically fastened to the substrate to act as a dust-tight, impermeable, permanent barrier between the lead-based paint and the environment.
- 4.17 <u>Engineering Controls</u>: Measures which are put into place at the work sit to insure containment and control and/or the reduction of lead dust debris and fume exposure.
- 4.18 <u>EPA</u>: The United States Environmental Protection Agency.
- 4.19 <u>EPA Identification Number</u>: A number which is assigned specifically to a generator or transporter of hazardous waste.
- 4.20 <u>DNRE</u>: Puerto Rico Department of Natural Resources and Environmental.
- <u>4.21</u> <u>Exposure Monitoring:</u> The personal air monitoring of an employee's breathing zone to determine the amount of level of containment (e.g.

- lead) to which the individual is exposed. Monitoring is required for all employees directly involved with this LBP demolition abatement operation. All testing (before, during and final worker's monitoring) shall be executed by an independent ELPAT audited, AIHA or A2LA accredited environmental laboratory for lead air monitoring.
- 4.22 <u>Final Clearance Inspection:</u> An inspection by an DNRE Certified Lead Based Paint model trained Inspector or Risk Assessor with proven experience, to determine whether abatement and clean-up are complete and that all units tested pass the final clearance standards as set forth herein will performed the final clearance inspection.
- 4.23 <u>Generator</u>: Any person (s), by site, whose act or process produces hazardous waste identified or listed in 40 CFR 261 or whose act first caused a hazardous waste to become subject to regulation.
 - 4.23.1 Conditionally Exempt Small Generator: A generator producing no more than 100 kilograms (220 pounds) of hazardous waste per month and has received a written exemption from EPA. Conditionally exempt generators are required only to dispose of their wasted is compliance with the DNRE regulations, which, in most States, means that they must label their and take it to a licensed solid waste disposal facility. However, some States require disposal of even small quantities of hazardous waste at a licensed hazardous waste disposal facility.
- 4.24 <u>Small Generator:</u> A generator producing more than 100 kilograms but less than 1000 kilograms per month. A small generator must comply with EPA and DNRE hazardous waste regulations for accumulation, treatment, storage, and disposal of hazardous waste.
 - 4.24.1 <u>Large Generator</u>: A generator producing 1000 kilograms or more of hazardous waste per month. Large generator must comply with all EPA and DNRE hazardous waste regulations, including reporting and record keeping.
- 4.25 <u>Hazardous Waste</u>: As defined in EPA regulations, hazardous waste is solid waste or a combination of solid wastes that because of its quantity, concentration, or physical, chemical, or infectious characteristics may cause or significantly contribute to increases in mortality, serious and irreversible or incapacitating but reversible illness, or pose a substantial present or potential hazard to human health or the environment when improperly treated, stored, transported, or disposed. Lead-based hazardous waste is waste that contains greater than or equal to 5 parts

- per million (ppm) of leachable lead as determined by the toxicity characteristic leaching procedure (TCLP) test, or is waste that is corrosive, ignitable, or reactive and not otherwise excluded.
- 4.26 <u>HEPA Filter</u>: A High Efficiency Particulate Air filters capable of trapping and retaining 99.97 percent of all mono-dispersed particles 0.3 micrometer in diameter or larger.
- 4.27 HUD: The United States Department of Housing and Urban Develop.
- 4.28 <u>Impermeable Waste Disposal Containers</u>: Containers suitable to receive and retain any lead-containing or lead-contaminated material until disposal at an EPA-approved site. The containers shall be labeled in accordance with all applicable regulations and as directed in these Specifications.
- 4.29 Interim Lead-Based Paint Controls: A set of measures designed to temporarily reduce human exposure or possible exposure to lead-based paint hazards. Interim controls include paint film stabilization, encapsulation of lead-based paint, friction and impact surface treatment, dust removal and control, and interim controls of lead-contaminated soil.
- 4.30 <u>Lead-Based Paint (LBP)</u>: Any paint, varnish, shellac, or other coating that contains lead equal to or greater than 0.5 percent by weight as measured by laboratory analysis, or 1.0 milligrams per square centimeter (mg/cm²) as measured by XRF or laboratory analysis.
- 4.31 <u>Lead-Based Paint Hazard</u>: A condition in which exposure to lead from lead contaminated dust, lead-contaminated soil, or deteriorated lead-based paint would have an adverse effect on human health.
- 4.32 <u>Manifest:</u> The shipping document, EPA form 8700-22, or the DNRE applicable form used for identifying the quantity, composition, origin, routing, and destination of hazardous waste during its transportation from the point of generation to the point of treatment, storage, or disposal.
- 4.33 <u>Microgram (g)</u>: The prefix "micro" means one millionth of (1/1,000,000 of). A microgram is one millionth of a gram.
- 4.34 NIOSH: National Institute for Occupational Safety and Health.

- 4.35 Off-Site Paint Removal: The process of removing a component from a building and stripping the lead-based paint from the component at an off-site paint-stripping facility.
- 4.36 OSHA: Occupational Safety and Health Administration.
- 4.37 <u>Permissible Exposure Limit (PEL)</u>: The level above which special precautions and procedures must be implemented for the protection of personnel within the work area; set by OSHA at 50 g/m³.
- 4.38 <u>Personal Monitoring</u>: Sampling of the airborne lead concentrations within an employee's breathing zone, to determine the eight hour time-weighted average (TWA).
- 4.39 <u>Personal Protective Equipment:</u> Equipment for protecting the eyes, face, head, and extremities. Personal protective equipment includes protective clothing, respiratory devices, and protective shields, and is used when hazards capable of causing bodily injury or impairment are encountered.
- 4.40 <u>Regulated Area</u>: An area established to demarcate areas where airborne concentrations of lead exceed or can reasonably be expected to exceed the Action Level.
- 4.41 Removal and Replacement: An abatement method that entails the removal of building components coated with lead-based paint (e.g., windows, doors, trim, etc.) and the installation of components free of lead-based paint.
- 4.42 Resource Conservation and Recovery Act (RCRA): The primary federal statute governing waste management from generation to disposal. RCRA defines the criteria for hazardous and non-hazardous waste.
- 4.43 <u>Respirator</u>: A device designed to protect the wearer from the inhalation of harmful atmospheres and approved by NIOSH or MSHA for a specific category of use.
- 4.44 <u>Substrate</u>: A surface on which paint, varnish, or other coating has been applied or may be applied. Examples of substrates include wood, plaster, metal, drywall, brick and block, stone, and concrete.
- 4.45 <u>Toxicity Characteristic Leaching Procedure (TCLP)</u>: A laboratory test used to determine if excessive concentrations of lead or other hazardous

- materials could leach from a sample into groundwater; usually used to determine if waste is hazardous based on its toxicity characteristics.
- 4.46 <u>Wet Cleaning</u>: The process of eliminating loose contamination from building surfaces and objects by using cloths, mops, or other cleaning tools. These cleaning tools shall be disposed of as lead-contaminated waste.
- 4.47 <u>Windowsill</u>: The portion of the horizontal window ledge, adjacent to the window sash when the window is closed, that protrudes into the interior or the room or from the exterior of the window; sometimes called the 'window stool'.
- 4.48 <u>Window Trough</u>: For a typical double-hung window, the portion of the exterior windowsill between the interior window sill and the frame of the storm window. If there is no storm window, the window trough is the area that receives both the upper and lower window sashes when they are both lowered; sometimes called the 'window well'.
- 4.49 <u>XRF Analyzer</u>: An instrument that determines lead concentration in milligrams per square centimeter using the principle of x-ray fluorescence (XRF).

5. ACCESS TO WORK AREA

- 5.1 Access to the work area shall be restricted to the Contractor's workers and authorized visitors.
- 5.2 Authorized visitors shall have access to the work site at all times, following notification to the Owner or its Representative. The Contractor shall supply protective clothing and equipment for authorized visitors, as necessary, except for respirators, which shall be provided by the authorized visitor.
- 5.3 <u>Signage for Abatement Work</u>: The Contractor shall prominently post signs at all entry points to the work area which clearly warns that lead abatement work is being conducted in the vicinity in Spanish and English languages. Immediately inside de entry point and outside critical barriers post a warning sign meeting specification of OSHA. The format shall be a sign of minimum size 500 mm by 350 mm displaying the following legend:

WARNING

LEAD WORK AREA POISON

UNAUTHORIZED ENTRY PROHIBITED NO SMOKING, EATING OR DRINKING PERMITTED IN THIS AREA

Signs shall be in bold lettering a minimum of 50 mm tall.

- 5.3.1 All workers and authorized visitors shall enter the work area through the decontamination unit only, in accordance with these Specifications.
- 5.3.2 All workers and authorized visitors, before entering the work area, shall read and be familiar with all posted regulations, personal protection requirements, and emergency procedures and exit routes.
- 5.3.3 The Contractor shall maintain a daily job site personnel log listing names and social security numbers of individuals who entered the work area, and the times of entering and leaving the work area.

6. LEAD MONITORING, TESTING, AND ANALYSIS PROCEDURES

- 6.1 Laboratories used to conduct lead analyses shall participate in the EPA's National Lead Laboratory Accreditation Program (NLLAP).
- 6.2 Sampling for lead-in-paint shall be performed by persons licensed by the DNRE to perform lead-based paint inspections/risk assessments. Sampling shall be performed generally following the protocols included in HUD's "Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing" using either an XRF Lead Paint Analyzer or by bulk paint chip sampling. Analysis of bulk paint chips for lead shall be performed by an accredited laboratory using either Flame Atomic Absorption Spectroscopy (FLAA) or by Inductively Coupled Plasma (ICP).
- 6.3 Sampling for lead-in-air shall be performed generally following the "Sampling Airborne Particulate for Lead (NIOSH Method 7082)" procedure as outlined in HUD's "Guidelines for the Evaluation and

Control of LeadBased Paint Hazards in Housing". Analysis of lead-inair samples shall be performed by an accredited laboratory using either FLAA or ICP methods.

- 6.4 Lead dust wipe sampling shall be performed generally following the "Wipe Sampling for Settled Lead-Contaminated Dust" procedure as outlined in HUD's "Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing". Analysis of lead wipe samples shall be performed by an accredited laboratory using FLAA following NIOSH Modified Method 7082 or by ICP following Modified OSHA Method ID-125.
- 6.5 Lead-in-soil sampling shall be performed generally following the procedures outlined in HUD's "Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing". Analysis of soil for lead shall be performed by an accredited laboratory by FLAA or ICP.
- 6.6 Bulk samples of waste for TCLP analysis shall be representative samples of the waste and shall be collected following the procedure indicated by the selected laboratory performing the TCLP analysis. TCLP analysis of representative samples of lead-containing or lead-contaminated waste shall be performed by an accredited laboratory following EPA Method SW-846 "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods".

INITIAL ISOLATION OF WORK AREA

- 7.1 The Contractor shall coordinate the sequence of work area preparation throughout the building with the Owner or its Representative and other trades to properly segregate work areas from areas that must remain fully or partially operational or in which other construction is being performed.
- 7.2 Doorways and corridors which will not be used for passage during work shall be sealed with 13 mm thick fire retardant plywood, fire retardant wood framing, and poly sheeting with tape.
- 7.3 The Contractor shall arrange for the work area to be locked during non-work hours. Install temporary doors with entrance-type lock sets that are key lockable from the outside and always unlocked and operable from the inside. Remove deadbolts and padlocks. Provide one key to be held by the Owner or its Representative in the Inspection Office.

PREPARATION OF WORK AREA: ABATEMENT - INTERIOR

- 8.1 The Contractor shall clean and remove items required for access; clean all furniture, equipment, and supplies in the work area with a HEPA-filtered vacuum or by wet wiping, as directed by the Owner or its Representative, prior to being moved or covered.
- 8.2 The Contractor shall remove all removable furniture, equipment, and supplies that have been deemed by Owner or its Representative to be uncontaminated, or shall completely seal with two layers of 6 mils poly sheeting and duct tape.
- 8.3 The Contractor shall cover the floor of the work area with two layers of 6 mil poly sheeting turned up at the walls at least 600 mm.
- 8.4 The Contractor shall cover all walls in the work area, including sealed critical barriers, with two layers of 6 mil poly sheeting, sealed with duct tape or spray glue.

9. CONSTRUCTION OF WORKER/EQUIPMENT DECONTAMINATION AND WASTE LOAD UNIT

- 9.1 The Contractor shall construct a three-stage worker/equipment decontamination unit at each location where workers and equipment will enter or exit the work area.
- 9.2 Decontamination units shall consist of a Clean Room, a Wash Area (with shower facilities when required by these Specifications), and an Equipment Room, each separated by 1.0 meter air locks (narrower air locks may be built if approved by the Owner or its Representative).

10. PREPARATION OF WORK AREA: ABATEMENT - EXTERIOR

- 10.1 Exterior lead-based paint abatement work shall not be conducted if wind speeds or gusts are equal to or greater than 30 km/hr; work must stop and cleanup shall be completed before precipitation begins; work shall not begin if precipitation has been forecast to occur during the work shift.
- 10.2 The Contractor shall post warning signs on the building exterior and along temporary fencing or tape barrier.

- 10.3 The Contractor shall clean all surfaces in the work area with a HEPAfiltered vacuum or by wet wiping, as directed by the Owner or its Representative.
- 10.4 The Contractor shall install a minimum of two layers of 6 mils poly sheeting on all critical barriers in the work area to the building interior (e.g., windows, doors, air intake grills, window air conditioning units, etc.).
- 10.5 The Contractor shall cover the floor surface of the work area with two layers of 6 mil poly sheeting, turned up at any walls at least 600 mm.

11. PROHIBITED ABATEMENT METHODS

- 11.1 Open Flame Burning or Torching
- 11.2 Heat Guns Operating Above 590 C
- 11.3 Machine Sanding or Grinding Without a HEPA Exhaust Tool
- 11.4 Uncontained Hydroblasting or High-Pressure Water Wash
- 11.5 Abrasive Blasting or Sandblasting
- 11.6 Chemical Paint Removal Using Methylene Chloride-Based Paint Strippers
- 11.7 Dry Scraping:

12. ACCEPTABLE ABATEMENT METHODS AND PROCEDURES

- 12.1 Building Component Removal and Replacement
- 12.2 Paint Removal Mechanical Methods
- 12.3 Heat Guns
- 12.4 HEPA Vacuum Needle Gun
- 12.5 HEPA Vacuum Blasting
- 12.6 Component Demolition

- 12.7 Machine HEPA Sanding
- 12.8 Wet Sanding
- 12.9 Paint Removal Chemical Methods
- 12.10 Soil Abatement:

13. LEAD BASED PAINT ENCAPSULATION

- 13.1 Preparation of Surfaces General surface preparation instructions for all substrates: All surfaces to be encapsulated should be properly prepared so that all are clean, dry, sound, and deglossed at the time of application.
 - (a) Wash all areas to be encapsulated with manufacturer-approved leadspecific surface cleaner. Clean to the extent required to remove existing deteriorated coatings and any other foreign matter, paying particular attention to areas found under structural components such as eaves, beams, archways, etc.
 - (b) If necessary, oil, grease and similar surface contamination should be removed with any manufacturer-approved degreasing surface cleaner which is free-rinsing and does not require a neutralizer.
 - (c) Rinse surfaces with clean water. Avoid uncontrolled release of rinsate beyond the work area, as it may contain lead. Jurisdictional regulations for the management of rinsate (collection and disposal of waste liquids) can vary, and project-specific requirements are the responsibility of the installer.
 - (d) On representative surfaces, perform a "water-break" test to determine if traces of oil, grease, and similar hydrophobic contaminants are still present.
 - (e) Surfaces contaminated with mold, mildew, and/or other contaminant microorganisms (e.g., biofilms) should be examined carefully for sources of excess moisture and water-damage and thoroughly cleaned.
 - (f) If cleaned and dry surfaces continue to exhibit loose particulate residues, such as chalking, and dusting, attempt to remove post-cleaning residues with a HEPA vacuum.

- (g) Surface Drying After Cleaning:
 - a. Allow the surface to dry before applying an encapsulant.
 - b. The extent of drying after cleaning may be product specific, and the manufacturer will make specific guidance available

13.2 Application

- 13.2.1 Apply encapsulant only after the surface has been examined, assessed, prepared, cleaned, primed, and dried, as outlined in the surface assessment and preparation sections of this specification. Application of encapsulant to surfaces that are not clean, dry, sound, deglossed and properly primed as described will void all warranties.
- 13.2.2 Apply encapsulant at a wet mil film thickness that will yield the recommended minimum dry mil film thickness at which the submitted testing to ASTM E 1795-20a documents compliance with performance requirements mandated in regulations.
- 13.2.3 Wet mil film thickness should be measured throughout any encapsulation project using a wet mil gauge.

13.3 Methods of Application

- 13.3.1 Airless Spray: Encapsulants can be successfully applied with most major brands of airless spray equipment.
- 13.3.2 Roller: For best results apply with a 3/8" 1/2" nap roller (manufacturer recommendations may vary).
- 13.3.3 Brush: Apply liberally and uniformly with a polyester or nylon brush.

14. CLEARANCE PROCEDURES

14.1 Visual Inspection:

14.1.1 All surfaces from which paint has been removed and/or encapsulated will be visually examined by the Owner or its Representative. The Owner or its Representative will examine the bare surfaces to ensure that there is no visible residue. If residue remains, the Contractor shall re-clean the component prior to repeating the visual inspection.

- 14.1.2 If a building component has been removed and replaced, the Owner or its Representative will examine the work area to ensure that each building component specified for removal and replacement has been completely removed.
- 14.1.3 If a lead-based paint enclosure system has been installed, the Owner or its Representative will examine the mechanical fastening system used to hold the enclosure to the substrate to determine that the fastening system is adequate. All seams and edges in the enclosure will be examined to ensure that they are sealed to provide a dust tight system.
- 14.1.4 If a lead-contaminated soil abatement has been performed, the Owner or its Representative will examine the work area to ensure that no visible lead-based paint chips are present in the soil following the Work. The Owner or its Representative will examine all soil areas selected for abatement to document that each has been completely treated, or removed, as specified.
- 14.1.5 There shall be no evidence of settled dust following the Contractor's cleanup effort. Any settled dust present in the work area during the visual inspection provides sufficient evidence that the Contractor's cleanup effort was not adequate. The area immediately outside the containment will also be visually examined to confirm that no leaded dust or paint chips have been transferred outside the work area.

14.2 Lead Wipe Sampling:

- 14.2.1 Final Lead dust wipe clearance sampling will be performed by the Contractors Industrial Hygienist following the "Wipe Sampling for Settled Lead-Contaminated Dust" procedure as outlined in HUD's "Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing". Analysis of lead wipe samples shall be performed by an accredited laboratory using FLAA following NIOSH Modified Method 7082 or by ICP following Modified OSHA Method ID-125.
- 14.2.2 Decontamination shall be considered complete when every lead dust wipe sample is at or below the following levels (given in micrograms of lead per square foot):

Surface		Leaded Dust Loading (g/ft²)
Bare Floors		10
Interior Window Sills		100
Window Troughs		800
Exterior Concrete of Other Surfaces	^{or} Rough	800

14.2.3 The Contractor shall re-clean those areas which do not comply with the specified final clearance levels. Following recleaning efforts, visual inspection and clearance sampling shall be performed to ensure that the re-cleaning was effective. The Contractor is responsible for the cost incurred during re-cleaning activities and all clearance sampling costs.

14.2 Lead Soil Sampling:

- 14.2.1 Lead-in-soil sampling shall be performed generally Following an exterior lead-based paint abatement the Contractors Industrial Hygienist will collect a minimum composite soil samples following the procedures outlined in HUD's "Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing". Analysis of soil for lead shall be performed by an accredited laboratory by FLAA or ICP.
- 14.2.2 Decontamination shall be considered complete when each composite lead soil sample is at or below the following levels (given in micrograms of lead per gram of soil):

Soil Area	Lead in Soil Level (g/g)
High-Contact Public Areas	400
Child Care Play Areas	400
Other Soil Areas	1,200

14.2.3 If lead in soil levels are greater than or equal to the applicable limits, additional soil treatment may be required.

15. WASTE MANAGEMENT

15.1 General: The Contractor shall properly store and secure all waste at all times. Do not leave debris in the work area or in uncovered or unlocked trucks or dumpsters. Do not leave any waste in unsecured areas accessible to the public. Do not incinerate debris or use any unauthorized dumpster. Do not introduce lead-contaminated water into storm or sanitary sewers. Do not permit recycling of building components coated with lead-based paint.

15.2 Waste Management:

- 15.2.1 If the waste characterization of the samples sent for 8 RCRA TCLP resulted below the regulatory limit of 5 mg/L for lead; the waste generated during the lead-based paint abatement shall be removed and categorized as Non-Hazardous Special Waste for lead. If the results esceed the regulatory limit is shall be disposed as Hazardous Waste.
- 15.2.2 If required to perform additional 8 RCRA TCLP analysis the Contractor shall segregate abatement waste into distinct waste streams (e.g., disposable suits, lead-contaminated polyethylene sheeting, lead-contaminated wastewater, hazardous chemical sludge, etc.). Various combinations of each in different containers will not be accepted.
- 15.2.3 Lead-containing or lead-contaminated waste shall be considered as hazardous waste, and labeled in accordance with this specification, unless:
 - i. lead leachate concentrations of the waste are determined to be less than 5 ppm from representative bulk samples, by TCLP analysis.
 - ii. The waste does not meet any other regulatory definitions as "hazardous waste".
- 15.2.4 Waste tested which results in a lead leachate concentration of greater than or equal to 5 parts per million shall be

considered hazardous and shall be handled and disposed of as such according to local, state, and federal regulations.

- 15.2.5 The Contractor shall not accumulate hazardous waste on site for longer than 90 days.
- 15.3 Hazardous and non-hazardous waste shall be disposed according to all federal, state, and local regulations.

END OF SECTION

SECTION 06 20 00

CARPENTRY

For listing of subsections, see subsection index at end of

section. PART 1 - GENERAL

1.01 DESCRIPTION:

- A. Furnish and install the necessary materials to do finished carpentry as indicated and as specified.
- 1.02 RELATED WORK:
 - A. Section 09941: Field Painting
- 1.03 REFERENCES:
 - A. Federal Specifications:
 - 1. TT-W-535C, Wood Preservative: Fluorchrome Arsenate Phenol Mixture.
 - 2. TT-W-571I(2), Wood Preservation: Treating Practices.
 - B. American Wood Preserver's Association Standard for wood Pressure Treated with Water-Borne Preservatives, P5-78.
- 1.04 SUBMITTALS:
 - A. Treated Wood: Certificates of Compliance
- 1.05 DELIVERY, STORAGE, AND HANDLING: Deliver to jobsite and store off the ground in a manner to ensure proper drainage, ventilation, and protection from the weather.

PART 2 - PRODUCTS

- 2.01 LUMBER MATERIALS:
 - A. Provide lumber of grades and species indicated below for various uses listed:
 - 1. Nailers, cant strips and blocking: Standard grade
 - a. Douglas Fir, coast and inland.

- b. Fir, white
- c. Hemlock, eastern and west coast
- d. Spruce, eastern, Engelmann's and Sitka
- B. Sizes indicated are nominal.
- C. Dress four sides of lumber used in finish work.
- D. Moisture content of lumber:
 - 1. Kiln dried lumber not over 2-in. nominal thickness: Not to exceed 19 percent.
 - Lumber over 2-in. nominal thickness, not kiln dried: To conform to the rules of the association under which it is graded. Incorporate into structure without further seasoning.

2.02 WOOD PRESERVATIVES:

- A. For wood encased in or in contact with concrete or masonry, and wood items incorporated in the roofing, use preservatives conforming to following:
 - AWPA standard P5-78
 - 2. Federal Specification TT-W-

535C PART 3 - EXECUTION

3.01 INSTALLATION:

- A. Securely fasten and neatly fit carpentry with screws, nails, bolts, or spikes of ample size and suitable type.
 - 1. Secure wood work to masonry or other hard surfaces with expansion bolts and plugs or shield in a manner to provide rigid and permanent support.
 - 2. Countersink screws and bolts. Putty holes and sand smooth.
- B. Wood Nailers, Cants and Blocking:
 - 1. Anchor wood nailers with bolts and spike cant strips to nailer, as indicated, at edges of roofs and around roof openings.
 - 2. Install wood nailers in concrete bases under metal lockers.
 - 3. Provide wood blocking for base flashing and for pipe penetrations through roof, as indicated.

C. Wood Preservatives:

1. Apply preservatives in accordance with Federal Specification TT-W-571I(2), Treating Practices, Table III, Obtain notarized certificate of treatment from treatment company.

- 2. Prior to treatment, ensure that lumber is sawed to exact length and bored as required insofar as practicable.
- 3. Apply two heavy coats of preservative to any surfaces cut or bored after treatment, prior to installation.

PART 4 - SUBSECTION INDEX

A. GENERAL

- 1.01 Description
- 1.02 Related Work
- 1.03 References
- 1.04 Submittals
- 1.05 Delivery, Storage and Handling

B. PRODUCTS

- 2.01 Lumber Materials
- 2.02 Wood Preservatives

c. EXECUTION

3.01 Installation

* * *

SECTION 06 05 73 FIRE RETARDANT TREATED WOOD (FTRW) - PRESSURE TREATED WOOD

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Fire-retardant treatment of lumber and plywood.

1.2 RELATED SECTIONS

A. Section 06 20 00 - Carpentry.

1.3 REFERENCES

- A. ASTM International (ASTM):
 - ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
 - 2. ASTM A653 / A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
 - 3. ASTM D3201 Standard Test Method for Hygroscopic Properties of Fire-Retardant Wood and Wood-Base Products.
 - 4. ASTM D5516 Standard Test Method for Evaluating the Flexural Properties of Fire-Retardant Treated Softwood Plywood Exposed to Elevated Temperatures.
 - 5. ASTM D5664 Standard Test Method for Evaluating the Effects of Fire-Retardant Treatments and Elevated Temperatures on Strength Properties of Fire-Retardant Treated Lumber.
 - 6. ASTM D6305 Standard Practice for Calculating Bending Strength Design Adjustment Factors for Fire retardant Treated Plywood Roof Sheathing.
 - 7. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials.
- B. American Wood-Protection Association (AWPA):
 - AWPA E12 Standard Method of Determining the Corrosion of Metal in Contact with Wood.
 - 2. AWPA M4 Standard for the Care of Preservative Treated Wood Products.
 - 3. AWPA P5 Standard for Waterborne Preservatives.
 - 4. AWPA P17 Fire Retardant Formulations.
 - 5. AWPA P50 Standard for Fire Retardant FR-2 (FR-2).
 - 6. AWPA T1 Use Category System: Processing and Treatment Standard.
 - 7. AWPA U1 Use Category System: User Specification for Treated Wood.
- C. GREENGUARD Environmental Institute: GREENGUARD Green Certified Products.
- D. National Fire Protection Association (NFPA) 255 Method of Test of Surface Burning Characteristics of Building Materials.
- E. ESR 2645 D-Blaze Fire Retardant Treatment; International Code Council -Evaluation Service, ICC-ES.
- F. Underwriters Laboratories, Inc. (UL) 723 Tests for Surface Burning Characteristics of Building Materials.
- G. Hawaiian Local Building Code Standards.

1.4 SUBMITTALS

- A. Submit under provisions of Section 01 30 00 Administrative Requirements.
- B. Product Data: Manufacturer's instructions for use, including requirements for storage, cutting, and finishing.
- C. Preservative Treatment Certification: Treating plant's certification of compliance with specified standards, process employed, and preservative retention values.
- D. Fire-Retardant Treatment Certification: Treating plant's certification of compliance with specified requirements.

1.5 QUALITY ASSURANCE

- A. Wood Treatment Plant Qualifications: Wood treatment plant experienced in performing work of this section licensed by Viance, LLC.
- B. Source Quality: Obtain treated wood products from a single approved source.
- C. Preservative Treatment: Mark each piece of plywood and lumber to show compliance with specified standards.
- D. Fire-Retardant Treatment: Mark each piece of plywood and lumber to show compliance with specified standards.
- E. Regulatory Requirements: Provide fire retardant treatment which complies with the following regulatory requirements:
 - 1. International Building Code (IBC).
 - 2. International Residential Code (IRC).
 - 3. International Code Council Evaluation Service ICC-ES ESR 2645.
 - 4. City of Los Angeles, California RR24502.
 - 5. City of New York, New York Building Code, MEA 406 and MEA 407.
 - 6. Hawaiian Local Building Code Standards.
- F. Independent Third Party Inspection:
 - 1. Provide plant inspections.
- G. Low Chemical Emission Certification:
 - GREENGUARD Gold Certified.
- H. Kiln Dry after Treatment (KDAT): Provide kiln dry material as indicated or required.
 - 1. Kiln dry after treatment to 19 percent maximum moisture content for lumber and 18 percent for plywood in accordance with AWPA T1, Section 7 Drying After Treatment (lumber) and AWPA T1, Section :F: Pressure treated composites (3c) kiln drying after treatment.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Exposure: Prevent wood products against moisture and dimensional changes, in accordance with instructions from treating plant.

1.7 WARRANTY

A. Manufacturer's Warranty: Provide manufacturer's standard 50-year limited warranty for pressure-treated FRTW wood.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer:
- B. Substitutions: Following instructions on Drawing Set.

2.2 MATERIALS

- A. Finish Lumber and Plywood: As specified in Section 06 20 00 Finish Carpentry.
- B. Fasteners and Metal Hardware Provide corrosion resistant steel fasteners with hot-dip zinc coating per ASTM A153/A153M, provide corrosion resistant hardware per ASTM A653 / A653M Class G-185 in compliance with building code requirements.
- C. Fasteners used in D-Blaze Fire-Retardant Treated Wood: Use only code approved fasteners as specified in ICC-ES ESR 2645. Fasteners must be galvanized steel, stainless steel, silicon bronze or copper, in accordance with 2009 and 2006 IBC Section 2304.9.5, 2009 IRC Section R317.3 or 2006 IRC Section R319.3

2.3 FIRE RETARDANT PRESSURE TREATMENT OF LUMBER AND PLYWOOD

- A. Fire retardant treatment for wood, including roof and floor trusses, roof decks and sheathing; subflooring, beams and purlins, blocking and furring, studs, joists and paneling, architectural millwork and trim, interior non-load bearing partitions and exterior load-bearing walls.
 - 1. Lumber: Comply with AWPA U1 UCFA, Type A or ICC-ES ESR 2645.
 - 2. Plywood: Comply with AWPA U1, UCFA, Type A or ICC-ES ESR 2645.
 - 3. Surface Burning Characteristics: UL FR-S rating; or flame spread and smoke developed ratings of 25 or less in a test of 30 minutes' duration in accordance with IBC section 2303.2.
 - 4. Treatment: D-Blaze FRT as manufactured by Viance.
 - 5. Kiln dry after treatment to 19 percent maximum moisture content for lumber and 15 percent for plywood.
 - 6. Treat wood used for the following applications:
 - a. Roof and floor trusses.
 - b. Roof decks and sheathing.
 - c. Subflooring.
 - d. Beams and purlins.
 - e. Interior non-load bearing partitions.
 - f. Studs and joists.
 - g. Exterior load-bearing walls protected by weather barrier.
 - h. Millwork and trim.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Fire-Retardant Treated Wood:
 - Compliance: Comply with manufacturer's product data, including product technical bulletins, product catalog installation instructions and product carton instructions for installation.
 - 2. End cuts and drilling are permitted. Do not rip or mill lumber after fire-retardant treatment.

END OF SECTION

SECTION 06 300 00

EPOXY REPAIR FOR DETERIORATION AND DECAY IN WOODEN MEMBERS

SUMMARY

Deterioration and decay in wood are the result of moisture infiltration and the accompanying fungal growth and insect infestation. Moisture can enter wood from many sources including the original moisture in green wood, rainwater, condensation, ground water, piped water, and water released by water-conducting fungus through the process of decay itself. To arrest the decay process, the wood must be dried. When the wood dries, the fungus will die or go dormant. To repair wood that has been damaged by fungus, one can replace the damaged portion or restore it with epoxy consolidant and filler.

This work task will discuss the repair of decayed wood member by the use of epoxy materials. Where the replacement of decayed members is warranted and since the replacement techniques differ with the application of wood, the specific replacement specifications should be consulted.

A. WORK INSTRUCTIONS

1. INSPECTION

- (a) Rot can be detected with the 'Pick Test'. An ice pick is inserted into the wood at a slight angle. When the pick is lifted out, the wood should splinter in long pieces. If wood snaps where pick is being lifted, the wood is decayed. (figure 2)
- (b) When rot is discovered.
 - (1) The first thing to do is to find the source of the moisture infiltration and eliminate *it.* (*figure 3*) If rot is only present on the surface, drying is all that will be needed to stop the spread of decay and kill off any growth.
 - (2) If there is doubt about the source of moisture, the wood should be treated with a preservative. Preservatives are caustic chemicals and should be handled with care. A particularly dangerous wood preserving chemical is pentachlorophenol (a.k.a. penta). The use of it should be avoided.
 - (3) The use of a preservative will stop the growth of fungi; but it cannot restore material strength to an affected member. The member will have to be repaired with epoxy or replaced.

PREPARATION

- (a) Dry affected wood member completely. If complete drying is not possible in place, the member must be removed and kept in a cool dry place until dry. If this precaution is not taken, the epoxy can actually trap moisture in wood fibers and accelerate the decay process.
- (b) Organization and cleanliness are keys to proper epoxy repair. Have all materials at hand before the mixing process begins. Label all caps and lids so that a cap or lid is not placed on the wrong container or it will be stuck there forever. Putting all materials associated with one part of the

epoxy on the left and all associated with the other on the right helps keep things separated. Protect all adjacent surfaces from spills with plastic sheeting. If any epoxy happens to spill, wipe it up immediately before it sets or it will not come up.

EXECUTION

- (a) Drill 1/4' or 3/16' holes in affected wood to receive epoxy consolidant. (*figure 4*) Be sure not to drill through the entire surface for consolidant will leak out from behind. When working on a vertical surface, angle the holes so epoxy will not leak back out. Dam any surface cracks with oil clay so that epoxy will not leak.
- (b) Following manufacturer's instructions, mix a small amount of 'the consolidant components, the resin and the hardener, together in an applicator bottle. Stir the mixture thoroughly by hand with a thin stick for 4 minutes or with a bent coat hanger chucked into a drill for 2 minutes.
- (c) Carefully squirt the consolidant into the pre-drilled holes. (figure 5) The aim is to completely saturate the wood. Move from hole to hole refilling until the wood can hold no more. More than one application may be needed.
- (d) If severed pieces need to be re-attached, glue them in place with a mixture of consolidant and filler.;- (figure 6)
- (e) After the consolidant has cured, the voids in the surface can be filled with epoxy filler. If the voids are large, filler can be applied in succession, 1' of depth at a time. This cuts down on the possibility of problems associated with heat build-up.
- (f) Mixing of the two-part epoxy filler is similar to the consolidant. When mixed, the filler has the consistency of a glazing compound and can be worked with a putty knife. The surface of the filler should be built up slightly above of the wood surface to allow for planning and sanding smooth after it has cured.
- (g) After the filler has cured, the surface can be smoothed. (*figure* 7) A wood preservative can be applied to surrounding wood surfaces and the whole surface should be primed and painted properly.

c. RESOURCE REQUIREMENTS

1. MATERIALS

(a) Epoxy consolidant and epoxy filler, both a re multiple part compounds. It is recommended that it be purchased by the gallon unless a large amount of epoxying needs to be done.

2. EQUIPMENT

- (a) Plastic bottles, like those used for hair dye, to apply the consolidant; having many on hand is recommended. Cleaning of the bottles for reuse is possible.
- (b) Rags of different sizes to wipe up spills before epoxy has a chance to harden, small rags are recommended for quick one time uses such as wiping off spouts and caps.
- (c) Thin wooden sticks, approximately 8" long for scooping out paste and mixing consolidant.

- (d) Two pairs of medium-duty nitril rubber gloves and one box of disposable vinyl gloves for protection from contact with epoxy.
- (e) Goggles and a respirator for protection from fumes.
- (f) Oil clay that can be purchased from a hobby store used to keep consolidant from leaking through cracks.
- (g) Putty knives for application of filler.
- (h) Channel lock pliers for opening stuck caps.
- (i) Allen wrench to clean out cap holes.
- (j) Needle nose pliers to Pull out hardened epoxy.
- (k) 1/8" x 8' x I2' Masonite boards for mixing paste filler.
- (1) Because curing epoxy does create heat, have a carbon dioxide fire extinguisher on hand.

3. PRODUCTS/MANUFACTURERS

- (a) Epoxy materials are available from marine products stores, or
- (b) CONSERVATION SERVICES 8 Lakeside Trail Kinnelon, NJ 07405 (201) 838-6412

Con Serv (t) Flexible Consolidant 100 cures slowly with a 5 to 7 hour application time to allow deep penetration. Complete hardness is achieved in 3 to 6 days.

- (1) Bluestain occurs in sapwood and is generally not dangerous on its own. It is, though, an indicator of moisture and the possibility for more serious types of decay to occur. If wood is stained, it is already more vulnerable to further decay. The stain can be brown, blue, steel grey or black.
- (2) Mold or mildew is another form of decay that is not dangerous; but, it increases the susceptibility of wood to more serious types of decay. Mold occurs on the surface of wood and ranges from orange and pin through green and black on softwood and appears as black spots on hardwood.
- (3) Brown rot occurs as a result of fungi feeding on the cellulose of wood cell walls. It causes a rapid loss of strength and is characterized by the presence of cracks across the grain when the wood is dry. Brown rot primarily attacks softwoods such as pine, hemlock, fir, redwood, spruce, and cedar and it turns the color of decayed wood brown. Wood infested with brown rot will eventually shrink and collapse.
- (4) White rot fungi consume both the cellulose and the lignin of wood cell walls. It results in a gradual but steady loss of strength. With white rot, the wood appears to be bleached and, in the final stages, feels spongy. The bleached and non-bleached areas are usually,

- separated by black lines. Unlike brown rot, the wood does not develop checks across the grain. White rot usually attacks hardwoods such as mahogany, walnut, oak, maple, cherry, rosewood, and teak.
- (5) Soft rot usually affects only the surface of the wood and is therefore less dangerous. Soft rot occurs at surfaces that are frequently wet and appears as severe cracking both with and across the grain on the exterior. If sound wood is found after the surface of the wood is scraped away, then soft rot is the culprit.
- (6) Water-conducting rot or dry rot is the most dangerous type of decay. This type of rot is able to carry its own water supply across dry surfaces by a series of tentacles and inject sound wood with moisture to make it appetizing to fungi. The variety **poria incrassata** is the only type present in the United States and is confined to the Southeast. This type of rot can grow undetected within walls, revealing itself only after causing major damage.

2. HISTORIC STRUCTURE PRECAUTIONS

- (a) No smoking is allowed by repairs persons around historic structures.
- (b) If historic materials cannot be saved, the replacement piece must be an accurate duplicate of the original and installed using the exact manner as the original. If the original manner of installation is unknown, follow recognized standards.
- (c) All materials that are removed should be inconspicuously marked with the date and a symbol designating repair or maintenance.
- (d) Concealed carpentry need not duplicate the concealed historic material but must be of similar thickness to provide equivalent support, durability, and strength. If the historic work has a unique feature in the concealed carpentry, duplicate it.

SECTION 07 10 00 DAMPPROOFING AND WATERPROOFING

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Fluid-applied dampproofing.
- B. Fluid-applied waterproofing.

1.2 REFERENCES

- A. ASTM International (ASTM):
 - 1. ASTM C836 Standard Specification for High Solids Content, Cold Liquid-Applied Elastomeric Waterproofing Membrane for Use with Separate Wearing Course.
 - 2. ASTM D412 Tests for Rubber Properties in Tension
 - 3. ASTM D1187 Standard Specification for Asphalt-Base Emulsions for Use as Protective Coatings for Metal.
 - 4. ASTM D1227 Standard Specification for Emulsified Asphalt Used as a Protective Coating for Roofing.
 - 5. ASTM D4479 Standard Specification for Asphalt Roof Coatings Asbestos-Free.
 - 6. ASTM D4586 Standard Specification for Asphalt Roof Cement, Asbestos-Free.
 - 7. ASTM E96 Water Vapor Transmission of Materials.

B. Federal Specifications:

- 1. MIL-R-3472 Roof Coating, Asphalt Base Emulsion.
- 2. SS-A-694 Asphalt Roof Coating (Brushing & Spraying Consist).
- 3. SS-C-153 Cement, Bituminous, Plastic.
- 4. SS-R-1781 Roof-Coating, Asphalt-Base Emulsion.
- 5. SS-W-110 Water-Repellent Colorless, Silicone Resin Base.
- C. National Standard of Canada 37.58 M86.

1.3 SUBMITTALS

- A. Product Data: Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - 3. Installation methods.
- B. Warranty: Submit a sample warranty identifying the terms and conditions stated in Warranty article.

1.4 QUALITY ASSURANCE

- A. Applicator Qualifications: Applicator shall be experienced in applying the same or similar materials.
- B. Regulatory Requirements: Comply with applicable codes, regulations, ordinances, and laws regarding use and application of products that contain volatile organic compounds (VOC).
- C. Mock-Up: Provide a mock-up for evaluation of surface preparation techniques and

application workmanship.

- 1. Finish areas designated by Architect.
- 2. Do not proceed with remaining work until workmanship is approved by Architect.
- 3. Rebuild mock-up area as required to produce acceptable work.

1.5 PRE-INSTALLATION MEETINGS

- A. Pre-Installation Conference: Prior to beginning work, convene a conference to review conditions, installation procedures, schedules and coordination with other work.
- B. Convene minimum two weeks prior to starting work of this section.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to project site in original, factory-sealed, unopened containers bearing manufacturer's name and label intact and legible with following information.
 - 1. Name of material.
 - 2. Manufacturer's stock number and date of manufacture.
- B. Store materials in protected and well ventilated area. Handle materials to avoid damage.

1.7 PROJECT CONDITIONS

- A. Do not apply when surface temperature or weather conditions conflict with manufacturer's published requirements.
- B. Coordinate waterproofing work with other trades.
- C. Keep flammable products away from spark or flame. Do not allow the use of spark producing equipment during application and until all vapors have dissipated. Post "NO SMOKING" signs.
- D. Maintain work area in a neat and orderly condition, removing empty containers, rags, and rubbish daily from the site.

1.8 SEQUENCING

A. Ensure that products of this section are supplied to affected trades in time to prevent interruption of construction progress.

1.9 WARRANTY

A. Warranty: Provide manufacturer's standard limited material warranty.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Substitutions: See instructions on the Drawing Set.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Before work is started, applicator shall thoroughly examine all surfaces for any deficiencies.
- Notify Architect in writing of any defects.

3.2 SURFACE PREPARATION

- A. Surface should be free of oil, grease, dirt, laitance and loose material.
- B. Repair all cracks and holes as recommended by Manufacturer, before applying surface coating.

3.3 APPLICATION

- A. Comply with manufacturer recommendations and approved submittals. Mix as recommended by manufacturer.
- B. For fabric reinforced applications, apply first coat. Apply reinforcing fabric over the wet coating, overlapping all edges. Smooth out all wrinkles, to ensure there is no trapped air beneath fabric. Apply second coat.

END OF SECTION

SECTION 08 14 00 INTERIOR WOOD DOORS

Copyright 2018 - 2018 ARCAT, Inc. - All rights reserved

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Interior wood doors of the following types:
 - Contemporary doors.

1.2 REFERENCES

- A. American with Disabilities Act (ADA).
- B. National Fire Protection Association (NFPA): NFPA 80 Standard for Fire Doors and Other Opening Protectives.

1.3 SUBMITTALS

- A. Product Data: Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - Installation methods.
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
 - 1. Indicate locations of blocking and reinforcements required for installing wood doors.
- C. Verification Samples: For each finish product specified, two samples, representing actual product, color, and finish.
- D. Manufacturer's Certificates: Certify products meet or exceed specified requirements.
- E. Closeout Submittals: Provide manufacturer's maintenance instructions that include recommendations for periodic checking and adjustment, cleaning and maintenance of wood doors.

1.4 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Minimum five years experience in manufacturing wood doors.
- B. Installer: Experienced with installation of similar products, and acceptable to the manufacturer.
- C. Mock-Up: Provide a mock-up for evaluation of fabrication techniques and application workmanship.
 - 1. Install in areas designated by Architect.
 - 2. Do not proceed with remaining work until installation is approved by Architect.
 - 3. Rebuild mock-up until satisfactory results are achieved.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Store products in the manufacturer's unopened packaging until ready for installation.

B. Protect finished surfaces from soiling or damage during handling and installation.

1.6 PROJECT CONDITIONS

A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's recommended limits.

1.7 WARRANTY

A. Manufacturer's Warranty: Provide manufacturer's standard limited warranty for materials.

PART 2 PRODUCTS

2.1 MANUFACTURER

- A. Acceptable Manufacturer:
- B. Substitutions: See drawing instructions.

2.2 INTERIOR WOOD DOORS

- A. Contemporary Doors:
 - 1. Custom, refer to Drawings.

PART 3 EXECUTION

3.1 EXAMINATION AND PREPARATION

- A. Examine substrates for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Do not begin installation until substrates have been properly prepared.
- C. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.2 INSTALLATION

- A. Install products in strict accordance with manufacturer's instructions and approved submittals.
 - 1. Follow manufacturer's recommendations for attachment.
 - 2. Adjust to open and close smoothly and freely without binding.

3.3 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

END OF SECTION

DIVISION 9 - FINISHES

SECTION 09 30 00 - TILING

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Glazed Wall Tile.
- B. Ceramic Mosaic Tile.
- C. Paver Tile.
- D. Quarry Tile.
- E. Glass Mosaic Tile.
- F. Glass Tile.
- G. Waterproofing.
- H. Crack Isolation.
- I. Stone thresholds.
- J. Ceramic accessories.
- K. Ceramic trim.
- L. Non-ceramic trim.

1.3 REFERENCES

- A. ANSI A108.1A, 1999 Specifications for Installation of Ceramic Tile in the Wet-Set Method with Portland Cement Mortar.
- B. ANSI A108.1B, 1999 Specifications for Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set or Latex Portland Cement Mortar.

- C. ANSI A108.1C, 1999 Specifications for Contractors Option: Installation of Ceramic Tile in the Wet-Set Method with Portland Cement Mortar -or- Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set or Latex Portland Cement Mortar.
- D. ANSI A108.4, 1999 Specifications for Ceramic Tile Installed with Organic Adhesives or Water-Cleanable Tile Setting Epoxy Adhesive.
- E. ANSI A108.5, 1999 Specifications for Ceramic Tile Installed with Dry-Set Portland Cement Mortar or Latex-Portland Cement Mortar.
- F. ANSI A108.6, 1999 Specifications for Ceramic Tile Installed with Chemical-Resistant, Water-Cleanable Tile-Setting and -Grouting Epoxy.
- G. ANSI A108.8, 1999 Specifications for Ceramic Tile Installed with Chemical-Resistant Furan Mortar and Grout.
- H. ANSI A108.9, 1999 Specifications for Ceramic Tile Installed with Modified Epoxy Emulsion Mortar/Grout.
- I. ANSI A108.10, 1999 Specifications for Installation of Grout in Tilework.
- J. ANSI A118.1, 1999 Standard Specification for Dry-Set Portland Cement Mortar.
- K. ANSI A118.3, 1999 Chemical-Resistant, Water-Cleanable, Tile-Setting and -Grouting Epoxy and Water-Cleanable Tile-Setting Epoxy Adhesive.
- L. ANSI A118.4, 1999 Latex-Portland Cement Mortar.
- M. ANSI A118.5, 1999 Chemical-Resistant Furan Mortar and Grout.
- N. ANSI A118.6, 1999 Standard Ceramic Tile Grouts.
- O. ANSI A118.7, 1999 Polymer Modified Cement Grouts
- P. ANSI A118.8, 1999 Modified Epoxy Emulsion Mortar/Grout.
- Q. ANSI A118.9, 1999 Test Methods and Specifications for Cementitious Backer Units

- R. ANSI A118.10, 1999 Load bearing, Bonded, Waterproof Membranes for Thinset Ceramic Tile and Dimensional Stone.
- S. ANSI A118.11, 1999 Exterior Grade Plywood (EGP) Latex-Portland Cement Mortar.
- T. ANSI A136.1, 1999 Organic Adhesives for Installation of Ceramic Tile.
- U. ANSI A137.1, 1988 Specifications for Ceramic Tile.
- V. ASTM C50 Standard Specification for Portland Cement.
- W. ASTM C144 Standard Specification for Aggregate for Masonry Mortar.
- X. ASTM C207 Standard Specification for Hydrated Lime for Masonry Purposes.
- Y. ASTM C241 Test Method For Abrasion Resistance of Stone Subjected to Foot Traffic.
- Z. ASMT C503 Specification for Marble Building Stone (Exterior).
- AA. ASTM C615 Specification for Granite Dimension Stone.
- BB. ASTM C629 Specification for Slate Dimension Stone.
- CC. ASTM C847 Standard Specification for Metal Lath.
- DD. ASTM C1028 Test method for Determining the Static Coefficient of Friction or Ceramic Tile and Other Like Surfaces by the Horizontal Dynamometer Pull meter Method.
- EE. ASTM D4397 Specification for Polyethylene Sheeting for Construction, Industrial, and Agricultural Applications.
- FF. TCA (HB) Handbook for Ceramic Tile Installation; Tile Council of America, Inc.

1.4 PERFORMANCE REQUIREMENTS

- A. Static Coefficient of Friction: Tile on walkway surfaces shall be provided with the following values as determined by testing in conformance with ASTM C 1028.
 - 1. Level Surfaces: Minimum of 0.6 (Wet).

- 2. Step Treads: Minimum of 0.6 (Wet).
- 3. Ramp Surfaces: Minimum of 0.8 (Wet).

1.5 SUBMITTALS

- A. Submit under provisions of Section 01 30 00.
- B. Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - Installation methods.
- C. Shop Drawings: Indicate tile layout, patterns, color arrangement, perimeter conditions, junctions with dissimilar materials, control and expansion joints, thresholds, ceramic accessories, and setting details.
- D. Selection Samples: Color charts illustrating full range of colors and patterns.
- E. Selection Samples: Samples of actual tiles for selection.
- F. Samples: Mount tile and apply grout on two plywood panels, 36 by 36 inch in size illustrating pattern, color variations, and grout joint size variations.
- G. Manufacturer's Certificate:
 - Certify that products meet or exceed specified requirements.
 - 2. For each shipment, type and composition of tile provide a Master Grade Certificate signed by the manufacturer and the installer certifying that products meet or exceed the specified requirements of ANSI A137.1.
- H. Maintenance Data: Include recommended cleaning methods, cleaning materials, stain removal methods, and polishes and waxes.

1.6 QUALITY ASSURANCE

- A. Maintain one copy each of all Referenced standards and specifications on site. Include the TCA Handbook, ANSI A108 Series, ANSI A118 Series ANSI A136.1 and ANSI A137.1 and others as specified under paragraph References.
- B. Installer Qualifications: Company specializing in performing the work of this section with minimum 10 years experience.
- C. Single Source Responsibility:

- 1. Obtain each type and color of tile from a single source.
- 2. Obtain each type and color of mortar, adhesive and grout from the same source.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store products in manufacturer's unopened packaging until ready for installation.
- B. Protect adhesives and liquid additives from freezing or overheating in accordance with manufacturer's instructions.
- C. Store tile and setting materials on elevated platforms, under cover and in a dry location and protect from contamination, dampness, freezing or overheating.

1.8 ENVIRONMENTAL REQUIREMENTS

- A. Do not install adhesives in an unventilated environment.
- B. Maintain ambient and substrate temperature of 50 degrees F (10 degrees C) during installation of mortar materials.

1.9 EXTRA MATERIALS

A. Provide 200 sq ft of each size, color, and surface finish of tile specified.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer: As shown on drawings.
- B. Requests for substitutions will be considered in accordance with provisions of Section 01 60 00.

2.2 TILE

A. General: Provide tile that complies with ANSI A137.1 for types, compositions and other characteristics indicated. Provide tile in the locations and of the types colors and pattern indicated on the Drawings and identified in the Schedule and the end of this Section. Tile shall also be provided in accordance with the following:

- 1. Factory Blending: For tile exhibiting color variations within the ranges selected under Submittal of samples, blend tile in the factory and package so tile taken from one package shows the same range of colors as those taken from other packages.
- 2. Mounting: For factory mounted tile, provide back or edge mounted tile assemblies as standard with the manufacturer, unless otherwise specified.
- 3. Factory Applied Temporary Protective Coatings: Where indicated under tile type, protect exposed surfaces of tile against adherence of mortar and grout by precoating with a continuous film of petroleum paraffin wax applied hot. Do not coat unexposed tile surfaces.

2.3 SETTING MATERIALS

- A. Organic Adhesive: ANSI A136.1, thinset bond type; use Type I in areas subject to prolonged moisture exposure.
- B. Epoxy Adhesive: ANSI A118.3, thinset bond type.
- C. Mortar Bed Materials:
 - 1. Portland cement: ASTM C150, type 1, gray or white.
 - 2. Hydrated Lime: ASTM C207, Type S.
 - 3. Sand: ASTM C144, fine.
 - 4. Latex additive: As approved.
 - 5. Water: Clean and potable.
- D. Mortar Bond Coat Materials:
 - 1. Dry-Set Portland Cement type: ANSI A118.1.
 - 2. Latex-Portland Cement type: ANSI A118.4.
 - 3. Epoxy: ANSI A118.3, 100 percent solids.
- E. Standard Grout: Cement grout, sanded or unsanded, as specified in ANSI A118.6; color as selected.
- F. Polymer modified cement grout, sanded or unsanded, as specified in ANSI A118.7; color as selected.
- G. Epoxy Grout: ANSI A118.8, 100 percent solids epoxy grout; color as selected.
- H. Silicone Sealant: Silicone sealant, moisture and mildew resistant type, white; use for shower floors and shower walls.
- I. Cleavage Membrane:

- 1. No. 15 (6.9 kg) asphalt saturated felt, ASTM D226, Type 1.
- 2. Polyethylene film, ASTM D4397, 4.0 mil thickness.
- J. Waterproofing Membrane at Floors: Membrane in accordance with ANSI A118.10 and as follows:
 - 1. Chlorinated Polyethylene Sheet with polyester fabric reinforcing.
 - 2. Fabric Reinforced, Fluid-Applied elastomeric membrane.
 - 3. Un-Reinforced, Fluid-Applied elastomeric membrane.
 - 4. Polyethylene Sheet Product...
 - 5. Fabric-Reinforced, Modified-Bituminous Sheet Product.
 - 6. Urethane Waterproofing and Tile-Setting Adhesive Product.
- K. Membrane at Walls: No. 15 (6.9 kg) asphalt saturated felt, ASTM D226, Type 1.
- L. Membrane at Walls: 4 mil (0.1 mm) thick polyethylene film, ASTM D4397.
- M. Membrane at Walls: Reinforced asphalt paper.
- N. Reinforcing Mesh: 2 by 2 inch (50 by 50 mm) size weave of 16/16 wire size; welded fabric, galvanized.
- O. Metal Lath: ASTM C847, Flat expanded diamond mesh, not less than 2.5 lbs/SY, galvanized finish.
- P. Cementitious Backer Board: ANSI A118.9; High density, cementitious, glass fiber reinforced with 2 inch (50 mm) wide coated glass fiber tape for joints and corners:
 - 1. Thickness: 1/4 inch (6 mm).
 - 2. Thickness: 1/2 inch (13 mm).
 - 3. Thickness: 5/8 inch (16 mm).

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that wall surfaces are free of substances which would impair bonding of setting materials, smooth and flat within tolerances specified in ANSI A137.1, and are ready to receive tile.
- B. Verify that sub-floor surfaces are dust-free, and free of substances which would impair bonding of setting materials to sub-floor surfaces,

- and are smooth and flat within tolerances specified in ANSI A137.1.
- C. Verify that concrete sub-floor surfaces are ready for tile installation by testing for moisture emission rate and alkalinity; obtain instructions if test results are not within limits recommended by tile manufacturer and setting materials manufacturer.
- D. Verify that required floor-mounted utilities are in correct location.

3.2 PREPARATION

- A. Protect surrounding work from damage.
- B. Remove any curing compounds or other contaminates.
- C. Vacuum clean surfaces and damp clean.
- D. Seal substrate surface cracks with filler. Level existing substrate surfaces to acceptable flatness tolerances.
- E. Install cementitious backer board in accordance with ANSI A108.11 and board manufacturer's instructions. Tape joints and corners, cover with skim coat of dry-set mortar to a feather edge.
- F. Prepare substrate surfaces for adhesive installation in accordance with adhesive manufacturer's instructions.

3.3 INSTALLATION - GENERAL

- A. Install tile and grout in accordance with applicable requirements of ANSI A108.1 through A108.13, manufacturer's instructions, and TCA Handbook recommendations.
- B. Lay tile to pattern indicated. Arrange pattern so that a full tile or joint is centered on each wall and that no tile less than 1/2 width is used. Do not interrupt tile pattern through openings.
- C. Cut and fit tile to penetrations through tile, leaving sealant joint space. Form corners and bases neatly. Align floor joints.
- D. Place tile joints uniform in width, subject to variance in tolerance allowed in tile size. Make joints watertight, without voids, cracks, excess mortar, or excess grout.
- E. Form internal angles square and external angles bullnosed.

- F. Install ceramic accessories rigidly in prepared openings.
- G. Install non-ceramic trim in accordance with manufacturer's instructions.
- H. Install thresholds where indicated.
- I. Sound tile after setting. Replace hollow sounding units.
- J. Keep expansion joints free of adhesive or grout. Apply sealant to joints.
- K. Allow tile to set for a minimum of 48 hours prior to grouting.
- L. Grout tile joints. Use standard grout unless otherwise indicated.
- M. Apply sealant to junction of tile and dissimilar materials and junction of dissimilar planes.

3.4 INSTALLATION - FLOORS - THIN-SET METHODS

- A. Over exterior concrete substrates, install in accordance with TCA Handbook Method F102, with standard grout.
- B. Over interior concrete substrates, install in accordance with TCA Handbook Method F113, dry-set or latex-portland cement bond coat, with standard grout, unless otherwise indicated.
 - Where waterproofing membrane is indicated, install in accordance with TCA Handbook Method F122, with latexportland cement grout.
 - 2. Where epoxy bond coat and grout are indicated, install in accordance with TCA Handbook Method F131.
- C. Over wood substrates, install in accordance with TCA Handbook Method F142, with standard grout, unless otherwise indicated.
 - 1. Where epoxy bond coat and grout are indicated, install in accordance with TCA Handbook Method F143.

3.5 INSTALLATION - FLOORS - MORTAR BED METHODS

- A. Over exterior concrete substrates, install in accordance with TCA F101, bonded, with standard grout.
- B. Over interior concrete substrates, install in accordance with TCA Handbook Method F111, with cleavage membrane, unless otherwise indicated.

- 1. Where waterproofing membrane is indicated, with standard grout or no mention of grout type, install in accordance with TCA Handbook Method F121.
- 2. Where epoxy bond coat and grout are indicated, install in accordance with TCA Handbook Method F132, bonded.
- 3. Where epoxy or furan grout is indicated, but not epoxy or furan bond coat, install in accordance with TCA Handbook Method F114, with cleavage membrane.
- C. Over wood substrates, install in accordance with TCA Handbook method F141, with standard grout, unless otherwise indicated.
- D. Cleavage Membrane: Lap edges and ends.
- E. Waterproofing Membrane: Install as specified in ANSI A108.13.
- F. Mortar Bed Thickness: 1-1/4 to 2 inch (32 to 51 mm) maximum, unless otherwise indicated.

3.6 INSTALLATION - SHOWERS AND BATHTUB WALLS

- A. At tiled shower receptors install in accordance with TCA Handbook Method B415, mortar bed floor, and W244, thin-set over cementitious backer unit walls.
- B. At bathtub walls install in accordance with TCA Handbook Method B412, over cementitious backer units with waterproofing membrane.
- C. Grout with standard grout as specified above.
- D. Seal joints between tile work and other work with sealant specified in Section 07 92 00.

3.7 INSTALLATION - WALL TILE

- A. Over cementitious backer units on studs, install in accordance with TCA Handbook Method W244, using membrane at toilet rooms.
- B. Over cementitious backer units install in accordance with TCA Handbook Method W223, organic adhesive.
- C. Over gypsum wallboard on wood or metal studs install in accordance with TCA Handbook Method W243, thin-set with dry-set or latexportland cement bond coat, unless otherwise indicated.
 - 1. Where mortar bed is indicated, install in accordance with TCA Handbook Method W222, one coat method.

- 2. Where waterproofing membrane is indicated other than at showers and bathtub walls, install in accordance with TCA Handbook Method W222, one coat method.
- D. Over interior concrete and masonry install in accordance with TCA Handbook Method W202, thin-set with dry-set or latex-portland cement bond coat.
- E. Over wood studs without backer install in accordance with TCA Handbook Method W231, mortar bed, with membrane where indicated.
- F. Over metal studs without backer install in accordance with TCA Handbook Method W241, mortar bed, with membrane where indicated.

3.8 CLEANING

A. Clean tile and grout surfaces.

3.9 PROTECTION OF FINISHED WORK

- A. Do not permit traffic over finished floor surface for 72 hours after installation.
- B. Cover floors with kraft paper and protect from dirt and residue from other trades.
- C. Where floor will be exposed for prolonged periods cover with plywood or other similar type walkways

END OF SECTION

SECTION 09 90 00 INTERIOR, EXTERIOR AND INDUSTRIAL PAINTS AND COATINGS

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Interior paint and coatings systems (LEED-09 NC/CI/CS Compliant) including surface preparation.
- B. Interior high-performance paint and coatings systems including surface preparation.
- C. Exterior paint and coatings systems including surface preparation.

1.2 RELATED SECTIONS

- A. Section 03 30 00 Cast-in-Place Concrete.
- B. Section 04 20 00 Unit Masonry: Concrete Masonry Units (CMU) and brick.
- C. Section 05 50 00 Metal Fabrications.
- D. Section 06 20 00 Finish Carpentry.
- E. Section 06 40 00 Architectural Woodwork.
- F. Section 08 11 13.16 Custom Hollow Metal Doors and Frames.

1.3 REFERENCES

- A. Steel Structures Painting Council (SSPC):
 - 1. SSPC-SP 1 Solvent Cleaning.
 - 2. SSPC-SP 2 Hand Tool Cleaning.
 - 3. SSPC-SP 3 Power Tool Cleaning.
 - 4. SSPC-SP5/NACE No. 1, White Metal Blast Cleaning.
 - 5. SSPC-SP6/NACE No. 3, Commercial Blast Cleaning.
 - 6. SSPC-SP7/NACE No. 4, Brush-Off Blast Cleaning.
 - 7. SSPC-SP10/NACE No. 2, Near-White Blast Cleaning.
 - 8. SSPC-SP11, Power Tool Cleaning to Bare Metal.
 - SSPC-SP12/NACE No. 5, Surface Preparation and Cleaning of Metals by Waterjetting Prior to Recoating.
 - 10. SSPC-SP 13 / NACE No. 6 Surface Preparation for Concrete.
- B. Material Safety Data Sheets / Environmental Data Sheets: Per manufacturer's MSDS/EDS for specific VOCs (calculated per 40 CFR 59.406). VOCs may vary by base and sheen.
- C. South Coast Air Quality Management District (SCAQMD): Rule 1113 Architectural Coatings.
- D. Green Seal. Inc.:
 - 1. GS-11 Standard for Paints and Coatings (1st Edition, May 20,1993).
 - 2. GC-03 Environmental Criteria for Anti-Corrosive Paints.

E. United States Green Building Council (USGBC): LEED-09 NC/CI/CS.

1.4 SUBMITTALS

- A. Product Data: For each paint system indicated, including.
 - Product characteristics.
 - 2. Surface preparation instructions and recommendations.
 - 3. Primer requirements and finish specification.
 - 4. Storage and handling requirements and recommendations.
 - 5. Application methods.
 - 6. Cautions for storage, handling and installation.
- B. Selection Samples: Submit a complete set of color chips that represent the full range of manufacturer's products, colors and sheens available.
- C. Verification Samples: For each finish product specified, submit samples that represent actual product, color, and sheen.
- D. Only submit complying products based on project requirements (i.e. LEED). One must also comply with the regulations regarding VOCs (CARB, OTC, SCAQMD, LADCO). To ensure compliance with district regulations and other rules, businesses that perform coating activities should contact the local district in each area where the coating will be used.

E. USGBC LEED V4 Submittals:

- 1. MRc2 Environmental Product Declaration Product Language: Products shall be selected with a preference to products that have product-specific environmental product declaration documentation.
- 2. EQc2 Low Emitting Materials: The VOC content of all adhesives, sealants, paints and coatings in this Section shall not exceed the VOC limits established in Division 01 Sustainable Design sections.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: A firm or individual experienced in applying paints and coatings similar in material, design, and extent to those indicated for this Project, whose work has resulted in applications with a record of successful in-service performance.
- B. Paint exposed surfaces. If a color of finish, or a surface is not specifically mentioned, Architect will select from standard products, colors and sheens available.
- C. Do not paint prefinished items, concealed surfaces, finished metal surfaces, operating parts, and labels unless indicated.
- D. Mock-Up: Provide a mock-up for evaluation of surface preparation techniques and application workmanship.
 - 1. Finish surfaces for verification of products, colors and sheens.
 - 2. Finish area designated by Architect.
 - 3. Provide samples that designate primer and finish coats.
 - 4. Do not proceed with remaining work until the Architect approves the mock-up.

5.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Delivery: Deliver manufacturer's unopened containers to the work site. Packaging shall bear the manufacturer's name, label, and the following list of information.
 - 1. Product name, and type (description).
 - 2. Application and use instructions.
 - 3. Surface preparation.

- 4. VOC content.
- 5. Environmental handling.
- 6. Batch date.
- 7. Color number.
- B. Storage: Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.
- C. Store materials in an area that is within the acceptable temperature range, per manufacturer's instructions. Protect from freezing.
- D. Handling: Maintain a clean, dry storage area, to prevent contamination or damage to the coatings.

1.7 PROJECT CONDITIONS

A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's recommended limits.

1.8 EXTRA MATERIALS

- A. Furnish extra paint materials from the same production run as the materials applied and in the quantities described below. Package with protective covering for storage and identify with labels describing contents. Deliver extra materials to Owner.
- B. Furnish Owner with an additional one percent of each material and color, but not less than 1 gal (3.8 l) or 1 case, as appropriate.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer: As specified in drawings.
- B. Substitutions: See Drawing Instructions.

2.2 APPLICATIONS/SCOPE

- A. Interior Paints and Coatings:(LEED-09 NC/CI/CS COMPLIANT)
 - 1. Concrete: Poured, precast, tilt-up, cast-in-place, cement board, plaster.
 - 2. Concrete: Floors (Non-Vehicular).
 - 3. Masonry: Concrete masonry units, including split-face, scored, and smooth block.
 - 4. Metal: Aluminum, galvanized steel.
 - 5. Metal: Structural steel, joists, trusses, beams, partitions and similar items.
 - 6. Wood: Walls, ceilings, doors, trim and similar items.
 - 7. Drywall: Drywall board, Gypsum board.
- B. Interior High Performance Paints and Coatings:
 - 1. Concrete: Poured, precast, tilt-up, cast-in-place, cement board.
 - 2. Concrete: Ceilings.
 - 3. Masonry: CMU concrete, split face, scored, smooth, stucco.
 - 4. Non-Ferrous Metal: Galvanized steel and aluminum.
 - 5. Metal Ferrous: Ceilings, structural steel, joists, trusses, beams, and similar items including dryfall coatings.
 - 6. Wood: Walls, ceilings, doors, trim, cabinet work, and similar items.
 - 7. Drywall: Drywall board, Gypsum board
 - 8. Plaster: Walls, ceilings.

- C. Exterior Paints and Coatings:
 - Concrete: Cementitious siding, flexboard, transite, and shingles (non-roof).
 - 2. Masonry: Concrete masonry units, cinder or concrete block.
 - 3. Concrete: Concrete floors, patios, porches, steps and platforms, (non-vehicular).
 - 4. Metal: Aluminum, galvanized steel.
 - 5. Metal: Miscellaneous iron, ornamental iron, ferrous metal.
 - 6. Wood: Floors (non-vehicular), and platforms.
 - 7. Wood: Siding, trim, shutters, sash, and miscellaneous hardboard.
 - 8. Architectural PVC, plastic, fiberglass.
 - 9. Drywall: Gypsum board, and exterior drywall.
 - 10. Vinyl: Siding, EIFS, synthetic stucco.

2.3 PAINT MATERIALS - GENERAL

- A. Paints and Coatings:
 - 1. Unless otherwise indicated, provide factory-mixed coatings. When required, mix coatings to correct consistency in accordance with manufacturer's instructions before application. Do not reduce, thin, or dilute coatings or add materials to coatings unless such procedure is specifically described in manufacturer's product instructions.
 - For opaque finishes, tint each coat including primer coat and intermediate coats, onehalf shade lighter than succeeding coat, with final finish coat as base color. Or follow manufactures product instructions for optimal color conformance.
- B. Primers: Where the manufacturer offers options on primers for a particular substrate, use primer categorized as "best" by the manufacturer.
- C. Coating Application Accessories: Provide all primers, sealers, cleaning agents, cleaning cloths, sanding materials, and clean-up materials required, per manufacturer's specifications.
- D. Color: Refer to Finish Schedule for paint colors, and as selected.
- E. LEED Requirements: Products in compliance with requirements of IEQ Credit 4.2 USGBC LEED-09 NC/CI/CS.

2.4 INTERIOR PAINT SYSTEMS (LEED-V4 NC/CI/CS COMPLIANT)

- A. CONCRETE Walls and Ceilings, Poured Concrete, Precast Concrete, Unglazed Brick, Cement Board, Tilt-Up, Cast-In-Place including Plaster Walls and Ceilings.
 - Latex Systems:
 - a. Gloss Finish High Performance:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Gloss Acrylic Coating, B66-600 Series.
 - 3) 3rd Coat: S-W Pro Industrial Gloss Acrylic Coating, B66-600 Series (6.0 mils wet, 2.5 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series (4 mils wet, 1.6 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Harmony Interior Latex Semi-Gloss, B10 Series.

- 3) 3rd Coat: S-W Harmony Interior Latex Semi-Gloss, B10 Series (4 mils wet, 1.4 mils dry per coat).
- d. Semi-Gloss Finish High Performance:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Semi-Gloss Acrylic Coating, B66-650 Series.
 - 3) 3rd Coat: S-W Pro Industrial Semi-Gloss Acrylic Coating, B66-650 Series (6.0 mils wet, 2.5 mils dry per coat)
- e. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series (4 mils wet, 1.7 mils dry per coat).
- f. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Harmony Interior Latex Eg-Shel, B9 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Eg-Shel, B9 Series (4 mils wet, 1.7 mils dry per coat).
- g. Eg-Shel Finish, Microbicidal Paint:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200(50-100 sq ft/gal).
 - 2nd Coat: S-W Paint Shield Microbicidal Paint, D12W51 (4 mils wet, 1.8 mils dry per coat).
 - 3) 3rd Coat: S-W Paint Shield Microbicidal Paint, D12W51 (4 mils wet, 1.8 mils dry per coat).
- h. Low Sheen Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series (4 mils wet, 1.6 mils dry per coat).
- i. Low Sheen Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Gloss Eg-Shel, B41-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Low Gloss Eg-Shel, B41-2600 Series (4 mils wet, 1.6 mils dry per coat).
- j. Flat Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series (4 mils wet, 1.6 mils dry per coat).
- k. Flat Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Harmony Interior Latex Flat, B5 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Flat, B5 Series (4 mils wet, 1.8 mils dry per coat).
- 2. Alkyd Systems (Water based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8

- mils wet, 3.2 mils dry).
- 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series.
- 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series (4 mils wet, 1.7 mils dry per coat).

b. Gloss Finish:

- 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
- 2) 2nd Coat: Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
- 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4 mils wet, 1.7 mils dry per coat).

c. Semi-Gloss Finish:

- 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
- 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series.
- 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series (4 mils wet, 1.7 mils dry per coat).

d. Semi-Gloss Finish:

- 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
- 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
- 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).

e. Eg-Shel Finish:

- 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
- 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Eg-Shel, B33-8200 Series.
- 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Eg-Shel, B33-8200 Series (4 mils wet, 1.4 mils dry per coat).

f. Low Sheen Finish:

- 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
- 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
- 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).

3. Epoxy Systems (Water Based):

a. Gloss Finish:

- 1) 1st Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15.
- 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15 (6 mils wet,2.5 mils dry per coat).

b. Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series.
- 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series (5 mils wet, 2.0 mils dry per coat).

c. Semi-Gloss Finish:

- 1) 1st Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25.
- 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25 (6 mils wet, 2.5 mils dry per coat).

d. Semi-Gloss Finish:

1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8

- mils wet, 3.2 mils dry).
- 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series.
- 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series (4 mils wet, 1.5 mils dry per coat).
- e. Eg-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series (4 mils wet, 1.5 mils dry per coat).
- f. Eg-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series.
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series (5 mils wet, 2.0 mils dry per coat).
- B. CONCRETE: Ceilings, Poured Concrete, Precast Concrete, Cement Board, Cast-In-Place including Plaster Ceilings.
 - 1. Dryfall Waterborne Topcoats:
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series.
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (5.8 mils wet, 2.3 mils dry per coat).
 - b. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series.
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (6 mils wet, 1.9 mils dry per coat).
 - c. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series.
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (6 mils wet, 1.7 mils dry per coat).
- C. MASONRY: CMU Concrete, Split Face, Scored, Smooth, High Density, Low Density, Fluted.
 - 1. Latex Systems:
 - a. Gloss Finish High Performance:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W Pro Industrial Gloss Acrylic Coating, B66-600 Series.
 - 3) 3rd Coat: S-W Pro Industrial Gloss Acrylic Coating, B66-600 Series (6.0 mils wet, 2.5 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/qal).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series (4 mils wet, 1.6 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W Harmony Interior Latex Semi-Gloss, B10 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Semi-Gloss, B10 Series (4 mils wet, 1.4 mils dry per coat).
 - d. Semi-Gloss Finish High Performance:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W Pro Industrial Semi-Gloss Acrylic Coating, B66-650

- Series.
- 3) 3rd Coat: S-W Pro Industrial Semi-Gloss Acrylic Coating, B66-650 Series (6.0 mils wet, 2.5 mils dry per coat).
- e. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series.
 - 3rd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series (4 mils wet, 1.7 mils dry per coat).
- f. Eg-Shel / Satin Finish:
 - 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W Harmony Interior Latex Eg-Shel, B9 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Eg-Shel, B9 Series (4 mils wet, 1.7 mils dry per coat).
- g. Eg-Shel Finish, Microbicidal Paint:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
 - 2) 2nd Coat: S-W Paint Shield Microbicidal Paint, D12W51 (4 mils wet, 1.8 mils dry per coat.
 - 3) 3rd Coat: S-W Paint Shield Microbicidal Paint, D12W51 (4 mils wet, 1.8 mils dry per coat).
- h. Low Sheen Finish:
 - 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series (4 mils wet, 1.6 mils dry per coat).
- i. Low Sheen Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Gloss Eg-Shel, B41-2600 Series.
 - 3) 3rd Coat: S-W 200 Zero VOC Latex Low Gloss Eg-Shel, B41-2600 Series (4 mils wet, 1.6 mils dry per coat).
- j. Flat Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series (4 mils wet, 1.6 mils dry per coat).
- k. Flat Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W Harmony Interior Latex Flat, B5 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Flat, B5 Series (4 mils wet, 1.6 mils dry per coat).
- 2. Alkyd Systems (Water based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
 - 2) 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series (4 mils wet, 1.7 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).

- c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
 - 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series (4 mils wet, 1.7 mils dry per coat).
- d. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- e. Eg-Shel Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
 - 2) 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Eg-Shel, B33-8200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Eg-Shel, B33-8200 Series (4 mils wet, 1.4 mils dry per coat).
- f. Low Sheen Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- 3. Epoxy Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
 - 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15.
 - 3) 3rd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15 (6.0 mils wet, 2.5 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series (5.0 mils wet, 2.0 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
 - 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/B60V25.
 - 3) 3rd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25 (6.0 mils wet, 2.5 mils dry per coat).
 - d. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series (4 mils wet, 1.5 mils dry per coat).
 - e. Eq-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sg ft/gal).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series.
 - 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series (4.0 mils wet, 1.5 mils dry per coat).
 - f. Eg-Shel/Low Luster Finish:

- 1) 1st Coat: S-W Loxon Block Surfacer, A24W200 (50-100 sq ft/gal).
- 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series.
- 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series (5.0 mils wet, 2.0 mils dry per coat).

D. METAL: Aluminum, Galvanized.

- 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Latex Gloss Enamel, B21-2200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Latex Gloss Enamel, B21-2200 Series (4.0 mils wet, 1.5 mils dry per coat).
 - b. Gloss Finish High Performance:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series (6-10 mils wet, 2.5-4.0 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series (4.0 mils wet, 1.6 mils dry per coat).
 - d. Semi-Gloss Finish High Performance:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series (6-10 mils wet, 2.5-4.0 mils dry per coat).
 - e. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series.
 - 3rd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series (4 mils wet, 1.7 mils dry per coat).
 - f. Eg-Shel / Satin Finish High Performance:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel (6-10 mils wet, 2.5-4.0 mils dry per coat).
 - g. Low Sheen Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series (4 mils wet, 1.6 mils dry per coat).
 - h. Low Sheen Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Gloss Eg-Shel, B41-

- 2600 Series.
- 3) 3rd Coat: S-W 200 Zero VOC Latex Low Gloss Eg-Shel, B41-2600 Series (4 mils wet, 1.6 mils dry per coat).

i. Flat Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series.
- 3rd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series (4 mils wet, 1.6 mils dry per coat).

j. Flat Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Harmony Interior Latex Flat, B5 Series.
- 3) 3rd Coat: S-W Harmony Interior Latex Flat, B5 Series (4 mils wet, 1.8 mils dry per coat).

2. Alkyd Systems (Water based):

- a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series (4 mils wet, 1.7 mils dry per coat).

b. Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
- 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).

c. Semi-Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series.
- 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series (4 mils wet, 1.7 mils dry per coat).

d. Semi-Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
- 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).

e. Low Sheen Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
- 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).

3. Epoxy Systems (Water Based):

a. Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15.

- 3) 3rd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15 (6.0 mils wet. 2.5 mils dry per coat).
- b. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series (5.0 mils wet, 2.0 mils dry per coat).
- c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25.
 - 3) 3rd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25 (6.0 mils wet, 2.5 mils dry per coat).
- d. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series (4 mils wet, 1.5 mils dry per coat).
- e. Eg-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series (4 mils wet, 1.5 mils dry per coat).
- f. Eq-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series (5.0 mils wet, 2.0 mils dry per coat).
- 4. Urethane System (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Waterbased Acrolon 100, B65-720 series.
 - 3) 3rd Coat: S-W Waterbased Acrolon 100, B65-720 series (4.0 mils wet, 2.0 mils dry per coat).
- E. METAL: Galvanized; Ceilings, Duct work.
 - Multi-Surface Acrylic Coating System:
 - a. Gloss Finish High Performance:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic, B66-1500 Series.
 - 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic, B66-1500 Series (5.0 mils wet, 2.0 mils dry per coat).
 - 2. Dryfall Waterborne Topcoats:
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (5.8 mils wet, 2.3 mils dry per coat).
 - b. Eg-Shel Finish:

- 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series.
- 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (6.0 mils wet, 1.9 mils dry per coat).
- c. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series.
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (6.0 mils wet, 1.7 mils dry per coat).
- F. METAL (Structural Steel Columns, Joists, Trusses, Beams, Miscellaneous and Ornamental Iron, Structural Iron, Ferrous Metal)
 - Latex Systems:
 - a. Gloss Finish High Performance:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series (6-10 mils wet, 2.5-4.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2nd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series (4.0 mils wet, 1.6 mils dry per coat).
 - c. Semi-Gloss Finish High Performance:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series (6-10 mils wet, 2.5-4.0 mils dry per coat).
 - d. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series (4.0 mils wet, 1.7 mils dry per coat).
 - e. Eg-Shel / Satin Finish High Performance:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel B66 Series (6-10 mils wet, 2.5-4.0 mils dry per coat).
 - f. Low Sheen Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series (4.0 mils wet, 1.6 mils dry per coat).
 - g. Low Sheen Finish:
 - 1) 1st Coat: S-W Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Gloss Eg-Shel, B41-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Low Gloss Eg-Shel, B41-2600 Series (4 mils wet, 1.6 mils dry per coat).

- h. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series (4.0 mils wet, 1.6 mils dry per coat).
- i. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Harmony Interior Latex Flat, B5 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Flat, B5 Series (4.0 mils wet, 1.8 mils dry per coat).
- 2. Alkyd Systems (Water based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series (4 mils wet, 1.7 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series ((4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series (4.0 mils wet, 1.7 mils dry per coat).
 - d. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series ((4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - e. Low Sheen Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
 - 3) 3rd Coat: S-W -W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series ((4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- 3. Epoxy Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15.
 - 3) 3rd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15 (6.0 mils wet, 2.5 mils dry per coat).
 - b. Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet. 2.0 mils dry).
- 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series.
- 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series (5.0 mils wet, 2.0 mils dry per coat).

c. Semi-Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25.
- 3rd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25 (6.0 mils wet, 2.5 mils dry per coat).

d. Semi-Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series.
- 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series (4 mils wet, 1.5 mils dry per coat).

e. Eg-Shel/Low Luster Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series.
- 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series (4 mils wet, 1.5 mils dry per coat).

f. Eg-Shel/Low Luster Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series.
- 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series (5.0 mils wet, 2.0 mils dry per coat).

4. Urethane System (Water Based):

a. Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Waterbased Acrolon 100, B65-720 Series.
- 3) 3rd Coat: S-W Waterbased Acrolon 100, B65-720 Series (4.0 mils wet, 2 mils dry per coat).

5. Dryfall Waterborne Topcoat:

a. Semi-Gloss Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series.
- 3) 3rd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (5.8 mils wet, 2.3 mils dry per coat).

b. Eg-Shel Finish:

- 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
- 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series.
- 3) 3rd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (6.0 mils wet, 1.9 mils dry per coat).

c. Flat Finish:

1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).

- 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series.
- 3) 3rd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall, B42-80 Series (6.0 mils wet, 1.7 mils dry per coat).

G. WOOD - (Walls, Ceilings, Doors, Trim):

- Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall and Wood Primer, B28W8111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W ProClassic Waterborne Acrylic Gloss, B21-51 Series.
 - 3) 3rd Coat: S-W ProClassic Waterborne Acrylic Gloss, B21-51 Series (4 mils wet, 1.5 mils dry per coat).
 - b. Semi Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall and Wood Primer, B28W8111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W ProClassic Waterborne Acrylic Semi-Gloss, B31 Series.
 - 3) 3rd Coat: S-W ProClassic Waterborne Acrylic Semi-Gloss, B31 Series (4 mils wet, 1.3 mils dry per coat).
 - c. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W Premium Wall and Wood Primer, B28W8111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W ProClassic Waterborne Acrylic Satin, B20 Series.
 - 3) 3rd Coat: S-W ProClassic Waterborne Acrylic Satin, B20 Series (4 mils wet, 1.2 mils dry per coat).
 - d. Eg-Shel Finish, Microbicidal Paint:
 - 1st Coat: S-W PrepRite ProBlock Latex Primer/Sealer, B51 Series (4 mils wet, 1.4 mils dry per coat).
 - 2) 2nd Coat: S-W Paint Shield Microbicidal Paint, D12W51 (4 mils wet, 1.8 mils dry per coat).
 - 3) 3rd Coat: S-W Paint Shield Microbicidal Paint, D12W51 (4 mils wet, 1.8 mils dry per coat).
 - e. Flat Finish:
 - 1) 1st Coat: S-W Premium Wall and Wood Primer, B28W8111. (4 mils wet, 1.8 mils dry)
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series (4 mils wet, 1.6 mils dry per coat).
- 2. Alkyd Systems (Water based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall and Wood Primer, B28W8111 (4 mils wet, 1.8 mils drv).
 - 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Gloss, B35-8200 Series (4 mils wet, 1.7 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Premium Wood & Wall Primer, B28W8111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall and Wood Primer, B28W8111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-

- 8200 Series.
- 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Semi-Gloss, B34-8200 Series (4 mils wet, 1.7 mils dry per coat).
- d. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Premium Wood & Wall Primer, B28W8111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series ((4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- e. Eg-Shel Finish:
 - 1) 1st Coat: S-W Premium Wall and Wood Primer, B28W8111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Eg-Shel, B33-8200 Series.
 - 3) 3rd Coat: S-W ProMar 200 Waterbased Acrylic-Alkyd Eg-Shel, B33-8200 Series (4 mils wet, 1.4 mils dry per coat).
- f. Low Sheen Finish:
 - 1st Coat: S-W Premium Wood & Wall Primer, B28W8111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- 3. Stain and Varnish System:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W WoodClassics 250 Stains.
 - 2nd Coat: S-W WoodClassics Waterborne Polyurethane Varnish, A68 Series.
 - 3) 3rd Coat: S-W WoodClassics Waterborne Polyurethane Varnish, A68 Series (4 mils wet, 1.0 mil dry per coat).
 - b. Satin Finish:
 - 1) 1st Coat: S-W WoodClassics 250 Stains.
 - 2) 2nd Coat: S-W WoodClassics Waterborne Polyurethane Varnish, A68 Series.
 - 3) 3rd Coat: S-W WoodClassics Waterborne Polyurethane Varnish, A68 Series (4 mils wet, 1.0 mil dry per coat).
- H. DRYWALL (Walls, Ceilings, Gypsum Board and similar items)
 - 1. Latex Systems:
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W ProMar200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2nd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Semi-Gloss, B31-2600 Series (4 mils wet, 1.6 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Harmony Interior Latex Primer, B11 (4 mils wet, 1.3 mils dry).
 - 2) 2nd Coat: S-W Harmony Interior Latex Semi-Gloss, B10 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Semi-Gloss, B10 Series (4 mils wet, 1.4 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Interior Latex Primer, B28W08111 (4 mils wet, 1.8 mils dry).

- 2) 2nd Coat: S-W Emerald Interior Latex Semi-Gloss, K38 Series.
- 3) 3rd Coat: S-W Emerald Interior Latex Semi-Gloss, K38 Series (4 mils wet, 1.5 mils dry per coat).
- d. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series.
 - 3rd Coat: S-W ProMar 200 Zero VOC Latex Eg-Shel, B20-2600 Series (4 mils wet, 1.7 mils dry per coat).
- e. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W Harmony Interior Latex Primer, B11(4 mils wet, 1.3 mils dry).
 - 2) 2nd Coat: S-W Harmony Interior Latex Eg-Shel, B9 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Eg-Shel, B9 Series (4 mils wet, 1.7 mils dry per coat).
- f. Eg-Shel / Satin Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Interior Latex Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W Emerald Interior Latex Satin, K37 Series.
 - 3) 3rd Coat: S-W Emerald Interior Latex Satin, K37 Series (4 mils wet, 1.7 mils dry per coat).
- g. Eg-Shel Finish, Microbicidal Paint:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W Paint Shield Microbicidal Paint, D12W51 (4 mils wet, 1.8 mils dry per coat).
 - 3) 3rd Coat: S-W Paint Shield Microbicidal Paint, D12W51 (4 mils wet, 1.8 mils dry per coat).
- h. Low Sheen Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2nd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Low Sheen Enamel, B24-2600 Series (4 mils wet, 1.6 mils dry per coat).
- i. Low Sheen Finish:
 - 1) 1st Coat: S- Premium Wall & Wood Interior Latex Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W Emerald Interior Acrylic Latex Matte, K36 Series.
 - 3) 3rd Coat: S-W Emerald Interior Acrylic Latex Matte, K36 Series (4 mils wet, 1.6 mils dry per coat).
- j. Flat Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series.
 - 3) 3rd Coat: S-W ProMar 200 Zero VOC Latex Flat, B30-2600 Series (4 mils wet, 1.6 mils dry per coat).
- k. Flat Finish:
 - 1) 1st Coat: S-W Harmony Interior Latex Primer, B11 (4 mils wet, 1.3 mils dry).
 - 2) 2nd Coat: S-W Harmony Interior Latex Flat, B5 Series.
 - 3) 3rd Coat: S-W Harmony Interior Latex Flat, B5 Series (4 mils wet, 1.8 mils dry per coat).
- I. Flat Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Interior Latex Primer, B28W08111 (4 mils wet, 1.8 mils dry).

- 2) 2nd Coat: S-W Emerald Interior Acrylic Latex Flat. K35 Series.
- 3) 3rd Coat: S-W Emerald Interior Acrylic Latex Flat. K35 Series (4 mils wet, 1.6 mils dry per coat).
- 2. Epoxy Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15.
 - 3) 3rd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V15 (6.0 mils wet, 2.5 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-300 Series (5.0 mils wet, 2.0 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25.
 - 3) 3rd Coat: S-W Waterbased Catalyzed Epoxy, B70W211/ B60V25 (6.0 mils wet, 2.5 mils dry per coat).
 - d. Semi-Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K46-Series (4 mils wet, 1.5 mils dry per coat).
 - e. Eg-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy, K45-Series (4 mils wet, 1.5 mils dry per coat).
 - f. Eg-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Interior Latex Primer, B28W2600 (4 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy, B73-360 Series (5.0 mils wet, 2.0 mils dry per coat).
- I. Concrete (Floors, non-vehicular):
 - 1. Latex Systems:
 - a. Semi Gloss Finish:
 - 1) 1st Coat: S-W Tread-Plex Primer Acrylic Floor Coating, B90W110.
 - 2) 2nd Coat: S-W Tread-Plex Acrylic Floor Coating, B90 Series.
 - 3) 3rd Coat: S-W Tread-Plex Acrylic Floor Coating, B90 Series (3.5 mils wet, 1.5 mils dry, per coat).
 - b. Satin Finish:
 - 1) 1st Coat: S-W Porch and Floor Enamel, A32-200 Series.
 - 2) 2nd Coat: S-W Porch and Floor Enamel, A32-200 Series (4 mils wet, 1.5 mils dry per coat).

2.5 HIGH PERFORMANCE INTERIOR PAINT SYSTEMS

- A. CONCRETE Smooth (Walls and Ceilings, Poured Concrete, Precast Concrete, Unglazed Brick, Cement Board, Tilt-Up, Cast-In-Place).
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300, (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series (6.0-10.0 mils wet, 2.5-4.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300, (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series (6-10 mils wet, 2.5-4.0 mils dry per coat).
 - c. Eg-Shel/Satin Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300, (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel B66 Series (6.0-10.0 mils wet, 2.5-4.0 mils dry per coat).
 - d. Flat Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W1 (5.0-10.0 mils wet, 1.9-3.9 mils dry per coat).
 - 2. Alkyd Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss. B53-1050 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - c. Low Sheen Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - 3. Alkyd System (Solvent Base Finish):
 - a. Gloss Finish Urethane Modified:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 dry).
 - 2) 2nd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150

- Series.
- 3) 3rd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series (3.5-7.0 mils wet, 2.0-4.0 mils dry per coat).
- 4. Epoxy Systems (Water Based):
 - Gloss Finish:
 - 1st Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series.
 - 2) 2nd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series (6.5-8.0 mils wet, 2.5-3.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series.
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
 - c. Semi-Gloss/High Luster Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series (4 mils wet, 1.5 mils dry per coat).
 - d. Eg-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45-Series (4 mils wet, 1.5 mils dry per coat).
 - e. Eg-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series.
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
- 5. Epoxy Systems (Solvent Base):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial High Performance Epoxy Gloss, B67-200 Series.
 - 2) 2nd Coat: S-W Pro Industrial High Performance Epoxy Gloss, B67-200 Series (5.0-10.0 mils wet, 4-8.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Tile-Clad HS Epoxy Gloss, B62Z/B60VZ70 Series.
 - 2) 2nd Coat: S-W Tile-Clad HS Epoxy Gloss, B62Z/B60VZ70 Series (4.0-7.0 mils wet, 2.5-4.0 mils dry per coat).
- 6. Urethane System (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18 mils wet, 10 mils dry).
 - 2nd Coat: S-W Pro Industrial Waterbased Acrolon 100 Gloss, B65-720 Series.
 - 3) 3rd Coat: S-W Pro Industrial Waterbased Acrolon 100 Gloss, B65-720 Series (4.0-8.0 mils wet, 1.8-3.6 mils dry per coat).
 - b. Gloss Finish Single Component:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Urethane Gloss, B65-120 Series.

- 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Urethane Gloss, B65-1 20 Series (6.0-12.0 mils wet, 1.9-3.8 mils dry per coat).
- B. CONCRETE (Ceilings).
 - 1. MultiSurface Acrylic Coating:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Gloss, B66-1500 Series.
 - 2) 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Gloss, B66-1500 Series (3.7-5.0 mils wet, 1.5-2.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Semi-Gloss, B66-1550 Series.
 - 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Semi-Gloss, B66-1550 Series (3.75-5.0 mils wet, 1.5-2.0 mils dry per coat).
 - c. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Eg-Shel, B66-1560 Series.
 - 2) 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Eg-Shel, B66-1560 Series (3.75-5.0 mils wet, 1.5-2.0 mils dry per coat).
 - 2. Dryfall Waterborne Topcoats:
 - a. Semi-Gloss Finish:
 - 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Semi-Gloss, B42-80 Series.
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Semi-Gloss, B42-80 Series (6.0-9.0 mils wet, 2.3-3.5 mils dry per coat).
 - b. Eq-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Eg-Shel, B42-80 Series.
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Eg-Shel, B42-80 Series (6.0-9.0 mils wet, 2.0-3.0 mils dry per coat).
 - c. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Flat, B42-80
 Series
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Flat, B42-80 Series (6.0-9.0 mils wet, 1.5-2.3 mils dry per coat).
 - 3. Dryfall Alkyd Topcoats:
 - Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 dry).
 - 2) 2nd Coat: S-W Super Save-Lite Dryfall, B47W62.
 - 3) 3rd Coat: S-W Super Save-Lite Dryfall, B47W62(6.0-6.5 mils wet, 3.0-3.5 mils dry).
 - b. Flat Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (8 mils wet, 3.2 dry).
 - 2) 2nd Coat: S-W Dry Fall Flat, B48W60
 - 3) 3rd Coat: S-W Dry Fall Flat, B48W60 (8 mils wet, 3 mils dry).
- MASONRY (CMU Concrete, Split Face, Scored, Smooth, High Density, Low Density, Fluted, Stucco).
 - 1. Latex Systems:
 - Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series.

- 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series (6-10 mils wet. 2.5-4.0 mils dry per coat).
- b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series (6-10 mils wet, 2.5-4.0 mils dry per coat).
- c. Eg-Shel/Satin Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, Eg-Shel (6-9.5 mils wet, 2.5-4.0 mils dry per coat).
- d. Flat Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11 (5.0-10.0 mils wet, 1.9-3.9 mils dry per coat).
- 2. Alkyd Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - c. Low Sheen Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 series.
 - 3) 3rd Coat: S-W Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- 3. Alkyd System (Solvent Base Finish):
 - a. Gloss Finish Urethane Modified:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series.
 - 3) 3rd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series (3.5 -7.0 mils wet, 2.0-4.0 mils dry per coat)
- 4. Epoxy System (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2nd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series.

- 3) 3rd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series (6.5-8.0 mils wet, 2.5-3.0 mils dry per coat).
- b. Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
- c. Semi-Gloss/High Luster Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series (4 mils wet, 1.5 mils dry per coat).
- d. Eg-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series (4 mils wet, 1.5 mils dry per coat).
- e. Eq-Shel/Low Luster Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-13.0 mils wet, 10.0-18.0 mils wet).
 - 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
- 5. Epoxy Systems (Solvent Base Finish):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2nd Coat: S-W Pro Industrial High Performance Epoxy Gloss, B67-200 Series.
 - 3) 3rd Coat: S-W Pro Industrial High Performance Epoxy Gloss, B67-200 Series (5.0-10.0 mils wet, 4.0-8.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils wet).
 - 2) 2nd Coat: S-W Tile-Clad HS Epoxy Gloss, B62Z/B60VZ Series.
 - 3) 3rd Coat: S-W Tile-Clad HS Epoxy Gloss, B62Z/B60VZ Series (4.0-7.0 mils wet, 2.5-4.0 mils dry per coat).
- 6. Urethane Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Waterbased Acrolon 100 Gloss, B65-720 Series.
 - 3) 3rd Coat: S-W Pro Industrial Waterbased Acrolon 100 Gloss, B65-720 Series (4.0-8.0 mils wet, 1.8-3.6 mils dry per coat).
 - b. Gloss Finish Single Component:
 - 1) 1st Coat: S-W Heavy Duty Block Filler, B42W46 (18.0-34.0 mils wet, 10.0-18.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Urethane

- Gloss, B65-120 Series.
- 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Urethane Gloss, B65-120 Series (6.0-12.0 mils wet1.9-3.8 mils dry per coat).
- 7. Urethane Systems (Solvent Base Finish):
 - a. Gloss Finish:
 - 1) 1st Coat: Kem Cati-Coat HS Epoxy Filler/Sealer, B42-400 Series (14.0-28.0 mils wet, 10.0-20.0 mils dry).
 - 2) 2nd Coat: S-W Hi-Solids PolyurethaneGloss, B65/B60-30Series.
 - 3) 3rd Coat: S-W Hi-Solids PolyurethaneGloss, B65/B60-30 Series (4.5-8.0 mils wet, 3.0-5.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: Kem Cati-Coat HS Epoxy Filler/Sealer, B42-400 Series (14.0-28.0 mils wet, 10.0-20.0 mils dry).
 - 2) 2nd Coat: S-W Hi-Solids Polyurethane Semi-Gloss, B65-350/B60V30 Series.
 - 3) 3rd Coat: S-W Hi-Solids Polyurethane Semi-Gloss, B65-350/B60V30 Series (4.5-8.0 mils wet, 3.0-5.0 mils dry per coat).
- D. Non-Ferrous- (Galvanized and Aluminum):
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series.
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series (6.0-10.0 mils wet, 2.5-4.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series.
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series (6.0-10.0 mils wet, 2.5-4.0 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry per coat).
 - 2) 2nd Coat: S-W Metalatex Semi-Gloss Coating, B42 Series.
 - 3) 3rd Coat: S-W Metalatex Semi-Gloss Coating, B42 Series (4.0-11.0 mils wet, 1.5-4.0 mils dry per coat).
 - d. Eg-Shel/Satin Finish:
 - 1) 1st Coat: S-W Pro Industrial DTM Acrylic Eg-Shel, B66 Series.
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel (6.0- 9.5 mils wet, 2.5- 4.0 mils dry per coat).
 - e. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11 (5.0-10.0 mils wet, 1.9-3.9 mils dry per coat).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11 (5.0-10.0 mils wet, 1.9-3.9mils dry per coat).
 - 2. Alkyd System (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.

- 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- c. Low Sheen Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- 3. Alkyd System (Solvent Base Finish):
 - Gloss Finish Urethane Modified:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series.
 - 3) 3rd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series (3.5-7.0 mils wet, 2.0-4.0 mils dry per coat).
- 4. Epoxy Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15.
 - 2) 2nd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 (6.5-8.0 mils wet, 2.5-3.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46-K46- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series (4.0 mils wet, 1.5 mils dry per coat).
 - d. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series (4.0 mils wet, 1.5 mils dry per coat).
 - e. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0 mils wet, 2.0 mils dry).
 - 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series (5.0-10 mils wet, 2.0-4.0 mils dry per coat).
- 5. Epoxy Systems (Solvent Base):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Tile-Clad HS Epoxy, B62Z/B60VZ Series.
 - 2) 2nd Coat: S-W Tile-Clad HS Epoxy, B62Z/B60VZ Series (4.0-7.0 mils wet, 2.5-4.0 mils dry per coat).
 - b. Semi-Gloss Finish:

- 1) 1st Coat: S-W Macropoxy 646 Fast Cure Epoxy Semi-Gloss, B58-600 Series.
- 2) 2nd Coat: S-W Macropoxy 646 Fast Cure Epoxy Semi-Gloss, B58-600 Series (7.0-13.5 mils wet, 5.0-10.0 mils dry per coat).
- 6. Urethane Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W DTM Wash Primer, B71Y1 (3.4-6.4 mils wet, 0.7-1.3 mils dry).
 - 2) 2nd Coat: S-W Pro-Industrial Waterbased Acrolon 100 Gloss, B65-720 Series.
 - 3) 3rd Coat: S-W Pro-Industrial Waterbased Acrolon 100 Gloss, B65-720 Series (4.0-8.0 mils wet, 1.8-3.6 mils dry per coat).
 - b. Gloss Finish Single Component:
 - 1) 1st Coat: S-W DTM Wash Primer, B71Y1 (3.4-6.4 mils wet, 0.7-1.3 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Urethane Gloss, B65-120 Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Urethane Gloss, B65-120 Series (6.0-12.0 mils wet1.9-3.8mils dry per coat).
- 7. Urethane Systems (Solvent Base):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W DTM Wash Primer, B71Y1 (3.4-6.4 mils wet, 0.7-1.3 mils dry).
 - 2) 2nd Coat: S-W Hi-Solids Polyurethane Gloss, B65/B60-30 Series.
 - 3) 3rd Coat: S-W Hi-Solids Polyurethane Gloss, B65/B60-30 Series (4.5-8.0 mils wet, 3.0-5.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W DTM Wash Primer, B71Y1 (3.4-6.4 mils wet, 0.7-1.3 mils dry).
 - 2) 2nd Coat: S-W Hi-Solids Polyurethane Semi-Gloss, B65-350/B60V30 Series.
 - 3) 3rd Coat: S-W Hi-Solids Polyurethane Semi-Gloss, B65-350/B60V30 Series (4.5-8.0 mils wet, 3.0-5.0 mils dry per coat).
- 8. Multi-Surface Acrylic Coating:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Gloss, B66-1500 Series.
 - 2) 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Gloss, B66-1500 Series (3.7-5.0 mils wet, 1.5-2.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Semi-Gloss, B66-1550
 Series
 - 2) 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Semi-Gloss, B66-1550 Series (3.75-5.0 mils wet, 1.5-2.0 mils dry per coat).
 - c. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Eg-Shel, B66-1560 Series.
 - 2) 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Eg-Shel, B66-1560 Series (3.75-5.0 mils wet, 1.5-2.0 mils dry per coat).
- 9. Dryfall Waterborne Topcoats:
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Semi-Gloss,B42-80 Series.
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Semi-Gloss, B42-80 Series (6.0-9.0 mils wet, 2.3-3.5 mils dry per coat).
 - b. Eg-Shel Finish:

- 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Eg-Shel, B42-80 Series.
- 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Eg-Shel, B42-80 Series (6.0-9.0 mils wet, 2.0-3.0 mils dry per coat).
- c. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Flat, B42-80 Series.
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Flat, B42-80 Series (6.0-9.0 mils wet, 1.5-2.3 mils dry per coat).
- 10. Dryfall Alkyd Topcoats:
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W DTM Wash Primer, B71Y1 (3.4-6.4 mils wet, 0.7-1.3 mils dry).
 - 2) 2nd Coat: S-W Super Save-Lite Dryfall Semi-Gloss, B47W62.
 - 3) 3rd Coat: S-W Super Save-Lite Dryfall Semi-Gloss, B47W62 (6.0-7.0 mils wet, 3.0-3.5 mils dry).
 - b. Flat Finish:
 - 1) 1st Coat: S-W DTM Wash Primer, B71Y1 (3.4-6.4 mils wet, 0.7-1.3 mils dry).
 - 2) 2nd Coat: S-W Dry Fall Flat, B48W60.
 - 3) 3rd Coat: S-W Dry Fall Flat, B48W60 (8 mils wet, 3 mils dry).
- E. METAL (Structural Steel Columns, Joists, Trusses, Beams, Miscellaneous and Ornamental Iron, Structural Iron, Ferrous Metal).
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series.
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series (6.0-10.0 mils wet. 2.5-4.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series.
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series (6.0-10.0 mils wet, 2.5-4.0 mils dry per coat).
 - c. Eg-Shel/Satin Sheen:
 - 1) 1st Coat: S-W Pro Industrial DTM Acrylic Eg-Shel, B66 Series.
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel (6.0-10.0 mils wet, 2.5-4.0 mils dry per coat).
 - d. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11 (5.0-10.0 mils wet, 1.9-3.9 mils dry per coat).
 - 2. Alkyd Systems (Water based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).

- c. Low Sheen Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat:S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- 3. Alkyd System (Solvent Base Finish):
 - a. Gloss Finish Urethane Modified:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series.
 - 3) 3rd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series (3.5-7.0 mils wet, 2.0-4.0 mils dry per coat).
- 4. Epoxy Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2nd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series.
 - 3) 3rd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series (6.5-8.0 mils wet, 2.5-3.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss. K46- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series (4 mils wet, 1.5 mils dry per coat).
 - d. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series (4 mils wet, 1.5 mils dry per coat).
 - e. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
- 5. Epoxy System (Solvent Base):
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Recoatable Epoxy Primer, B67 Series. (6.0-9.0 mils wet, 4.0-6.0 mils dry).
 - 2) 2nd Coat: S-W Macropoxy 646 Fast Cure Epoxy, B58-600 Series.

- 3) 3rd Coat: S-W Macropoxy 646 Fast Cure Epoxy, B58-600 Series. (7.0-13.5 mils wet, 5.0-10.0 mils dry per coat).
- 6. Urethane System (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series. (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Acrolon 100 Gloss, B65-720 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Acrolon 100 Gloss, B65-720 Series. (4.0-8.0 mils wet, 1.8-3.6 mils dry per coat).
 - b. Gloss Finish Single Component:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series. (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Urethane Gloss, B65-120 Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyed Waterbased Urethane Gloss, B65-120 Series. (6.0-12.0 mils wet, 1.9-3.8mils dry per coat).
- 7. Urethane System (Solvent Base):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Recoatable Epoxy Primer, B67-5 Series. (6.0-9.0 mils wet, 4.0-6.0 mils dry).
 - 2) 2nd Coat: S-W Hi-Solids Polyurethane Gloss, B65-300 Series.
 - 3) 3rd Coat: S-W Hi-Solids Polyurethane Gloss, B65-300 Series. (4.5-8.0 mils wet, 3.0-5.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Recoatable Epoxy Primer, B67-5 Series. (6.0-9.0 mils wet, 4.0-6.0 mils dry).
 - 2) 2nd Coat: S-W Hi-Solids Polyurethane Semi-Gloss, B65-350 Series.
 - 3) 3rd Coat: S-W Hi-Solids Polyurethane Semi-Gloss, B65-350 Series. (4.5-8.0 mils wet, 3.0-5.0 mils dry per coat).
- F. METAL (Ceilings Structural Steel, Joists, Trusses, Beams).
 - 1. MultiSurface Acrylic Coating:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Gloss, B66-1500 Series.
 - 2) 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Gloss, B66-1500 Series (3.75-5.0 mils wet, 1.5-2.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Semi-Gloss, B66-1550 Series.
 - 2) 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Semi-Gloss, B66-1550 Series (3.75-5.0 mils wet, 1.5-2.0 mils dry per coat).
 - c. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Multi-Surface Acrylic Eg-Shel, B66-1560 Series.
 - 2) 2nd Coat: S-W Pro Industrial Multi-Surface Acrylic Eg-Shel, B66-1560 Series (3.75-5.0 mils wet, 1.5-2.0 mils dry per coat).
 - 2. Dryfall Waterborne Topcoats:
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Semi-Gloss, B42-80 Series.
 - 3) 3rd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Semi-Gloss, B42-80 Series (6.0-9.0 mils wet, 2.3-3.5 mils dry per coat).

- b. Eg-Shel Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series. (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Eg-Shel, B42-80 Series.
 - 3) 3rd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Eg-Shel, B42-80 Series (6.0-9.0 mils wet, 2.0-3.0 mils dry per coat).
- c. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Flat, B42-80 Series
 - 3) 3rd Coat: S-W Pro Industrial Waterborne Acrylic Dryfall Flat, B42-80 Series (6.0-9.0 mils wet, 1.5-2.3 mils dry per coat).
- 3. Dryfall Alkyd Topcoats:
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series(5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Super Save-Lite Dryfall Semi-Gloss, B47W62.
 - 3) 3rd Coat: S-W Super Save-Lite Dryfall Semi-Gloss, B47W62 (6.0-7.0 mils wet, 3.0-3.5 mils dry per coat).
 - b. Flat Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Dry Fall Flat, B48W60 3rd Coat: S-W Dry Fall Flat, B48W60(8 mils wet, 3 mils dry).
- G. WOOD- (Doors, Trim, Partitions, Frames).
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111, (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66-600 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66-600 Series (6.0-12.0 mils wet, 2.1-4.2 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111, (4 mils wet, 1.8 mils drv).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66-650 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66-650 Series (6.0-12.0 mils wet, 2.1-4.2 mils dry per coat).
 - c. Eq-Shel/Satin Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111, (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Eg-Shel, B66-660 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic, Eg-Shel, B66-660 Series (6.0-12.0 mils wet, 2.1-4.2 mils dry per coat).
 - d. Flat Finish:
 - 1st Coat: S-W Premium Wall and Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11 (5.0-10.0 mils wet, 1.9-3.9 mils dry per coat).
 - 2. Alkyd Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet,

- 1.8 mils dry).
- 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
- 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- c. Low-Sheen Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- 3. Alkyd System (Solvent Base Finish):
 - a. Gloss Finish Urethane Modified:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series.
 - 3) 3rd Coat: S-W Pro Industrial Urethane Alkyd Enamel Gloss, B54-150 Series. (3.5-7.0 mils wet, 2.0-4.0 mils dry per coat).
- 4. Epoxy System (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series.
 - 3) 3rd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series. (6.5-8.0 mils wet, 2.5-3.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series. (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss. K46- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series. (4 mils wet, 1.5 mils dry per coat).
 - d. Eq-Shel Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series. (4 mils wet, 1.5 mils dry per coat).

- e. Eg-Shel Finish:
 - 1) 1st Coat: S-W Premium Wall & Wood Primer, B28W08111 (4 mils wet, 1.8 mils dry).
 - 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series. (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
- 5. Epoxy System (Solvent Base):
 - a. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Macropoxy 646 Fast Cure Epoxy, B58-600 Series.
 - 2) 2nd Coat: S-W Macropoxy 646 Fast Cure Epoxy, B58-600 Series (7.0-13.5 mils wet, 5.0-10.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial High Performance Epoxy, B67-200 Series.
 - 2) 2nd Coat: S-W Pro Industrial High-Performance Epoxy, B67-200 Series. (5.0-10.0 mils wet, 4.0-8.0 mils dry per coat).
 - c. Gloss Finish:
 - 1) 1st Coat: S-W Tile-Clad HS Epoxy, B62Z/B60VZ70 Series.
 - 2) 2nd Coat: S-W Tile-Clad HS Epoxy, B62Z/B60VZ70 Series (4.0-7.0 mils wet, 2.5-4.0 mils dry per coat).
- H. DRYWALL (Walls, Ceilings, Gypsum Board).
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Gloss, B66 Series (6.0-10 mils wet. 2.5-4.0 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Semi-Gloss, B66 Series (6.0-10 mils wet, 2.5-4.0 mils dry per coat).
 - c. Eg-Shel/Satin Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.5 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Eq-Shel, B66 Series.
 - 3) 3rd Coat: S-W Industrial DTM Acrylic Eg-Shel, (6.0-10 mils wet, 2.5-4.0 mils dry per coat).
 - d. Flat Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W DTM Acrylic Primer/Finish, B66W11.
 - 3) 3rd Coat: S-W DTM Acrylic Primer/Finish, B66W11 (5.0-10.0 mils wet, 1.9-3.9 mils dry per coat).
 - 2. Alkyd Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W Waterbased Industrial Enamel, B53-300 Series.
 - 3) 3rd Coat: S-W Waterbased Industrial Enamel, B53-300 Series. (4.5-8.5 mils wet, 1.5-3.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0

- mils wet, 1.0 mils dry).
- 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series.
- 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Gloss, B53-1050 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Semi-Gloss, B53-1150 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- d. Low Sheen Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Alkyd Urethane Enamel Low Sheen, B53-1250 Series (4.0-5.0 mils wet, 1.4 1.7 mils dry per coat).
- 3. Epoxy Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2nd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series.
 - 3) 3rd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series. (6.5-8.0 mils wet, 2.5-3.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series. (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2nd Coat: S-W Water Based Catalyzed Epoxy Semi-Gloss, B70/B60V25
 Series
 - 3) 3rd Coat: S-W Water Based Catalyzed Epoxy Semi-Gloss, B70/B60V25 Series. (6.0-8.0 mils wet, 2.5-3.0 mils dry per coat).
 - d. Semi-Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer,B280W2600 (4.0 mils wet, 1.0 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series. (4 mils wet, 1.5 mils dry per coat).
 - e. Eg-Shel Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series. (4 mils wet, 1.5 mils dry per coat).
 - f. Eg-Shel Finish:

- 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet. 1.0 mils drv).
- 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series.
- 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series. (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
- 4. Epoxy System (Solvent Base):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial High Performance Epoxy, B67-200 Series.
 - 3) 3rd Coat: S-W Pro Industrial High Performance Epoxy, B67-200 Series. (5.0-10.0 mils wet, 4.0-8.0 mils dry per coat).
 - b. Gloss Finish:
 - 1) 1st Coat: S-W ProMar 200 Zero VOC Latex Primer, B28W02600 (4.0 mils wet, 1.0 mils dry).
 - 2) 2nd Coat: S-W Tile-Clad HS Epoxy Gloss, B62Z/B60VZ70 Series.
 - 3) 3rd Coat: S-W Tile-Clad HS Epoxy Gloss, B62Z/B60VZ70 Series. (4.0-7.0 mils wet, 2.5-4.0 mils dry per coat).
- I. PLASTER (Walls, Ceilings).
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Acrylic Coating Gloss, B66-600 Series.
 - 3) 3rd Coat: S-W Pro Industrial Acrylic Coating Gloss, B66-600 Series. (6.0-12.0 mils wet, 2.1-4.2 mils dry per coat).
 - b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Acrylic Coating Semi-Gloss, B66-650 Series.
 - 3) 3rd Coat: S-W Pro Industrial Acrylic Coating Semi-Gloss, B66-650 Series. (6.0-12.0 mils wet, 2.1-4.2 mils dry per coat).
 - c. Low Sheen Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet. 2.1-3.2 mils drv).
 - 2) 2nd Coat: S-W Pro Industrial Acrylic Coating Eg-Shel, B66-660 Series.
 - 3) 3rd Coat: S-W Pro Industrial Acrylic Coating Eg-Shel, B66-660 Series. (6.0-12.0 mils wet, 2.1-4.2 mils dry per coat).
 - d. Flat Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11.
 - 3) 3rd Coat: S-W Pro Industrial DTM Acrylic Primer/Finish, B66W11 (5.0-10 mils wet, 1.9- 3.9 mils dry per coat).
 - 2. Epoxy Systems (Water Based):
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2nd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series.
 - 3) 3rd Coat: S-W Water Based Catalyzed Epoxy Gloss, B70/B60V15 Series. (6.5-8.0 mils wet, 2.5-3.0 mils dry per coat).
 - b. Gloss Finish:

- 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils drv).
- 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series.
- 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Gloss, B73-300 Series. (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).
- c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss. K46- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Semi-Gloss, K46- Series. (4.0 mils wet, 1.5 mils dry per coat).
- d. Eg-Shel Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2nd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series.
 - 3) 3rd Coat: S-W Pro Industrial Pre-Catalyzed Waterbased Epoxy Eg-Shel, K45- Series. (4.0 mils wet, 1.5 mils dry per coat).
- e. Eg-Shel Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series.
 - 3) 3rd Coat: S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 Series. (5.0-10.0 mils wet, 2.0-4.0 mils dry per coat).

2.6 EXTERIOR PAINT SYSTEMS

- A. CONCRETE (Cementitious Siding, Flexboard, Transite Board, Shingles (Non-Roof), Common Brick, Stucco, Tilt-up, Precast, and Poured-in-place Cement).
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Gloss, A8 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Gloss, A8 Series (4.0 mils wet, 1.3 mils dry per coat).
 - b. Gloss Finish- Early Moisture Resistant:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Gloss, K44 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Gloss, K44 Series (4.0 mils wet, 1.6 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series.
 - 3) 3rd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series (4.0-11.0 mils wet, 1.5-4.0 mils dry per coat).
 - d. Satin Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Satin, A82 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Satin, A82 Series (4.0 mils wet, 1.5

mils dry per coat).

- e. Satin Finish- Early Moisture Resistant:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Satin, K43 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Satin, K43 Series (4.0 mils wet, 1.6 mils dry per coat).
- f. Flat Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Flat, A6 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Flat, A6 Series (4.0 mils wet, 1.2 mils dry per coat).
- g. Flat Finish- Early Moisture Resistant:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Flat, K42 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Flat, K42 Series (4.0 mils wet, 1.6 mils dry per coat).
- h. High Build Coating:
 - 1) 1st Coat: S-W Loxon XP, A24-1400 Series (14.0-18.0 mils wet; 6.4-8.3 mils dry).
- 2. Elastomeric System: Not including cementitious siding, Flexboard, Transite board or shingles (non-roof).
 - a. Flat Finish:
 - 1) 1st Coat: S-W Loxon Concrete & Masonry Primer Sealer, A24W8300 (5.3-8.0 mils wet, 2.1-3.2 mils dry).
 - 2nd Coat: S-W ConFlex XL Elastomeric High Build Coating, A5-400 Series.
 - 3) 3rd Coat: S-W ConFlex XL Elastomeric High Build Coating, A5-400 Series (13.0-16.0 mils wet, 6.0-7.5 mils dry per coat).
 - b. Flat Finish:
 - 1) 1st Coat: S-W Loxon BlockSurfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2) 2nd Coat: S-W SherLastic Elastomeric Masonry Coating, A5-600 Series.
 - 3) 3rd Coat: S-W SherLastic Elastomeric Masonry Coating, A5-600 Series (10.0-14.0 mils wet, 4.0-6.0 mils dry per coat).
- 3. Textured Elastomeric System:
 - Textured Finish:
 - 1) 1st Coat: S-W Loxon BlockSurfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2) 2nd Coat: S-W ConFlex XL Elastomeric High Build Coating, A5-400 Series (13.0-16.0 mils wet,6.0- 7.5 mils dry per coat).
 - 3) 3rd Coat: S-W ConFlex XL Textured Elastomeric High Build Coating, A5-800 (20.0-23.0 mils wet, 9.4-11.0 mils dry per coat).
 - a) Finish Texture: Fine.
 - b) Finish Texture: Medium.
 - c) Finish Texture: Extra Coarse.
- 4. Textured and Smooth Systems:
 - a. Textured (Water Based Finish):
 - 1) 1st Coat: S-W Loxon BlockSurfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2) 2nd Coat: S-W UltraCrete Textured Masonry Topcoat A44-800 Series (50-80 sq ft/gal).
 - a) Finish Texture: Fine.
 - b) Finish Texture: Medium.

- c) Finish Texture: Extra Coarse.
- b. Textured Finish (Solvent Based):
 - 1) 1st Coat: S-W UltraCrete Smooth Waterproofing Masonry Coating, B46 Series (100-160 sq ft/gal).
 - 2) 2nd Coat: S-W UltraCrete Textured Waterproofing Masonry Coating, B46 Series (50-80 sq ft/gal).
 - a) Finish Texture: Fine.
 - b) Finish Texture: Medium.
 - c) Finish Texture: Extra Coarse.
- c. Smooth (Water Based Finish):
 - 1) 1st Coat: S-W Loxon XP, A24-1400 Series.
 - 2) 2nd Coat: S-W Loxon XP, A24-1400 Series (14.0-18.0 mils wet; 6.4-8.3 mils dry per coat).
- 5. Stain System:
 - a. Solid Color Waterborne Finish:
 - 1) 1st Coat: S-W Loxon Vertical Concrete Stain, A31 Series.
 - 2) 2nd Coat: S-W Loxon Vertical Concrete Stain, A31 Series (50-250 sq/ft gal).
- 6. Clear Water Repellant:
 - a. Clear:
 - 1) 1st Coat: S-W Loxon 7% Siloxane Water Repellant, A10T7.
 - 2) 2nd Coat: S-W Loxon 7% Siloxane Water Repellant, A10T7 (50-200 sq ft/ gal).
- B. MASONRY: Concrete Masonry Units (CMU)- Cinder or Concrete Block.
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Gloss, A8 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Gloss, A8 Series (4.0 mils wet, 1.3 mils dry per coat).
 - b. Gloss Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Gloss, K44 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Gloss, K44 Series (4.0 mils wet, 1.6 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series.
 - 3) 3rd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series (4.0-11.0 mils wet, 1.5-4.0 mils dry per coat).
 - d. Satin Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Satin, A82 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Satin, A82 Series (4.0 mils wet, 1.5 mils dry per coat).
 - e. Satin Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Loxon Block Surfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Satin, K43 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Satin, K43 Series (4.0 mils wet, 1.6 mils dry per coat).
 - f. Flat Finish:
 - 1) 1st Coat: S-W PrepRite Block Filler, B25W25 (75-125 sq ft/gal).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Flat, A6 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Flat, A6 Series (4.0 mils wet, 1.2

mils dry per coat).

- g. Flat Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Loxon BlockSurfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Flat, K42 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Flat, K42 Series (4.0 mils wet, 1. 6 mils dry per coat).
- h. High Build Coating:
 - 1) 1st Coat: S-W Loxon XP Waterproofing System, A24-1400 Series (14.0-18.0 mils wet; 6.4-8.3 mils dry).
- 2. Elastomeric System:
 - a. Flat Finish:
 - 1st Coat: S-W Loxon BlockSurfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2nd Coat: S-W ConFlex XL Elastomeric High Build Coating, A5-400 Series.
 - 3) 3rd Coat: S-W ConFlex XL Elastomeric High Build Coating, A5-400 Series (13.0-16.0 mils wet, 6.0-7.5 mils dry per coat).
 - b. Flat Finish:
 - 1) 1st Coat: S-W Loxon BlockSurfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2) 2nd Coat: S-W Sherlastic Elastomeric Coating, A5-600 Series.
 - 3) 3rd Coat: S-W Sherlastic Elastomeric Coating, A5-600 Series (10.0-14.0 mils wet, 4.0-6.0 mils dry per coat).
- 3. Textured Elastomeric System:
 - a. Textured Finish:
 - 1) 1st Coat: S-W Loxon BlockSurfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2) 2nd Coat: S-W ConFlex XL Elastomeric High Build Coating, A5-400 Series (13.0-16.0 mils wet, 6.0-7.5 mils dry per coat).
 - 3) 3rd Coat: S-W ConFlex XL Textured Elastomeric High Build Coating, A5-800 (20 mils wet, 9.4 mils dry per coat).
 - a) Finish Texture: Fine.
 - b) Finish Texture: Medium.
 - c) Finish Texture: Extra Coarse.
- 4. Textured Masonry System:
 - a. Textured (Water Based Finish):
 - 1) 1st Coat: S-W Loxon BlockSurfacer, A24W00200 (16.0 mils wet, 8.8 mils dry).
 - 2) 2nd Coat: S-W UltraCrete Textured Masonry Topcoat A44-800 Series (50-80 sq ft/ gal).
 - a) Finish Texture: Fine.
 - b) Finish Texture: Medium.
 - c) Finish Texture: Extra Coarse.
 - b. Textured Finish (Solvent Based):
 - 1) 1st Coat: S-W UltraCrete Smooth Waterproofing Masonry Coating, B46 Series (100-160 sq ft/qal).
 - 2) 2nd Coat: S-W UltraCrete Textured Waterproofing Masonry Coating, B46 Series (50-80 sq ft/gal).
 - a) Finish Texture: Fine.
 - b) Finish Texture: Medium.
 - c) Finish Texture: Extra Coarse.
 - c. Smooth (Water Based Finish):
 - 1) 1st Coat: S-W Loxon XP, A24-1400 Series.
 - 2) 2nd Coat: S-W Loxon XP, A24-1400 Series (14.0-18.0 mils wet; 6.4-8.3 mils dry per coat).

- 5. Stain System:
 - Solid Color Waterborne Finish:
 - 1) 1st Coat: S-W Loxon Vertical Concrete Stain, A31 Series.
 - 2nd Coat: S-W Loxon Vertical Concrete Stain, A31 Series (50-250 sq/ft gal).
- 6. Clear Water Repellant:
 - a. Clear Finish:
 - 1) 1st Coat: S-W Loxon 7% Siloxane Water Repellant, A10T7.
 - 2) 2nd Coat: S-W Loxon 7% Siloxane Water Repellant, A10T7 (50-200 sq ft/ gal).
- C. CONCRETE: Concrete Floors (non-vehicular), Patios, Porches, Steps and Platforms.
 - 1. Acrylic System Water-Based:
 - a. Floor Finish:
 - 1) 1st Coat: S-W Porch & Floor Enamel, A32-200 Series.
 - 2) 2nd Coat: S-W Porch & Floor Enamel, A32-200 Series (4.0 mils wet, 1.5 mils dry per coat).
 - b. Floor Finish:
 - 1st Coat: S-W Sher-Crete Flexible Concrete Waterproofer-Smooth, A5-250 Series.
 - 2) 2nd Coat: S-W Sher-Crete Flexible Concrete Waterproofer-Smooth, A5-250 Series (10.0-12.0 mils wet per coat).
- D. METAL: Aluminum, Galvanized.
 - Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W A-100 Exterior Latex Gloss, A8 Series.
 - 2) 2nd Coat: S-W A-100 Exterior Latex Gloss, A8 Series (4.0 mils wet, 1.3 mils dry per coat).
 - b. Gloss Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Resilience Exterior Latex Gloss, K44 Series.
 - 2) 2nd Coat: S-W Resilience Exterior Latex Gloss, K44 Series (4.0 mils wet, 1.6 mils dry per coat).
 - c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series.
 - 2) 2nd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series (4.0-11.0 mils wet, 1.5-4.0 mils dry per coat).
 - d. Satin Finish:
 - 1) 1st Coat: S-W A-100 Exterior Latex Satin, A82 Series.
 - 2) 2nd Coat: S-W A-100 Exterior Latex Satin, A82 Series (4.0 mils wet, 1.5 mils dry per coat).
 - e. Satin Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Resilience Exterior Latex Satin, K43 Series.
 - 2) 2nd Coat: S-W Resilience Exterior Latex Satin, K43 Series (4.0 mils wet, 1.6 mils dry per coat).
 - f. Flat Finish:
 - 1) 1st Coat: S-W A-100 Exterior Latex Flat, A6 Series.
 - 2) 2nd Coat: S-W A-100 Exterior Latex Flat, A6 Series (4.0 mils wet, 1.2 mils dry per coat).
 - g. Flat Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Resilience Exterior Latex Flat, K42 Series.
 - 2) 2nd Coat: S-W Resilience Exterior Latex Flat, K42 Series (4.0 mils wet, 1.6 mils dry per coat).
- E. METAL: Misc. Iron, Ornamental Iron, Structural Iron and Steel, Ferrous Metal.
 - 1. Latex Systems:

- a. Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Gloss, A8 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Gloss, A8 Series (4.0 mils wet, 1.3 mils dry per coat).
- b. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Pro Industrial Pro-Cryl Universal Primer, B66-1310 Series (5.0-10.0 mils wet, 1.8-3.6 mils dry).
 - 2) 2nd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series.
 - 3) 3rd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series (4.0-11.0 mils wet, 1.5-4.0 mils dry per coat).
- F. WOOD: Decks, Exterior including pressure treated lumber, Floors (non-Vehicular), Platforms.
 - 1. Acrylic Water-Based Floor System:
 - a. Floor Finish:
 - 1) 1st Coat: S-W Porch & Floor Enamel, A32-200 Series.
 - 2) 2nd Coat: S-W Porch & Floor Enamel, A32-200 Series (4.0 mils wet; 1.5 mils dry per coat).
 - 2. Stain Systems:
 - a. Solid Color Acrylic Latex:
 - 1st Coat: S-W SuperDeck Exterior Waterborne Solid Color Deck Stain, SD7-Series.
 - 2nd Coat: S-W SuperDeck Exterior Waterborne Solid Color Deck Stain, SD7-Series (200-400 sq ft/gal).
 - b. Semi-Solid Color Acrylic Latex:
 - 1) 1st Coat: S-W SuperDeck Exterior Waterborne Semi-Solid Color Deck Stain, SD5-Series.
 - 2) 2nd Coat: S-W SuperDeck Exterior Waterborne Semi-Solid Color Deck Stain, SD5-Series (100-350 sq ft/gal).
 - c. Semi-Transparent Stain:
 - 1) 1st Coat: S-W SuperDeck Exterior Waterborne Semi-Transparent Stain, SD3TSeries.
 - 2) 2nd Coat: S-W SuperDeck Exterior Waterborne Semi-Transparent Stain, SD3T Series (100 350 sq ft/gal).
 - d. Clear Stain:
 - 1st Coat: S-W SuperDeck Exterior Waterborne Clear Sealer, SD1T00100.
 - 2) 2nd Coat: S-W SuperDeck Exterior Waterborne Clear Sealer, SD1T00100, (150 300 sq ft/gal).
- G. WOOD: Siding, Trim, Shutters, Sashes, Hardboard-Bare/Primed.
 - 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Exterior Latex Wood Primer, B42W8041 (4.0 mils wet, 1.4 mils dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Gloss, A8 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Gloss, A8 Series (4.0 mils wet, 1.3 mils dry per coat).
 - b. Gloss Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Exterior Latex Wood Primer, B42W8041 (4.0 mils wet, 1.4 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Gloss, K44 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Gloss, K44 Series (4.0 mils wet, 1.6 mils dry per coat).

- c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Exterior Latex Wood Primer, B42W8041 (4.0 mils wet, 1.4 mils dry).
 - 2) 2nd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series.
 - 3) 3rd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series (4.0-11.0 mils wet, 1.5-4.0 mils dry per coat).
- d. Satin Finish:
 - 1) 1st Coat: S-W Exterior Latex Wood Primer, B42W8041 (4.0 mils wet, 1.4 mils dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Satin, A82 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Satin, A82 Series (4.0 mils wet, 1.5 mils dry per coat).
- e. Satin Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Exterior Latex Wood Primer, B42W8041 (4.0 mils wet, 1.4 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Satin, K43 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Satin, K43 Series (4.0 mils wet, 1.6 mils dry per coat).
- f. Flat Finish:
 - 1) 1st Coat: S-W Exterior Latex Wood Primer, B42W8041 (4 mils wet, 1.4 mils dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Flat, A6 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Flat, A6 Series (4.0 mils wet, 1.2 mils dry per coat).
- g. Flat Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Exterior Latex Wood Primer, B42W8041 (4.0 mils wet, 1.4 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Flat, K42 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Flat, K42 Series (4.0 mils wet, 1.6 mils dry per coat).
- 2. Stain Water Reducible Systems:
 - a. Semi-Transparent:
 - 1) 1st Coat: S-W WoodScapes Exterior Polyurethane Semi-Transparent Stain, A15T00005.
 - 2) 2nd Coat: S-W WoodScapes Exterior Polyurethane Semi-Transparent Stain, A15T00005 (100-350 sq ft/qal).
 - b. Solid Color:
 - 1) 1st Coat: S-W WoodScapes Exterior Acrylic Solid Color Stain, A15 Series
 - 2) 2nd Coat: S-W WoodScapes Exterior Acrylic Solid Color Stain, A15 Series (200-400 sq ft/gal).

H. ARCHITECTURAL PVC, PLASTIC, FIBERGLASS

- 1. Latex Systems:
 - a. Gloss Finish:
 - 1) 1st Coat: S-W Extreme Bond Bonding Primer, B51W00150 (3.1 mils wet, .9 mils dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Gloss, A8 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Gloss, A8 Series (4.0 mils wet, 1.3 mils dry per coat).
 - b. Gloss Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Extreme Bond Bonding Primer, B51W00150 (3.1mils wet, .9 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Gloss, K44 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Gloss, K44 Series (4.0 mils wet, 1.6 mils dry per coat).

- c. Semi-Gloss Finish:
 - 1) 1st Coat: S-W Extreme Bond Bonding Primer, B51W00150 (3.1 mils wet, .9 mils dry).
 - 2) 2nd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series.
 - 3) 3rd Coat: S-W Metalatex Acrylic Semi-Gloss, B42 Series (4.0-11.0 mils wet, 1.5-4.0 mils dry per coat).
- d. Satin Finish:
 - 1) 1st Coat: S-W Extreme Bond Bonding Primer, B51W00150 (3.1 mils wet, .9 mils dry).
 - 2nd Coat: S-W A-100 Exterior Latex Satin, A82 Series.
 - 3rd Coat: S-W A-100 Exterior Latex Satin, A82 Series (4.0 mils wet, 1.5 mils dry per coat).
- e. Satin Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Extreme Bond Bonding Primer, B51W00150 (3.1 mils wet, .9 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Satin, K43 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Satin, K43 Series (4.0 mils wet, 1.6 mils dry per coat).
- f. Flat Finish:
 - 1) 1st Coat: S-W Extreme Bond Bonding Primer, B51W00150 (3.1 mils wet, .9 mils dry).
 - 2) 2nd Coat: S-W A-100 Exterior Latex Flat, A6 Series.
 - 3) 3rd Coat: S-W A-100 Exterior Latex Flat, A6 Series (4.0 mils wet, 1.2 mils dry per coat).
- g. Flat Finish Early Moisture Resistant Finish:
 - 1) 1st Coat: S-W Extreme Bond Bonding Primer, B51W00150 (3.1 mils wet, .9 mils dry).
 - 2) 2nd Coat: S-W Resilience Exterior Latex Flat, K42 Series.
 - 3) 3rd Coat: S-W Resilience Exterior Latex Flat, K42 Series (4.0 mils wet, 1. 6 mils dry per coat).

PART 3 EXECUTION

3.1 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared; notify Architect of unsatisfactory conditions before proceeding. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.
- B. Proceed with work only after conditions have been corrected and approved by all parties, otherwise application of coatings will be considered as an acceptance of surface conditions.
- C. Previously Painted Surfaces: Verify that existing painted surfaces do not contain lead based paints, notify Architect immediately if lead based paints are encountered.

3.2 SURFACE PREPARATION

- A. General: Surfaces shall be dry and in sound condition. Remove oil, dust, dirt, loose rust, peeling paint or other contamination to ensure good adhesion.
 - Prior to attempting to remove mildew, it is recommended to test any cleaner on a small, inconspicuous area prior to use. Bleach and bleaching type cleaners may damage or discolor existing paint films. Bleach alternative cleaning solutions are advised.
 - 2. Remove mildew before painting by washing with a solution of 1 part liquid household bleach and 3 parts of warm water. Apply the solution and scrub the mildewed area. Allow the solution to remain on the surface for 10 minutes. Rinse thoroughly with clean water and allow the surface to dry before painting. Wear protective glasses or

- goggles, waterproof gloves, and protective clothing. Quickly wash off any of the mixture that comes in contact with your skin. Do not add detergents or ammonia to the bleach/water solution.
- 3. Remove items including but not limited to thermostats, electrical outlets, switch covers and similar items prior to painting. After completing painting operations in each space or area, reinstall items removed using workers skilled in the trades involved.
- 4. No exterior painting should be done immediately after a rain, during foggy weather, when rain is predicted, or when the temperature is below 50 degrees F (10 degrees C), unless products are designed specifically for these conditions. On large expanses of metal siding, the air, surface and material temperatures must be 50 degrees F (10 degrees F) or higher to use low temperature products.
- B. Aluminum: Remove all oil, grease, dirt, oxide and other foreign material by cleaning per SSPC-SP1, Solvent Cleaning.
- C. Block (Cinder and Concrete): Remove all loose mortar and foreign material. Surface must be free of laitance, concrete dust, dirt, form release agents, moisture curing membranes, loose cement, and hardeners. Concrete and mortar must be cured at least 30 days at 75 degrees F (24 degrees C). The pH of the surface should be between 6 and 9, unless the products are designed to be used in high pH environments. On tilt-up and poured-in-place concrete, commercial detergents and abrasive blasting may be necessary to prepare the surface. Fill bug holes, air pockets, and other voids with a cement patching compound.
- D. Concrete, SSPC-SP13 or NACE 6: This standard gives requirements for surface preparation of concrete by mechanical, chemical, or thermal methods prior to the application of bonded protective coating or lining systems. The requirements of this standard are applicable to all types of cementitious surfaces including cast-in-place concrete floors and walls, precast slabs, masonry walls, and shotcrete surfaces. An acceptable prepared concrete surface should be free of contaminants, laitance, loosely adhering concrete, and dust, and should provide a sound, uniform substrate suitable for the application of protective coating or lining systems.
- E. Cement Composition Siding/Panels: Remove all surface contamination by washing with an appropriate cleaner, rinse thoroughly and allow to dry. Existing peeled or checked paint should be scraped and sanded to a sound surface. Pressure clean, if needed, with a minimum of 2100 psi pressure to remove all dirt, dust, grease, oil, loose particles, laitance, foreign material, and peeling or defective coatings. Allow the surface to dry thoroughly. The pH of the surface should be between 6 and 9, unless the products are designed to be used in high pH environments.
- F. Copper and Stainless Steel: Remove all oil, grease, dirt, oxide and other foreign material by cleaning per SSPC-SP 2, Hand Tool Cleaning.
- G. Exterior Composition Board (Hardboard): Some composition boards may exude a waxy material that must be removed with a solvent prior to coating. Whether factory primed or unprimed, exterior composition board siding (hardboard) must be cleaned thoroughly and primed with an alkyd primer.
- H. Drywall Exterior: Must be clean and dry. All nail heads must be set and spackled. Joints must be taped and covered with a joint compound. Spackled nail heads and tape joints must be sanded smooth and all dust removed prior to painting. Exterior surfaces must be spackled with exterior grade compounds.
- I. Drywall Interior: Must be clean and dry. All nail heads must be set and spackled. Joints must be taped and covered with a joint compound. Spackled nail heads and tape joints must be sanded smooth and all dust removed prior to painting.

- J. Galvanized Metal: Clean per SSPC-SP1 using detergent and water or a degreasing cleaner to remove greases and oils. Apply a test area, priming as required. Allow the coating to dry at least one week before testing. If adhesion is poor, Brush Blast per SSPC-SP16 is necessary to remove these treatments.
- K. Plaster: Must be allowed to dry thoroughly for at least 30 days before painting, unless the products are designed to be used in high pH environments. Room must be ventilated while drying; in cold, damp weather, rooms must be heated. Damaged areas must be repaired with an appropriate patching material. Bare plaster must be cured and hard. Textured, soft, porous, or powdery plaster should be treated with a solution of 1 pint household vinegar to 1 gallon of water. Repeat until the surface is hard, rinse with clear water and allow to dry.
- L. Steel: Structural, Plate, And Similar Items: Should be cleaned by one or more of the surface preparations described below. These methods are used throughout the world for describing methods for cleaning structural steel. Visual standards are available through the Society of Protective Coatings. A brief description of these standards together with numbers by which they can be specified follow.
 - Solvent Cleaning, SSPC-SP1: Solvent cleaning is a method for removing all visible oil, grease, soil, drawing and cutting compounds, and other soluble contaminants. Solvent cleaning does not remove rust or mill scale. Change rags and cleaning solution frequently so that deposits of oil and grease are not spread over additional areas in the cleaning process. Be sure to allow adequate ventilation.
 - Hand Tool Cleaning, SSPC-SP2: Hand Tool Cleaning removes all loose mill scale, loose rust, and other detrimental foreign matter. It is not intended that adherent mill scale, rust, and paint be removed by this process. Before hand tool cleaning, remove visible oil, grease, soluble welding residues, and salts by the methods outlined in SSPC-SP1.
 - 3. Power Tool Cleaning, SSPC-SP3: Power Tool Cleaning removes all loose mill scale, loose rust, and other detrimental foreign matter. It is not intended that adherent mill scale, rust, and paint be removed by this process. Before power tool cleaning, remove visible oil, grease, soluble welding residues, and salts by the methods outlined in SSPC-SP1.
 - 4. White Metal Blast Cleaning, SSPC-SP5 or NACE 1: A White Metal Blast Cleaned surface, when viewed without magnification, shall be free of all visible oil, grease, dirt, dust, mill scale, rust, paint, oxides, corrosion products, and other foreign matter. Before blast cleaning, visible deposits of oil or grease shall be removed by any of the methods specified in SSPC-SP1 or other agreed upon methods.
 - 5. Commercial Blast Cleaning, SSPC-SP6 or NACE 3: A Commercial Blast Cleaned surface, when viewed without magnification, shall be free of all visible oil, grease, dirt, dust, mill scale, rust, paint, oxides, corrosion products, and other foreign matter, except for staining. Staining shall be limited to no more than 33 percent of each square inch of surface area and may consist of light shadows, slight streaks, or minor discoloration caused by stains of rust, stains of mill scale, or stains of previously applied paint. Before blast cleaning, visible deposits of oil or grease shall be removed by any of the methods specified in SSPC-SP1 or other agreed upon methods.
 - 6. Brush-Off Blast Cleaning, SSPC-SP7 or NACE 4: A Brush-Off Blast Cleaned surface, when viewed without magnification, shall be free of all visible oil, grease, dirt, dust, loose mill scale, loose rust, and loose paint. Tightly adherent mill scale, rust, and paint may remain on the surface. Before blast cleaning, visible deposits of oil or grease shall be removed by any of the methods specified in SSPC-SP 1 or other agreed upon methods.
 - 7. Power Tool Cleaning to Bare Metal, SSPC-SP11: Metallic surfaces that are prepared according to this specification, when viewed without magnification, shall be free of all visible oil, grease, dirt, dust, mill scale, rust, paint, oxide corrosion products, and other foreign matter. Slight residues of rust and paint may be left in the lower portions of pits if the original surface is pitted. Prior to power tool surface preparation, remove visible

- deposits of oil or grease by any of the methods specified in SSPC-SP1, Solvent Cleaning, or other agreed upon methods.
- 8. Near-White Blast Cleaning, SSPC-SP10 or NACE 2: A Near White Blast Cleaned surface, when viewed without magnification, shall be free of all visible oil, grease, dirt, dust, mill scale, rust, paint, oxides, corrosion products, and other foreign matter, except for staining. Staining shall be limited to no more than 5 percent of each square inch of surface area and may consist of light shadows, slight streaks, or minor discoloration caused by stains of rust, stains of mill scale, or stains of previously applied paint. Before blast cleaning, visible deposits of oil or grease shall be removed by any of the methods specified in SSPC-SP1 or other agreed upon methods.
- 9. High- and Ultra-High Pressure Water Jetting for Steel and Other Hard Materials: SSPC-SP12 or NACE 5: This standard provides requirements for the use of high- and ultra-high pressure water jetting to achieve various degrees of surface cleanliness. This standard is limited in scope to the use of water only without the addition of solid particles in the stream.
- 10. Water Blasting, SSPC-SP12/NACE No. 5: Removal of oil grease dirt, loose rust, loose mill scale, and loose paint by water at pressures of 2,000 to 2,500 psi at a flow of 4 to 14 gallons per minute.
- M. Vinyl Siding, Architectural Plastics, EIFS and Fiberglass: Clean vinyl siding thoroughly by scrubbing with a warm, soapy water solution. Rinse thoroughly. Do not paint vinyl siding with any color darker than the original color, unless the paint system features Sherwin-Williams VinylSafe technology. Painting with darker colors that are not Sherwin-Williams VinylSafe may cause siding to warp. Follow all painting guidelines of the vinyl manufacturer when painting. Only paint properly installed vinyl siding. Deviating from the manufacturer's painting guidelines may cause the warranty to be voided.
- N. Stucco: Must be clean and free of any loose stucco. If recommended procedures for applying stucco are followed, and normal drying conditions prevail, the surface may be painted in 30 days. The pH of the surface should be between 6 and 9, unless the products are designed to be used in high pH environments such as Loxon.
- O. Wood: Must be clean and dry. Prime and paint as soon as possible. Knots and pitch streaks must be scraped, sanded, and spot primed before a full priming coat is applied. Patch all nail holes and imperfections with a wood filler or putty and sand smooth.

3.3 INSTALLATION

- A. Apply all coatings and materials with the manufacturer's specifications in mind. Mix and thin coatings according to manufacturer's recommendations.
- B. Do not apply to wet or damp surfaces. Wait at least 30 days before applying to new concrete or masonry. Or follow manufacturer's procedures to apply appropriate coatings prior to 30 days. Test new concrete for moisture content. Wait until wood is fully dry after rain or morning fog or dew.
- C. Apply coatings using methods recommended by manufacturer.
- D. Uniformly apply coatings without runs, drips, or sags, without brush marks, and with consistent sheen.
- E. Apply coatings at spreading rate required to achieve the manufacturers recommended dry film thickness.
- F. Regardless of number of coats specified, apply as many coats as necessary for complete hide, and uniform appearance.

G. Inspection: The coated surface must be inspected and approved by the Architect just prior to the application of each coat.

3.4 PROTECTION

- A. Protect finished coatings from damage until completion of project.
- B. Touch-up damaged coatings after substantial completion, following manufacturer's recommendation for touch up or repair of damaged coatings. Repair any defects that will hinder the performance of the coatings.

END OF SECTION

SECTION 09 91 00 PAINTING

1. GENERAL

The work in this Section shall be performed in accordance with the General Conditions of the Contract, which are made a part hereof by reference.

2. SCOPE OF THE WORK

Includes the painting work of all the building exteriors sufaces; exterior doors; windows; electrical sub-stations and other elements specified herein. It is the intention to describe all painting work required, with the exception of the excluded work indicated below, and the Contractor shall so execute all required painting work, regardless of whether such work may be indicated on the drawings or schedule of finishes.

3. SUBMITTALS

- a. .Submit for preliminary approval of the Architect samples of all colors, and sample panels of metal and wood finishes made on materials of the same kind as those used in the building.
- b. After preliminary approval of samples and colors, prepare ten (10) 5'x5' sample panels on the actual surfaces at the building in the areas where work is to be done and obtain Architect's final approval before proceeding with work.
- c. All work shall be executed in strict accordance with approved sample panels.

4. PRODUCT DELIVERY, HANDLING AND STORAGE

Materials shall be delivered to the job site in unopened containers which shall show the designated name, formula or specifications, color, manufacturer's directions, and name of manufacturer, all of which shall be plainly legible at time of use. Pigmented paints shall be furnished in containers not larger than 5 gallons. Materials listed in the painting schedule without reference to a particular product and not further described hereinafter shall be products which have had a minimum of two (2) years satisfactory field service. Laboratory tests simulating field conditions will not be accepted in lieu of actual fields results.

All materials used on the job shall be stored in a single place as designed. Such storage place shall be kept clean and all damage to it or its surroundings shall be repaired. Any oily rags, waste, etc., must be removed from the building every night and every precaution taken to avoid the danger of fire.

5. <u>MATERIALS</u>

- a. All paints shall be equal or similar to the top of the line quality of Glidden Mnfg. Co.
 - 1) Exterior cement plasteres surfaces shall receive one coat of Glid Seal Waterproofing Sealer No. 19528/29 spray applied and two (2) finish coats of Spread Ultra Exterior Flat Latex House & Trim Paint No. 65XX. Primer shall have a dry mil thickness of 4. Finish shall have a dry mil thickness of 8.
 - 2) Exterior hollow metal doors, frames, trim, exposed structural steel and miscellaneous metal paint shall receive two coats of Devguard Alkyd Industrial Enamel No. 4308-XXXX. Finish shall have a dry mil thickness of 4.
 - 3) Interior and Exterior galvanized surfaces shall receive one primer coat of Devguard Alkyd All Purpose Metal No. 4120-1000 and two coats of Devguard Alkyd Industrial Enamel No. 4308-XXXX Primer to have a dry mil thickness of 2 and finish to have a dry mil thickness of 4.

- 4) Interior and Exterior ferrous metal surfaces shall receive one primer coat of Devguard Alkyd Metal No. 4100-7100 and two coats of Devguard Alkyd Industrial Enamel No. 4308-XXXX Primer to have a dry mil thickness of 2 and finish to have a dry mil thickness of 4.
- 5) Fillers, sealers, primers and undercoaters shall be as recommended for optimum results by the manufacturer of the paint used.
- b. The above list is intended to present a general idea of the materials required, but is not to be interpreted as necessarily complete or exact. Before proceeding with the painting work the Contractor shall prepare and submit for approval by the Architect, a paint schedule showing the paints he proposes to use in each area to be finished. No painting work shall be done until this schedule has been finally approved.
- c. Primers and undercoats shall be by the same manufacturer as the finish coat, and as approval.
- d. Color pigments shall be color stable to sunlight and atmosphere, finely ground.

6. EXECUTION

- a. Before starting any work, surfaces to receive paint finishes shall be examined carefully for defects which cannot be corrected by the procedures specified herein and which might prevent satisfactory painting results. Work shall not proceed until such damages are corrected. The commencing of work in a specific area shall be construed as acceptace of the surfaces, and thereafter the Contractor shall be fully responsible for satisfactory work as required herein.
- b. Before painting is started in any area, broom clean and remove excessive dust.
- c. After painting operation begin in a given area, broom cleaning will not be allowed; cleaning shall then be done only with commercial vacuum cleaning equipments.

- d. Adequate illumination shall be provided in all areas where painting operations are in progress.
- e. Only skilled workers shall be employed. Application may be by brush, roller or spray, as approved by owner and the architect.
- f. Remove and protect hardware, accessories, device plates, lighting fixtures, factory finished work, and similar items, or provide ample in-place protection. Upon completion of each space, carefully replace all removed item.
- g. Remove electrical panel box cover and doors before painting walls. Paint separately and reinstall after all paint is dry.
- h. All materials shall be evenly spread and flowed-on smoothly to avoid runs, sags, holidays, brush marks, air bubbles and excessive roller stipple.
- i. Coverage and hide shall be complete. When color, stain, dirt or undercoats show through final coat of paint, the surface shall be covered by additional coats until the paint film is of uniform finish, color, appearance and coverage, at no additional cost to the owner.
- j. All coats shall be dry to manufacturer's recommendations before applying succeeding coats.
- k. All suction spots or "hot spots" in plaster and/or cement after the application of the first coat shall be touched up before +

7. PREPARATION OF SURFACES

a. General

- 1) Surfaces shall be clean, dry and adequately protected from dampness.
- 2) All plastered surfaces shall be waterblasted @ 3000 PSI.
- 3) Surface shall be free of any foreign materials which will adversely affect adhesion or appearance of applied coating.

- 4) Mildew shall be removed and the surface neutralized per the coating manufacturer's recommendations.
- 5) Efflorescence on any area will be corrected before painting.

b. Concrete, Masonry and Stucco

- 1) Patch large openings and holes and finish flush with adjacent surface. After priming, fill any remaining small holes with prepared patching material.
- 2) Patch small openings with Anvil Elastomeric Textured No. 1214#1215 No. 12414/12415
- 3) Following manufacturers recommendations, patch loose cement plasters with Thorite Patching Material No. 14013
- 4) Masonry and concrete surface shall be cleaned until free of all loose and foreign materials and excess mortar, using metal scrapers and wire brushes if necessary. Grease and oil spots shall be removed by suitable cleaning compound and then rinsed with clean water to remove all traces of Alkali. Efflorescence (Alkali salts) shall be removed by washing with a 5 to 10 per cent solution of muriatic acid. Allowed to stand unit effervescing ceases, then rinsing with clear water to remove all traces of acid. Treated surfaces shall be allowed to dry throughly before any oil base paint is applied. Concrete surfaces shall be washed with zinc. sulphate solution.

c. Ferrous Metal Surfaces

- 1) Remove dirt and grease with Thinner Low Odor No. 38121-90 and wipe dry with clean cloths.
- 2) Remove rust, mill scale and defective paint down to sound surfaces or bare metal using scraper, sandpaper or wire brush as necessary. Grind, disc sand, etc., if necessary to remove shoulders at edge of sound paint to prevent them from photographing through finish coats.
- 3) Touch up all bare metal and damaged shop coats with specified shop coat primer.

4) For ferrous surfaces with shop coats touched up, as above required, the first coat as listed in the following schedule will be applied to the dry mil film thickness specified.

d. Galvanized Metal Surfaces

1) Remove dirt and grease with Thinner Low Odor No. 38121-90 and wipe dry with clean cloths.

e. Wood to be Painted

- 1) Sandpaper to a smooth and even surface, then dust off.
- 2) Apply shellac, four (4) pounds cut, to all knots, pitch and resinous sapwood prior to application of specified primer coats.
- 3) After priming coat has dried, putty all nail holes, cracks, open joints and other defects. Putty shall be colored to match primer; if putty is not compatible with finish, spot prime puttied areas.

f. Existing Surfaces to be Repainted

Where existing work is cut, patched, or added to, all surfaces shall be painted or touched up to match present work as closely as possible. Existing work, where scheduled for repainting, shall be put in condition to provide good adhesion and to receive paint.

g. Aluminum shall be cleaned with a weak solution of phosphoric acid solution containing suitable degreasing compound then rinsed with clean water and allowed to dry before bituminous protective paint is applied.

9. COATING

- a. Unless otherwise specifically so directed in writting by the architect, all paints and finishes shall be applied in strict accordance with manufacturer's printed instructions.
- b. All wood surfaces, except those to receive natural finish, and millwork shall receive one (1) coat enamel primer, as recommended by manufacturer and two (2) finish coat semi-gloss enamel.
- c. All wood doors and bases shall receive mahogany oil stain and one (1) coat clear matte laquer.

d. All paints shall be applied to the dry and wet mil thickness as recommended by the paint manufacturer and/or specified herein.

8. WORKMANSHIP

Each coat of paint and enamel shall be evently worked out and allowed to become dry before any subsequent coat is applied or rubbing done, and shall be a different tint from that of the preceeding coat. Finish coatts shall be the exact shades selected. The finished work shall be free from runs and sags, detective coverage and clogging of lines and angles. Edges of paint adjoining other material or other colors shall be full and clean-cut without overlapping.

9. CLEAN UP

- a. Upon termination of painting work the Contractor shall remove all masking materials, tools, scaffolding surplus materials from the premises and leave area clean for the work of other trades or for the uses intended.
- b. Contractor should clean off all misplaced paint, spots and spills.

END OF SECTION

SECTION 09 94 10

FIELD PAINTING

PART 1 - GENERAL

1.01 DESCRIPTION:

- A. Furnish and apply required paints and coatings. Prepare, clean, and finish all surfaces specified, scheduled or otherwise indicated to be field painted.
 - The terms "paint" and "coating" used herein include emulsions, enamels, paints, stains, varnishes, sealers, and other coatings, organic or inorganic, whether used as intermediate, or finish coats.
- B. Complete painting in accordance with Specifications, and paint manufacturer's current surface preparation and application instructions.

1.02 RELATED WORK:

 Manufacturer's standard prime paint finishes are specified under the applicable Sections for Architectural.

1.03 SUBMITTALS:

- A. To aid in determining coating compatibility, submitfollowing:
 - 1. List of coating products proposed, giving brand, type and manufacturer.
 - 2. Manufacturer's current printed recommendations and product data sheets for each.
 - 3. Field painting applicator's correspondence for determining compatibility of field coatings with primers and for selecting manufacturer producing field coats.
- B. Submit color chips of materials proposed, and sample panels of paints and coatings selected. Make samples not less than 12-in. square, on sheet metal for metal coatings, on cement asbestos board for masonry and concrete coatings.
- C. Submit Manufacturer's certificates and test reports for the following materials:
 - 1. List materials

1.05 PAINT STORAGE AND MIXING AREAS, AND WASTE DISPOSAL:

A. Store paints and painter's materials only in area or areas designated solely for this purpose. Confine mixing, thinning, clean-up and associated operations, and storage of painting debris before authorized disposal, to these areas.

- B. Do not use plumbing fixtures, piping or mechanical equipment for mixing or disposal of paint materials.
 - 1. Transport water to paint area by approved temporary hose or piping.
 - 2. Store waste temporarily in closed, nonflammable containers until final disposal. Keep no rubbish in painter's area longer than 24 hours. Finally dispose of waste in an approved disposal system outside of buildings.

1.06 DELIVERY, HANDLING, STORAGE, PROTECTION:

- A. Deliver materials to painter's area in original, unbroken, containers with name and analysis of product, manufacturer's name, and shelf life date. Do not use or retain contaminated, outdated, prematurely opened, or diluted materials.
- B. Store coated items carefully. Avoid damaging or dirtying coatings, by contact with soil, pavement or other harmful contacts which might necessitate special cleaning. Use suitable blocking during storage.
- C. Do not expose primed surfaces to weather for more than six months before top coating. Allow less open time if recommended by coating manufacturer.
- D. During surface preparation, cleaning and painting operations, protect all surfaces not to be painted.
- E. Protect coated items, whether prime or finish, from damage due to shipping and handling. For items with type E or S service coatings; use padding, blocking, fabric slings and extra care.
- F. Upon completion of field painting, ensure coatings undamaged and in good condition. Make good damage or coating deterioration resulting from failure to observe foregoing requirements.

1.07 JOB CONDITIONS:

- A. Environmental Requirements:
 - 1. Comply with manufacturer's recommendations as to environmental conditions under which coatings and coating systems can be applied.
 - 2. Do not apply coatings when dust is being generated.

B. Protection:

1. Cover or otherwise protect finish work of other trades and surfaces not being painted concurrently or not to be painted.

PART 2 - PRODUCTS

2.01 MATERIALS: GENERAL:

- A. Paint Coatings: Suitable for intended use, recommended by their manufacturer for intended service.
- B. Products Used: Minimum of five years satisfactory use under similar service conditions.
- C. Use products of one manufacturer in any one paint coating system; all coating materials compatible. Coatings for touch-up; same as original.

2.02 COLORS AND FINISHES:

- A. All finish colors as selected from manufacturer's color chips. Color schedule will indicate colors to be used. Match final colors to selected color chips, as scheduled.
- C. To provide contrast between successive coats, lightly tint each coat to distinguish it from preceding coats.
- D. Unless otherwise indicated, for finish paint use gloss or semigloss on wood and metal, and matte finish or flat on masonry and concrete.

PART 3 - EXECUTION

3.01 INSPECTION:

- A. Examine surfaces scheduled to receive paint and finishes for conditions that will adversely affect execution, permanence or quality of work and which cannot be put into an acceptable condition through preparatory work.
- B. Do not proceed with surface preparation or coating application until conditions are suitable.

3.02 PREPARATION:

A. Basic Steps:

- 1. Coordinate cleaning and painting operations to eliminate contamination of one by the other.
- Maintain all coating materials at manufacturer's recommended mixing and application temperatures for not less than 24 hours before use. Have clean, proper containers, spray equipment, applicators and accessory items ready for use before decanting or mixing paint materials.
- 3. Ensure proper coordination of materials to be applied hereunder with previous coatings on affected surfaces. Have all manufacturer's written directions on hand, and follow them strictly, except where otherwise specified.
- 4. Carefully coordinate preparation and material compatibility requirements with the work under Section 09940.

B. PAINT REMOVAL:

- 1. Coordinate cleaning and painting operations to eliminate contamination of one by the other.
- 2. Paint must be removed from cracked finishes before surface preparation. Removal methods are limited to:
 - Scrapping
 - o vapor removal
 - o heat gun removal
- C. Before any paint application, carefully clean all surfaces to be coated of dust, dirt, grease, loose rust, mill scale, paint unsuitable for top coating, efflorescence, oil, moisture, foreign matter or conditions detrimental to coating bond and durability.
 - Following cleaning, apply preparatory treatment in strict accordance with manufacturer's written instructions.

2. Fill imperfections and holes in surfaces to be painted.

3.03 TOUCH-UP:

A. Before applying field coat, touch-up abraded areas of shop coats with paint of the same type. Apply an entire coat if necessary. Touch-up coats are in addition to, and not a substitute for first field coat. Clean deteriorated surfaces to bare wood before applying touch-up coat.

3.04 APPLICATION:

A. In general, apply minimum of one under coat and one finish coat to all previously primed surfaces. Following careful inspection of surfaces not previously primed, prepare and clean as specified, apply proper prime coat and minimum of one under coat and one finish coat. Refer to Paint Schedule at end of section.

B. Conditions:

- 1. Do not apply paints or other finish to wet or damp surfaces, except in accordance with instructions of manufacturer. Do not apply exterior paint during cold, rainy, or frosty weather, or when temperature is likely to drop to freezing. Avoid painting of surfaces while they are exposed to the sun.
- 2. Paint surfaces which have been cleaned, pretreated, or otherwise prepared for painting with first field coat as soon as practicable after such preparation has been completed, but in any event prior to deterioration of prepared surface.

C. Methods:

- 1. Spraying with adequate apparatus may be substituted for brush application of suitable paints and in locations suitable for spraying.
- Prepare surfaces, mix and apply paint materials in strict accordance with manufacturer's printed instructions and recommendations, except where specifically directed otherwise. Control temperature of materials upon mixing and application, surface temperature and condition, thinning and modifying.
- 3. Protect surfaces to be coated, before, during and after application unless ambient weather conditions are favorable.

D. Workmanship:

- 1. Spot prime with aluminum paints, all exposed nails and other ferrous metal on surfaces to be painted with water-thinned paints.
- Apply coating materials to meet manufacturer's spreading rate and dry film thickness recommendations. Dry film thickness specified are constant for brush, spray, roller or other form of application.
 - a. Control thinning for spray use and to manufacturer's printed instructions, and produce specified dry film thickness on level surfaces, interior and exterior angles.

- b. Record quantities of materials of each type, for each coat, used in each location.
- 3. Apply paints and coatings using skilled painters, brushed or rolled out carefully to a smooth, even coating without runs or sags. Flow enamel on evenly and smoothly. Allow each coat of paint to dry thoroughly, on the surface and throughout the film thickness, before the next coat is applied. High polymer coatings may be excepted from the drying requirement if recoat time is specified by manufacturer.
- 4. Finish surfaces: Uniform in finishes and colors, and free from flash spots and brush marks.
- 5. Accessory items, finish hardware, lighting fixtures, escutcheons, plates, trim and similar finish items not to be painted: Remove or carefully mask before painting adjacent surfaces. Carefully replace and reposition upon completion of adjacent painting and cleaning work.

3.05 PROTECTION, CLEAN-UP:

A. Protect all materials and surfaces painted or coated under this section, both before and after application. Also protect all adjacent work and materials by the use of sufficient drop cloths during the progress of this work. Upon completion of the work, clean up all paint spots, oil, and stains from floors, glass, hardware, and similar finished items.

3.06 PAINT SCHEDULE:

A. Coordinate, schedule and confirm the various cleaning, touch-up and finishing operations. Ensure the transmission of materials data, color selections and coating system methods between the coating applicators. Take responsibility for not exceeding exposure and recoat time limits.

3.07 FINAL TOUCH-UP:

- A. Prior to final completion and acceptance, examine painted and finished surfaces and retouch or refinish as necessary and required to leave surfaces in perfect condition.
- B. After doors have been fitted and hung, refinish edges, tops and bottom.

END OF SECTION

SECTION 10 82 13 EXTERIOR GRILLES AND SCREENS

PART 1 GENERAL 1.01 SECTION INCLUDES

- A. Expanded Metal Window Grills.
- B. Perforated Steel Grills.

1.02 QUALITY ASSURANCE

- A. Where windows are indicated or required for proper egress. Provide assemblies that comply with NFPA 101 sec. 5-2.1.7.2 for push or pull type exit devices.
- B. All grills shall qualify as a HUD "HEAVY" (level 5) as certified by NAMI or similar testing agencies. At a minimum they shall met the following standard tests:
 - 1. Impact Test: Resist 100 foot-pounds of force without stretching the grill material more than 3" and without tearing the grill fabric at any point.
 - Forced Entry Test: Resist prying load of 150 pounds and simultaneous pulling load of 300 pounds without springing the lock or bending the frame. This requirement is subject to review and approval by the Denver Fire Department.
 - 3. Sag Test: Resist 90 pounds of weight on the open grill with no more than a .063" sag in the grill.

1.03 SUBMITTALS

A. Submit product literature and test results to the Architect.

PART 2 PRODUCTS 2.01 ACCEPTABLE MANUFACTURERS

- A. Provide exterior window grills as manufactured by one of the following:
 - 1. Avant Guards, Inc.
 - 2. Kane Manufacturing Corp.

2.02 FABRICATION

- A. Welding shall comply with the requirements of AWS. Grind welds smooth.
- Window grills, unless otherwise noted by DPS, shall cover the entire window opening.
- C. Where hinged grills cannot be opened due to obstructions, provide removable sections.
- D. Unless otherwise noted by DPS, provide windows at roof levels with hinged grills at lower sash.

2.03 MATERIALS

A. Frames:


- 1. Galvanized Steel 10 gauges (12-gauge subframe).
- 2. Extruded Aluminum 10 gauge (12 gauge subframe).
- 3. Hot Rolled Steel 10 gauge (12 gauge subframe), ASTM A36.
- 4. Cold Rolled Steel 10 gauge (12 gauge subframe), ASTM A611, Grade C.
- 5. Wrought Iron 10 gauge (12 gauge subframe). B. Grills:

- 1. Expanded Perforated Steel, Various Patterns.
- a) Standard: 16 gauge galvannealed metal having 63% open area with 5/32" holes on 3/16" stagger centers, and shall comply with ASTM A568.
- 2. Steel Wire Mesh Diamond or Square, 3/8" clear opening is maximum. C. Connections shall be:
 - 1. Galvanized Steel Bolts.
 - 2. Stainless Steel Bolts.
- D. All components shall be isolated from dissimilar metals as recommended by the grill manufacturer and as approved by the architect.
- E. Hinges: A minimum of 2 heavy duty hinges shall be provide for a 4 foot long grill and a minimum of 4 for an 8 foot long grill, or as otherwise approved in writing by DPS.

END OF SECTION 10 82 13


IMAGE TAKEN ON SITE VISIT

SHP




RESTAURACIÓN EL CORTIJO


CATASTRO 273-000-001-02 Km18.5, C. PR 162, Barranquitas, 00705



BARRANQUITAS, BO. PUEBLO - 4 DE ABRIL DEL 2011




MAPA DE CLALIFICACIÓN DE SUELOS



FLOOD MAP PANEL 1170H MAP 72000C1170H - APRIL 13, 2018





EL CORTIJO



FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

ro, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversiór por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia va sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y

PROFESSIONAL TEAM:

disciplinaria por la OGPe.

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

No.	Issue	Date
$\overline{\wedge}$		
$\overline{\wedge}$		
	rawn by	

GM | EM | CB | LR

SHEET TITLE AND NUMBER:

DEMOLITION NOTES:

- EXISTING CONDITIONS ILLUSTRATED AS OF JUNE 28, 2022
- IT IS NOT THE INTENTION OF THE A/E FIRM TO COVER ALL REQUIRED DEMOLITION AND CLEANING WORK IN THESE DRAWINGS, NOR TO ANTICIPATE EVERY CIRCUMSTANCE UNDER WHICH SPECIFIC TASKS SHALL BE PERFORMED. AS THE INTENTION IS TO ILLUSTRATE ONLY THE MOST SIGNIFICANT DEMOLITION WORK IN THE DRAWINGS, THE G.C. SHALL BE RESPONSIBLE FOR VERIFYING WHICH RESTORATION WORKS REQUIRE DEMOLITION.
- ALL DEMOLITION WORK NOT SHOWN IN DRAWINGS, BUT NECESSARY TO PERFORM THE ENTIRE SCOPE OF THE PROJECT SHALL BE DONE BY THE GENERAL CONTRACTOR AT NO EXTRA COST AND TIME NO MATTER THE SIZE.
- IT IS THE INTENTION OF THE A/E FIRM TO PRESERVE HISTORIC AS MUCH AS POSSIBLE AND ONLY REPLACING MATERIAL WHEN ABSOLUTELY NECESSARY.
- CONTRACTOR SHALL FURNISH ALL LABOR AND MATERIALS REQUIRED TO COMPLETE THE DEMOLITION, SELECTIVE REMOVAL AND SUBSEQUENT OFF-SITE DISPOSAL OF ALL ITEMS WITHIN THE PROJECT AREA.
- SUBMIT SCHEDULE INDICATING PROPOSED SEQUENCE OF OPERATIONS FOR SELECTIVE DEMOLITION WORK TO THE OWNER FOR REVIEW PRIOR TO COMMENCEMENT OF WORK. INCLUDE COORDINATION FOR SHUT-OFF, CAPPING, AND CONTINUATION OF UTILITY SERVICES AS REQUIRED, TOGETHER WITH DETAILS FOR DUST AND NOISE CONTROL PROPOSED SEQUENCE OF OPERATION SHALL ENSURE THE INHABITANTS ARE UNDISTURBED.
- THE CONTRACTOR, PRIOR TO COMMENCEMENT OF THE WORK, SHALL VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS AT THE PROJECT'S SITE AND SHALL NOTIFY THE ARCHITECT, IN WRITING, OF ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS AND THE CONTRACT DOCUMENTS WHICH MIGHT AFFECT PROPER DEMOLITION AND CONSTRUCTION WORKS SCHEDULE AND/OR PERFORMANCE. THEREFORE, THE CONTRACTOR SHALL CERTIFY THAT HE HAS VISITED THE PROJECT SITE AND FAMILIARIZED HIMSELF WITH THE EXISTING CONDITIONS PRIOR TO ENTERING INTO A CONSTRUCTION AGREEMENT WITH THE OWNER. NO ALLOWANCE WILL BE MADE FOR ADDITIONAL COSTS DUE TO CONTRACTOR'S FAILURE TO VERIFY EXISTING CONDITIONS AND DIMENSIONS.
- DURING DEMOLITION PHASE AND CONSTRUCTION. THE GENERAL CONTRACTOR SHALL INSTALL EXTENSIVE SIGNING IN WORKING AT PUBLIC AREAS TO WARN WORKERS AND GENERAL PUBLIC ABOUT UNSAFE AREAS. SIGNS SHALL COMPLY WITH OSHA REGULATIONS.
- IF HAZARDOUS MATERIALS ARE ENCOUNTERED DURING DEMOLITION OPERATIONS, G.C. TO STOP WORK IN THAT AREA AND NOTIFY OWNER IN WRITING. GC SHALL COMPLY WITH APPLICABLE REGULATIONS, LAWS, AND ORDINANCES CONCERNING REMOVAL, HANDLING AND PROTECTION AGAINST EXPOSURE OR ENVIRONMENTAL POLLUTION.
- NONE OF THE WALLS TO DEMOLISH ARE REINFORCED CONCRETE. IF THE CONTRACTOR FINDS A REINFORCED CONCRETE WALL DURING THE DEMOLITION, THE CONTRACTOR SHALL STOP CONSTRUCTION IMMEDIATELY AND REPORT TO THE ARCHITECT.
- THE OWNER WILL BE RESPONSIBLE FOR THE REMOVAL OF ALL LOOSE ITEMS SUCH AS ARTWORK, FRAMED PICTURES, FURNITURE, ETC...
- CONTRACTOR MUST PRESERVE ALL HISTORIC ITEMS INDICATED TO BE REMOVED AND STORE THEM IN A SECURE PLACE UNTIL REVIEW BY A/E FIRM. ITEMS REVIEWED AND APPROVED BY A/E FOR REMOVAL SHALL DISPOSED OF BY THE CONTRACTOR.
- 13. ALL ITEMS INDICATED TO BE RELOCATED ARE TO BE CAREFULLY REMOVED, CLEANED, REPAIRED TO A LIKE-NEW CONDITION AND STORED IN A SECURE PLACE UNTIL REINSTALLED AS SHOWN ON CONSTRUCTION PLAN OR RCP.
- 14. CONTRACTOR MUST FOLLOW ALL PROPER AND LEGAL PROCEDURES REGARDING WASTE DISPOSAL. G.C. SHALL PROVIDE A/E EVIDENCE OF DISPOSAL AT THE APPROPRIATE LANDFILL SITE.
- 15. THE OWNER SHALL BE CONTACTED AND NOTIFIED IMMEDIATELY IF ASBESTOS OR LEAD PAINT ARE FOUND IN ANY AREAS OR STRUCTURES OF THE PROJECT NOT PREVIOUSLY IDENTIFIED BY THE ENVIRONMENTAL CONSULTANT.
- 16. TRASH AND DEBRIS TO BE REMOVED DAILY. KEEP SITE CLEAN.
- ALL SCRAP MATERIAL FROM THE DEMOLITION WORKS SHALL BE LEGALLY DISPOSED.
- THE CONTRACTOR SHALL TAKE THE REQUIRED MEASUREMENTS TO CONTROL THE DEMOLITION DUST FROM SPREADING OUTSIDE OF AREAS THAT ARE GOING TO BE INTERVENED. WATER SPRINKLING SHALL NOT BE USED AS A FORM OF DUST CONTROL.
- THE CONTRACT CANNOT STORE SCRAP MATERIALS FROM DEMOLITIONS OUTSIDE OF THE DESIGNATED AREAS. DURING THE PRE-CONSTRUCTION PHASE THE G.C. SHALL CONSULT WITH A/E WHICH ARE THE DESIGNATED AREAS FROM SCRAP MATERIALS.
- ALL CONSTRUCTION, DEMOLITION & RENOVATION ACTIVITIES SHALL COMPLY WITH NFPA 241, OSHA AND ANY REGULATION THAT INTERFERES WITH THE HEALTH, WELFARE, AND SAFETY OF HIS EMPLOYEES AND FUTURE BUILDING OCCUPANTS.
- G.C. SHALL MAINTAIN ON SITE FIRE EXTINGUISHERS TO PROTECT THE HISTORIC PROPERTY IN THE EVENT OF FIRE.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO MEET ALL OSHA REQUIREMENTS & NORMATIVES.
- 23. EXIT ACCESS AND EXITS ARE TO REMAIN CLEAR AND UNOBSTRUCTED.
- ANY PART OF THE WORK AND/OR THE EXISTING BUILDING DAMAGED BY THE DEMOLITION PHASE SHALL BE RESTORED TO ITS ORIGINAL CONDITION ACCORDING TO A/E INSTRUCTIONS AT NO COST TO THE
- ALL DEMOLITION/CONSTRUCTION WORKS SHALL BE COORDINATED WITH THE OWNER IN ORDER TO PREVENT AND AVOID POSSIBLE CONFLICTS WITH THE OWNER'S NORMAL OPERATING CONDITIONS.
- THE CONTRACTOR MUST INCLUDE IN THE ECONOMIC PROPOSAL A DETAILED DESCRIPTION OF THE MEANS AND METHODS THAT WILL BE DONE DURING DEMOLITION PHASE TO MINIMIZE AIR POLLUTION.
- GC SHALL BE RESPONSIBLE FOR DEMOLITION MEANS AND METHODS AS WELL AS TO PROVIDE THE NECESSARY BRACING TO GUARANTEE STRUCTURAL STABILITY DURING THE DEMOLITION/REMOVAL PROCESS OF THOSE ELEMENTS INSTRUCTED ON PLANS AND DURING NEW CONSTRUCTION. IN CASE OF ANY STRUCTURAL COLLAPSE OF ANY ELEMENT TO REMAIN, THESE SHALL BE REPLACED USING ORIGINAL MATERIALS, AT NO COST TO OWNER.

29. DURING THE DEMOLITION PROCESS, THE GENERAL CONTRACTOR IS RESPONSIBLE IN MAINTAINING A HEALTHY AIR QUALITY THAT DOES NOT AFFECT THE HEALTH OF HIS EMPLOYEES.

OBTAIN THE CES PLAN APPROVAL IF APPLICABLE.

- 30. G.C. SHALL PROTECT ALL ITEMS THAT ARE TO REMAIN SUCH AS FLOORS, WALLS, FINISHES, INFRASTRUCTURE, CEILINGS, DOORS, EQUIPMENT, DOOR HINGES, RAILINGS, BALUSTERS, WALL BASES, LAMPS, ETC...
- 31. IF ANY OTHER ELEMENT NOT INSTRUCTED IN THIS DRAWINGS IS NEEDED TO BE REMOVED IN ORDER TO FULFILL THE PROJECT SCOPE, G.C. SHALL NOTIFY AND CONFIRM WITH THE ARCHITECT. SUCH WORK SHALL BE AT NO ADDITIONAL COST TO THE OWNER.
- 32. IF THE COMPLETION OF NEW ENGINEERING INFRASTRUCTURE REQUIRED ADDITIONAL DEMOLITION BY THE G.C. IN WALLS, CEILINGS AND FLOORS THAT IS NOT EXPLICITLY SHOWN IN DRAWINGS. G.C. SHALL CONTEMPLATE THIS ADDITIONAL DEMO AND THE PATCHING AND REPAIRS REQUIRED TO LEAVE AREA AS NEW.
- 33. IF PATCHING AND REPAIRS MAY REQUIRE NEW MOLDINGS, NEW GYPSUM, NEW WALL BASES, NEW A.C.T., NEW FLOORS, AMONG OTHERS. NEW WOOD BASES, TRIMS, MOLDINGS AND CASINGS SHALL HAVE THE LENGTH OF THE ORIGINAL ELEMENT BEING REPLACED. THE INTENTION IS TO MINIMIZE JOIN AND SHORT MEMBERS.
- 34. G.C. SHALL DISCUSS WITH ARCHITECT PATH OF NEW INFRASTRUCTURE PRIOR TO DEMOLITION. IN ORDER TO DISCUSS HOW TO MINIMIZE DEMO, PATCHING, AND REPAIRS OF EXISTING WALLS/CEILINGS/FLOORS. G.C. REQUIRES ARCHITECT APPROVAL TO PROCEED WITH DEMOLITIONS.
- 35. HISTORIC INTERIORS SHOULD BE PROTECTED FROM POTENTIAL DAMAGE DURING CONSTRUCTION WORK. IF ANY DAMAGE DOES OCCUR, THE CONTRACTOR SHALL RESTORE ANY DAMAGE TO ITS ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE OWNER.
- 36. ALL CONTAMINATED MATERIALS IDENTIFIED BY ENVIRONMENTAL HEALTH & SAFETY SERVICES SHALL BE REMOVED AND SHOULD BE DONE AS PER JCA AND EPA REGULATON. G.C. SHALL OBTAIN ALL THE NECESSARY PERMITS TO PERFORM THE WORKS AND LATER SUBMIT TO THE OWNER ALL THE CERTIFICATIONS REQUIRED BY LAW STATING THAT ALL CONTAMINATED MATERIALS WERE REMOVED FROM THE PROJECT AND LEGALLY DISPOSED.
- 37. ALL ELECTRICAL WORK SHALL BE DONE BY A LICENCED ELECTRICIAN.
- 38. G.C. SHALL ENSURE A SUPERINTENDENT MUST BE PRESENT DURING THE ENTIRE DEMOLITION PROCESS.

GENERAL NOTES:

- 28. THE CONTRACTOR SHALL BE RESPONSIBLE TO DESIGN, SUBMIT & | KNOWLEDGE WITH THE APPLICABLE MINIMUM BUILDING CODE.
 - RESTORATION AND DOES NOT NECESSARILY INDICATE OR DESCRIBE ALL WORK REQUIRED FOR FULL PERFORMANCE AND COMPLETION OF THE REQUIREMENTS OF THE CONTRACT DOCUMENTS. IT IS THE RESPONSIBILITY OF THE GC TO CORRELATE DEMO AND REPAIRS/NEW CONSTRUCTION.
 - DIMENSIONS ON DRAWING MAY VARY SLIGHTLY.
 - DOORS ARE IDENTICAL IN THEIR DIMENSIONS. THE G.C. SHALL BE RESPONSIBLE FOR THE WINDOW/ DOOR REPLACEMENTS TO FIT IN THEIR ORIGINAL LOCATION.
 - ALL PLAN DIMENSIONS TAKE PRECEDENCE OVER THE SCALING OF THE PLANS. THE DIMENSIONS ARE CALCULATED AND ANNOTATED BY COMPUTER AND ROUNDED TO THE NEAREST INCH. LOCATING PARTITIONS TO CENTERLINE OF MULLIONS (WHERE APPLICABLE) SHALL TAKE PRECEDENCE OVER GIVEN DIMENSIONS.
 - ALL WORK SHALL COMPLY WITH THE PROVISIONS OF THE LOCAL BUILDING CODE AND ALL APPLICABLE ORDINANCES AND PROVISIONS.
 - THE CONTRACTOR SHALL SUBMIT WITH HIS BID PROPOSAL A COMPLETE CONSTRUCTION SCHEDULE TO THE OWNER, WHICH COORDINATES ALL WORK WITH SUPPLIERS AND SUB-CONTRACTORS.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONSTRUCTION MEANS. METHODS, TECHNIQUES, SEQUENCES, PROCEDURES, OR FOR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK. FOR THE ACTS OR OMISSIONS OF THE CONTRACTOR, SUBCONTRACTOR OR ANY OTHER PERSONS PERFORMING WORK OR FAILURE OF ANY OF THEM TO CARRY OUT WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
 - EACH CONTRACTOR & SUBCONTRACTOR SHALL CARRY PUBLIC LIABILITY, PROPERTY DAMAGE AND WORKMAN'S COMPENSATION INSURANCE AND SHALL PROVIDE OWNER WITH A VALID CERTIFICATE BEFORE STARTING CONSTRUCTION.
 - ALL CONTRACTORS SHALL PROTECT THE WORK OF OTHER TRADES. ANY & ALL CONFLICTS BETWEEN TRADES ARE TO BE COORDINATED BY THOSE TRADES AND NOTIFICATION OF SUCH CONFLICTS MADE TO THE THE RESPONSIBLE PARTY AT HIS EXPENSE.
 - BE CONSTRUCTED AND SHALL REPORT ANY SUCH WORK WHICH IS NOT IN SUITABLE CONDITION TO RECEIVE WORK UNDER THIS CONTRACT THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR THE CONDITION OF THE FINISHED WORK AFTER THE WORK UNDER THIS CONTRACT IS STARTED.
 - 12. THE CONTRACTOR SHALL VISIT THE JOB SITE AND SHALL VERIFY ARCHITECT'S DIMENSIONS AND DETAILS PRIOR TO INITIAL BID SUBMITTAL. CONTRACTOR SHALL NOTIFY ARCHITECT OF ANY ERRORS, OMISSIONS. DISCREPANCIES AND/OR CONFLICTS IN CONSTRUCTION DOCUMENTS. BEFORE BID SUBMITTAL. WHICH WOULD INTERFERE ALL DISCREPANCIES NOT BROUGHT TO THE ATTENTION OF THE ARCHITECT/OWNER PRIOR TO FINAL BID SUBMITTAL SHALL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST TO OWNER. DISCREPANCIES IN DRAWINGS SHALL BE DECIDED BY THE ARCHITECT
 - 13. ALL WORK IS TO CONFORM TO CONSTRUCTION DRAWINGS AND SPECIFICATIONS. ANY CONDITIONS IN THE FIELD AFFECTING THE DESIGN CONCEPT ARE TO BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO BID SUBMITTAL.
 - 14. ALL WORK SHALL BE LIMITED TO THAT SHOWN ON THE PERMIT WRITTEN APPROVAL OF THE OWNER AND ARCHITECT. ANY ADDITIONAL WORK PERFORMED WITHOUT THIS CONSENT SHALL BE DONE AT THE CONTRACTOR'S SOLE EXPENSE. IN THE EVENT THAT CERTAIN FEATURES OF THE CONSTRUCTION ARE NOT FULLY SHOWN ON THE CHARACTER AS FOR SIMILAR CONDITIONS THAT ARE SHOWN, EXISTING AND/OR NOTED.
 - ANY WORK IS BEING DONE.
 - 16. PROVIDE AND MAINTAIN AT A CONVENIENT LOCATION WITHIN THE JOB SITE, A COMPLETE SET OF THE SIGNED AND SEALED PERMIT DOCUMENTS INCLUDING ALL THE LATEST SHOP DRAWINGS, ADDENDUMS. REVISIONS AND SUPPLEMENT SHEETS FOR REFERENCE AND COORDINATION FOR CONSTRUCTION.
 - 17. THE G.C. SHALL BE RESPONSIBLE TO ALWAYS HAVE AVAILABLE WITHIN CONSTRUCTION DOCUMENTS.
 - 18. THE CONTRACTOR SHALL AT ALL TIMES PROVIDE PROTECTION AGAINST THE WEATHER AS TO MAINTAIN THE WORK, MATERIALS, APPARATUS AND FIXTURES FREE FROM INJURY OR DAMAGE. ANY WORK DAMAGED BY FAILURE OF THE CONTRACTOR TO PROVIDE PROTECTION SHALL BE
 - 19. ALL CHANGE ORDERS SHALL BE SUBMITTED IN WRITING AND SHALL BE SIGNED BY OWNER AND ARCHITECT PRIOR TO EXECUTION.
 - 20. CONTRACTOR SHALL COORDINATE AND EXPEDITE THE PROCUREMENT OF "LONG LEAD" ITEMS TO ASSURE PROMPT DELIVERY AND INSTALLATION BY MILESTONE DATES ON THE CONSTRUCTION SCHEDULE. ADDITIONAL TIME WILL NOT BE GIVEN TO THE G.C. IF THEY HAVE NOT MET THE SCHEDULED INSTALLATION TIME FOR THESE ITEMS. THE CONTRACTOR SHALL PURCHASE, COORDINATE & INSTALL ALL APPLIANCES AND EQUIPMENT UNLESS SPECIFICALLY NOTED OTHERWISE ON THE PERMIT DRAWINGS. SPECIFICATIONS AND INSTALLATIONS METHODS PROVIDED BY MANUFACTURE SHALL BE STRICTLY FOLLOWED AND ARE HEREWITH MADE A PART OF THESE DOCUMENTS.
 - CONTRACTOR SHALL PROVIDE ALL NECESSARY ELECTRICAL OR MECHANICAL EQUIPMENT MAINTENANCE, INSTRUCTION MANUALS, AND ALL OTHER CLOSE-OUT DOCUMENTS TO THE OWNER FOR REVIEW AT FINAL COMPLETION.
 - 22. ALL WORK SHALL BE DONE IN A NEAT AND SKILLFULL MANNER AND IN ACCORDANCE WITH ALL GOVERNING BODIES, RULES, AND REGULATIONS. REMOVE RUBBISH AND DEBRIS DAILY, LEAVE JOB CLEAN UPON COMPLETION OF WORK, INCLUDING CLEANING OF HARDWARE, FIXTURES, AND GLASS, AND REMOVING OF STAINS, DUST, DIRT, AND PAINT, AND POLISHING OF ALL FINISHED FLOORS AND CABINETRY.

- THE DRAWINGS AND NOTES COMPLY, TO THE BEST OF OUR 23. ALL MATERIALS & EQUIPMENTS SHALL BE INSTALLED AS PER MANUF RECOMMENDATION AND THE BEST PRACTICES OF THE INDUSTRY.
- THE DRAWINGS DEMOLITION SHOWN ARE A GUIDE FOR THE 24. G.C. SHALL ALWAYS FOLLOW MANUFACTURER RECOMMENDATIONS FOR THE MANAGE, QUALITY, INSTALLATION AND/OR CONSTRUCTION OF ANY MATERIAL, EQUIPMENT, SYSTEM AND/OR ELEMENT CONTAIN ON THE PROJECT.
 - 25. GENERAL CONTRACTOR SHALL PROVIDE EXTENSIVE SIGNING IN WORKING AT PUBLIC AREAS TO WARN WORKERS AND GENERAL PUBLIC ABOUT UNSAFE AREAS. SIGNS SHALL COMPLY WITH OSHA REGULATIONS.
- DUE TO THIS BEING A HISTORIC BUILDING, NOT ALL WINDOWS AND 26. CONTRACTOR IS NOT ALLOW TO CUT AND PATCH STRUCTURAL ELEMENTS IN A MANNER THAT WOULD REDUCE THEIR LOAD-CARRYING CAPACITY OR LOAD-DEFLECTION RATIO.
 - 27. OBTAIN APPROVAL FROM OWNER BEFORE CUTTING AND PATCHING THE FOLLOWING OPERATING BUILDING ELEMENTS OR SAFETY RELATED SYSTEMS: PRIMARY OPERATIONAL SYSTEMS AND EQUIPMENT, AIR OR SMOKE BARRIERS, FIRE PROTECTION SYSTEMS, CONTROL SYSTEMS, COMMUNICATION SYSTEMS, AND ELECTRICAL WIRING SYSTEMS.
 - 28. THE GENERAL CONTRACTOR, SUB-CONTRACTORS AND ALL VENDORS ARE TO VERIFY ALL CLEARANCES (CORRIDORS, STAIRS, ELEVATORS, ETC.) REQUIRED FOR DELIVERIES, PASSAGE OF ALL JOB MATERIALS OR EQUIPMENT. THE OWNER'S PROJECT MANAGER SHALL BE INFORMED OF ANY POTENTIAL OR ACTUAL PROBLEMS WHICH, IN ANY WAY, MIGHT AFFECT WORK, SCHEDULING, ANY VENDORS, SUBCONTRACTORS, ETC. INCLUDING AFTER HOURS DELIVERIES IMPOSED BY OWNER.
 - 29. THE CONTRACTOR SHALL INCLUDE ALL TEMPORARY UTILITIES (IF APPLICABLE) INCLUDING ELECTRICITY, WATER AND TELEPHONE IN HIS
 - THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR RE-DOING ANY WORK THAT FAILS TO CONFORM TO THE DRAWINGS AND DETAILS AS SHOWN IN THESE CONSTRUCTION DOCUMENTS, AND CORRECT ANY DEFECTS DUE TO FAULTY MATERIALS AND WORKMANSHIP WHICH APPEAR WITHIN ONE YEAR FROM DATE OF MOVE-IN. THESE PROVISIONS APPLY, ALSO, TO WORK DONE BY DIRECT EMPLOYEES OF THE CONTRACTOR, SUB-CONTRACTORS OR VENDORS. NOTHING IN THE ABOVE INTENDS OR IMPLIES THAT THIS RESPONSABILITY SHALL APPLY TO WORK WHICH HAS BEEN ABUSED OR NEGLECTED BY THE OWNER OR HIS SUCCESSOR IN INTEREST.
- ARCHITECT AND THE OWNER. ANY DAMAGES SHALL BE REPAIRED BY 31. ALL METAL WELDING SHALL BE CONTINUOUS AND SANDED FOR SMOOTH
- THE CONTRACTOR SHALL EXAMINE ALL AREAS IN WHICH WORK IS TO 32. ALL METAL MATERIALS THAT REQUIRED SCREWS OR BOLTS SHALL USE THE METAL MATERIAL IN KIND.
 - 33. ARCHITECT HAS FINAL WORDS OF CONFLICTING INSTRUCTIONS IN DRAWINGS. IF G.C. FINDS CONFLICTING INSTRUCTIONS G.C. SHALL NOTIFY THE ARCHITECT PRIOR TO CREATING WORK, FOR ARCHITECT DECISION.
 - 34. ALL CONSTRUCTION SITE SHALL BE EXTREMELY VACUUMED AND CLEANED BEFORE FINAL DELIVERY TO OWNER. NO DUST WILL BE ACCEPTED.
- COMPLETION OF THIS WORK OR WHICH WOULD AFFECT THE BID PRICE. 35. ONCE THE WORK IS COMPLETED AND ACCEPTED, THE GENERAL CONTRACTOR SHALL SUBMIT DIGITAL AS-BUILT PLANS TO THE ARCHITECT.
 - 36. NO STRUCTURAL MEMBER SHALL BE NOTCHED, CUT, ALTERED OR MOVED IN ANY WAY WITHOUT PREVIOUS WRITTEN AUTHORIZATION FROM ARCHITECT OR STRUCTURAL ENGINEER. THERE SHALL BE NO PENETRATIONS IN PRE-STRESSED BEAMS OR JOISTS AND NO DRILLING OR SHOOTING HANGERS OR PINS IN PRE-STRESSED BEAMS OR PRE-CAST JOISTS.
- DOCUMENTS. NO ADDITIONAL WORK SHALL BE DONE WITHOUT PRIOR 37. IF G.C. ENCOUNTERS MOLD, FUNGUS, TERMITE, AND/OR ANY HAZARD MATERIAL, THEY SHALL SUBMIT A WRITTEN REPORT WITH PICTURES AND IDENTIFY IN A FLOOR PLAN THE LOCATIONS AND SEND TO THE ARCHITECT VIA EMAIL IMMEDIATELY.
- DRAWINGS, THEN THEIR CONSTRUCTION SHALL BE OF THE SAME 38. FOR ALL SPECIFIED PRODUCTS IN THIS DRAWING SET, AN EQUIVALENT PRODUCT IS ALLOWED AS LONG AS IT IS ACCEPTED BY THE PROJECT ARCHITECT THROUGH A SUBMITTAL.
- 15. GENERAL CONTRACTOR SHALL HAVE A SUPERVISOR ON SITE WHILE 39. G.C. SHALL BE RESPONSIBLE FOR ENSURING THEY RECEIVED THE ASBESTOS AND LEAD REPORTS DURING THE BIDDING PHASE. G.G. SHALL BE RESPONSIBLE FOR CONSIDERING THE PROJECT REQUIREMENTS THESE REPORTS CREATE AND INCLUDE IT IN THEIR BID PROPOSAL.
 - 40. GENERAL CONTRACTOR SHALL PROVIDE EXTENSIVE SIGNING IN WORKING AT PUBLIC AREAS TO WARN WORKERS AND GENERAL PUBLIC ABOUT UNSAFE AREAS. SIGNS SHALL COMPLY WITH OSHA REGULATIONS.
 - THE JOB SITE THE DIGITAL INFORMATION CONTAINED IN THE \(\frac{2}{41}\). PREPARATIONS FOR FACADE CLEANING SHALL DEPEND ON LEAD-CONTAINING PAINT. IF ACCORDING TO THE LEAD REPORT, THE FACADE DOES NOT CONTAIN LEAD PAINT, IT MAY BE CLEANED BY G.O. PRIOR TO PAINTING. IF ACCORDING TO THE LEAD REPORT, THE FACADE DOES CONTAIN LEAD PAINT, IT MUST BE CLEANED ACCORDING TO THE TECHNICAL SPECIFICATIONS FOR THAT PROCEEDURE.
- REMOVED AND REPLACED WITH NEW WORK AT CONTRACTORS EXPENSE. \ \ 42. THE G.C. SHALL BE RESPONSIBLE FOR PROVIDING FIRE EXTINGUISHERS TYPE ABC DURING THE CONSTRUCTION PROCESS AND HAVE THEM READILY AVAILABLE IN CASE OF FIRE.
 - 43. G.C. SHALL HAVE A CONSTRUCTION FIREMAN, WHO WILL REPORT TO THE CONSTRUCTION FOREMAN AND WILL BE PRESENT AT THE SITE WHEN WELDING AND CUTTING WORK IS BEING PERFORMED. THIS PERSON MUST VERIFY WORK BEING DONE DOES NOT CAUSE FIRES, PAYING SPECIAL ATTENTION TO WORKS THAT CAUSE SPARKS OR MOLTEN METAL, AND THAT COMBUSTIBLE MATERIALS ARE APPROPRIATELY COVERED WITH FIRE BLANKETS AND/OR OTHER APPROPRIATE FIRE PROTECTIVE MEASURES. THE CONSTRUCTION FIREMAN SHALL ALSO BE RESPONSIBLE FOR INSPECTING AND MAINTAINING FIRST AID AND FIRE PROTECTION EQUIPMENT ON SITE.
 - 44. SMOKING ON THE PROJECT SITE IS PROHIBITED. G.C. SHALL DISPLAY NO-SMOKING NOTICES AND TAKE REASONABLE MEASURES SO ENSURE THAT ALL PERSONS ARE AWARE OF THE BAN AND DO NOT SMOKE ON THE PROJECT SITE.
 - 45. G.C. SHALL INSTALL TEMPORARY FIRE DETECTION DEVICES THAT ARE DIRECTLY MONITORED AND ARE IN CLOSE PROXIMITY TO THE AREAS OF

IMPORTANT NOTE

G.C. SHALL CONSIDER THAT ON ALL NOTES, THE WORD "OWNER" REFERS TO THE OWNER'S REPRESENTATIVE

BIDDING SET

SHEET INDEX **ISSUE DATES**

TITLE SHEET

INDEX & GENERAL NOTES

EXISTING ELEVATIONS A

EXISTING ELEVATIONS B

TITLE PAGES

T-02

FX-04

EX-05

EXISTIN	NG	
EX-01	EXISTING FIRST FLOOR PLAN	
EX-02	EXISTING SECOND, THIRD AND FOURTH FLOOR PLAN	
EX-03	EXISTING ROOF PLAN	

ARCHITECTURAL

A-0	GENERAL RESTORATION NOTES	
A-00	INTENTIONALLY SKIPPED	
A-000	CONSTRUCTION BANNER DETAIL	
A-01	RESTORATION FIRST FLOOR PLAN	
A-01.1	RESTORATION PHOTOS — 1ST FLOOR	
A-01.2	RESTORATION PHOTOS — 1ST FLOOR	
A-01.3	RESTORATION PHOTOS — 1ST FLOOR	
A-02	RESTORATION SECOND, THIRD, FOURTH FLOOR PLAN	
A-02.1	RESTORATION PHOTOS — 2ND, 3RD & 4TH FLOOR	
A-02.2	RESTORATION PHOTOS — 2ND, 3RD & 4TH FLOOR	
A-03	RESTORATION ROOF PLAN	
A-03.1	RESTORATION PHOTOS — ROOF	
A-04	RESTORATION ELEVATIONS — C	
A-05	RESTORATION ELEVATIONS — B	
A-06	DOOR & WINDOW SCHEDULE	
A-07	FINISH & SUBMITTAL NOTES	
A-07.1	LEAD-BASED PAINT ABATEMENT NOTES	
} P-01	FRESHWATER SYSTEM DETAILS	

IMPORTANT NOTE:

IT IS RECOMMENDED THAT THE CONSTRUCTION DRAWING SET BE PRINTED IN COLOR -4AS SOME OF THE PAGES USE COLOR AS A WAY OF DISPLAYING IMPORTANT INFORMATION.

PAINT ENTIRE EXTERIOR SURFACE, INCL. EXISTING DOORS AND WINDOWS.

SCOPE OF WORK

2.	REFINISH WOODEN BALUSTRADES ON BALCONIES.
3.	REPAIR/REPLACE EXISTING METAL BALUSTRADES ON 2 BALCONIES.
4.	REMOVE/REPLACE EXISTING WOOD & GLASS DOORS.
5.	REMOVE/REPLACE EXISTING DAMAGED WINDOWS.
6.	REFINISH EXIST. WOOD DOOR IN KITCHEN.
7.	REPAIR EXISTING KITCHEN BACKSPLASH TILES.
8.	REPAIR RED CLAY ROOF TILES.
9.	REMOVE/REPLACE LAMP SCONCE.
10.	REPAIR/REPLACE ROOF DRAINAGE AND GUTTER SYSTEM
11.	REPAIR DECORATIVE WALL TILES ON STAIRCASE & REPAIR REINF. CONCRETE WALL.
12.	RESTORE METAL SAILBOAT WEATHERVANE.
13.	CLEAN ROOF TILES AND REMOVE EXISTING VEGETATION.
14.	REPAIR PLASTER ON 1 COLUMN.
15.	CLEAN AND REFINISH EXISTING WOOD DOOR.
16.	REPAIR/REFINISH METAL GRILLES.
17.	REPLACE METAL GRILLE.
18.	REPAIR MARBLE CHIMNEY FACADE.
19.	CLEAN & PAINT 21 WOOD BEAMS ON MAIN FAÇADE BALCONY.
20.	CLEAN ALL EXTERIOR FLOOR TILES.
21.	PAINT INTERIOR ELEMENTS
22.	PROVIDE AND INSTALL SMOKE DETECTORS
23.	WATERPROOF ROOF TILES
24.	FRESHWATER SYSTEM EQUIPMENT
25.	SECOND FLOOR BALCONY FLOOR TILE REPAIR 1

TASKS MARKED IN RED IN THIS SECTION REFER TO ALTERNATES AND ARE NOT


PART OF THE BASE SCOPE OF WORK.

THIS SCOPE OF WORK TABLE IS ONLY FOR THE PURPOSE OF GUIDING THE G.C. IN UNDERSTANDING THE SCOPE AND SHALL IN NO WAY TAKE PRECEDENCE OVER THE

DETAILED INSTRUCTIONS INCLUDED IN HE CONSTRUCTION DRAWINGS AND NOTES.

NATIONA

NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS PLANIFICADORES

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-203 FAXCIMIL (787) 722-5031

arquitectospr@arquiteg.com Yo, Victor M. Villegas Durán, Lic. #11445, certifico que so el profesional que diseñó estos planos y las entiendo que dichos planos y especificaciones cumplen co las disposiciones aplicables del Reglamento Conjunto y la: disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicciór Certifico, además, que en la preparación de estos planos v especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversić por la Industria Puertorriqueña"y con la [Ley Núm. 319 d 15 de mayo de 1938, según enmendada; Ley Núm. 96 de

6 de julio de 1978, según enmendada; según aplique].

de los hechos que se hava producido por desconocimient

Reconozco que cualquier declaración falsa o falsificación

o por negligencia va sea por mí, mis agentes o

empleados, o por otras personas con mi conocimiento, m

hacen responsable de cualquier acción judicial y

Laurie S. Rivera

disciplinaria por la OGPe. PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez

No.	Issue		Date
1 N	OTES UPDATE		06.19.23
	1		
1	Orawn by	$- \frac{R}{R}$	eviewed by


SHEET TITLE AND NUMBER:

GM | EM | CB | LR

GENERAL NOTES & DETAILS

ISSUE FOR BIDDING NOT FOR CONSTRUCTION

BY: V.M.V. DATE:JUNE 19, 2023



0

Ы Н

PLANOS

J0

ORTI

ᄓ

0

TOS

YEC

ESHPF


SHP

/RESTAURACIONES

∪ 2 −




NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS **PLANIFICADORES**


AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversiór por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me

PROFESSIONAL TEAM:

disciplinaria por la OGPe.


Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera




SHEET TITLE AND NUMBER:

EX-01

EXISTING FIRST FLOOR PLAN



Reviewed by



03

CORTIJO/PLANOS

01

M/PROYECTOS


ESHPF

SHP

/ACTIVOS/RESTAURACIONES



SHPO



STATE HISTORIC
PRESERVATION OFFICE
OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record:

Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS PLANIFICADORES


AVE. FERNADEZ JUNCOS 751
MIRAMAR SAN JUAN
OFICINA TEL.723-2031
FAXCIMIL (787) 722-5031
arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que entiendo que dichos planos y especificaciones cumplen con las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la "Ley para la Inversión por la Industria Puertorriqueña" y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me

PROFESSIONAL TEAM:

hacen responsable de cualquier acción judicial y disciplinaria por la OGPe.

> Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera



GM | EM | CB | LR

GM | EM | CB

SHEET TITLE AND NUMBER:

FX-03

EXISTING ROOF PLAN

BALUSTERS AND RAILING TO-BE REMOVED. SEE SPECS. RAILING TO BE REMOVED. SEE SPECS. **EXISTING ELEVATION** NATIONAL PARK SERVICE

SHPO

STATE HISTORIC
PRESERVATION OFFICE
OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.




arquiteg
arquitectos
ingenieros
planificadores

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que entiendo que dichos planos y especificaciones cumplen con las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la "Ley para la Inversión por la Industria Puertorriqueña" y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y disciplinaria por la OGPe.

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera



GM | EM | CB | LR

EX-04

scale: $\frac{1}{4}$ "=1'-0" (if printed on 24"x36")

SHEET TITLE AND NUMBER:

EX-04

EXISTING ELEVATION

ISSUE FOR BIDDING
NOT FOR CONSTRUCTION
BY: V.M.V. DATE:JUNE 19, 2023


NOTE:
ELEMENTS SHOWN IN RED SHALL
BE REMOVED. SEE SPECS.

M/PROYECTOS/01

ESHPF

SHPO

DATA/ACTIVOS/RESTAURACIONES



EXISTING ELEVATION

scale: \(\frac{1}{4}\) "=1'-0" (if printed on 24"x36")

B

EX-05

NOTE:
ELEMENTS SHOWN IN RED SHALL
BE REMOVED. SEE SPECS.

/PROYECTOS/

ESHPF

SHP

DATA/ACTIVOS/RESTAURACIONES

NATIONAL PARK SERVICE

SHPO OECH

STATE HISTORIC
PRESERVATION OFFICE
OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



INGENIEROS
PLANIFICADORES

AVE. FERNADEZ JUNCOS 751
MIRAMAR SAN JUAN

MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que entiendo que dichos planos y especificaciones cumplen con las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la "Ley para la Inversión por la Industria Puertorriqueña" y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y disciplinaria por la OGPe.

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

	13340	Date
		_
		_
		_
		_
	Drawn by	Reviewed by

GM | EM | CB | LR VV

SHEET TITLE AND NUMBER:

EX-05

EXISTING ELEVATION

GENERAL RESTORATION NOTES:

1. GENERAL RESTORATION NOTES APPLY TO WORK UNLESS SPECIFICALLY INDICATED OTHERWISE.

2. REMOVAL OF MATERIALS SHALL BE ACCOMPLISHED USING MEANS AND METHODS NECESSARY TO MINIMIZE DAMAGE TO ADJACENT AND/OR REMAINING MATERIALS AND FINISHES.

3. ALL TIMES THE FRASE "MATCH EXISTING" IS USED, CONTRACTOR WILL USE MATERIALS AND METHODS TO MATCH ALL VISUAL CHARACTERISTICS AND FEATURES OF THE EXISTING WORK.

4. ANCHOR BOLTS, DOWELS, INSERTS, HARDWARE, ETC...SHALL BE SECURELY TIED IN PLACE PRIOR TO POURING CONCRETE.

5. FOOTINGS WILL BE POURED AGAINST FIRM, UNDISTURBED NATURAL SOIL OR FILL COMPACTED TO A MINIMUM OF 90%.

6. ALL STRUCTURAL LUMBER TO BE DOUGLAS FIR-LARCH (ROUGH SAWN OR S4S) a. GRADE #2 OR BETTER FOR ALL 2X JOISTS/RAFTERS/LEDGERS b. GRADE #1 OR BETTER FOR ALL 4X OR LARGER BEAMS AND POSTS.

7. WOOD USED IN CONSTRUCTION OF PERMANENT STRUCTURE AND LOCATED NEARER THAN 6"TO EARTH SHALL BE TREATED WOOD OR REDWOOD.

8. ALL HARDWARE CONNECTORS (NAILS, BOLTS, ETC..) SHALL BE GALVANIZED.

9. A METAL PLATE, METAL STRAP OR WASHER NOT LESS THAN STANDARD CUT WASHER SHALL BE BETWEEN THE WOOD AND BOLT HEAD AND BETWEEN THE WOOD AND THE NUT.

10. FLOOR JOISTS WILL BE DOUBLED UNDER BEARING PARTITIONS RUNNING PARALLEL WITH THE JOISTS.

11. BEARING PARTITIONS PERPENDICULAR TO JOISTS WILL NOT BE OFFSET FROM SUPPORTING GIRDERS, WALLS OR PARTITIONS MORE THAN THE JOIST DEPTH.

PLATES INSTALLED TO PROVIDE OVERLAPPING AT CORNERS & AT INTERSECTIONS WITH OTHER PARTITIONS. END JOISTS IN DOUBLE TOP PLATES SHALL BE OFFSET AT LEAST 48".

13. HOLD DOWNS SHALL BE RE-TIGHTENED JUST PRIOR TO COVERING WALL FRAMING.

14. IN ROOF STRUCTURES G.C. MUST ENSURE ALL CONNECTIONS USE SIMPSON STRONG TIE-CONNECTORS, OR EQUIVALENT.

15. G.C. SHALL BE RESPONSIBLE FOR PROTECTING THE INTERIOR OF THE PROPERTY ALWAYS, INCLUDING WHEN THE ROOFING REPAIRS ARE BEING

16. IT IS POSSIBLE THAT DURING THE PROCESS OF REMOVING THE EXISTING DOORS AND WINDOW FRAMES MAY CAUSE VOIDS IN THE OPENINGS. SINCE THE STRUCTURE IS A HISTORICAL ONE, THESE VOIDS MUST BE RESTORED WITH THE SPECIFIED RESTORATION PROCESS LOCATED IN THE BIDDING

17. DURING THE INSTALLATION PROCESS AND AS PART OF COMPLETING IT, IT IS POSSIBLE THE NEED TO REPAIR THE WINDOW/DOOR NOTCH (MOCHETA) FOLLOWING THE SPECIFICATIONS ON THE FINISHES NOTES.

GENERAL CLEANING NOTES:

- 1. ALL ACTIVITIES PERTAINING TO THE CLEANING AND/OR RESTORATION OF THE FAÇADE SHALL BE DONE WITH THE REQUIRED PRECAUTIONS FOR INTERVENING A HISTORICAL PROPERTY, SO AS TO NOT DAMAGE OR ADVERSELY AFFECT ANY OF ITS COMPONENTS.
- 2. ABRASIVE CLEANING TREATMENTS SUCH AS, BUT NOT LIMITED TO, GRINDING AND DANDING SHALL NOT BE USED BY ANY MEANS.
- 3. IN CASE OF ACCIDENTAL DAMAGE, CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING/ REPLACING THE AFFECTED AREA/PIECE AT NO EXTRA COST TO THE OWNER. ANY NEEDED INTERVENTION SHALL BE DONE WITH THE ADEQUATE MATERIALS/TECHNIQUE SO AS TO REPLICATE ORIGINAL EXISTING CONDITION. ALL TIMES THE WORD "OWNER" IS USED IT SHALL ALSO REFER TO "OWNERS REPRESENTATIVE".
- 4. CONTRACTOR SHALL BE RESPONSIBLE FOR TESTING BOTH, CLEANING AND COATING PRODUCTS, IN A SMALL AND INCONSPICUOUS AREA PRIOR TO FULL USE AND APPLICATION. TESTING AREA SHALL NOT EXCEED 10'X10'. LOCATION AND TESTING ARA SIZE SHALL BE COORDINATED WITH THE ARCHITECT BEFORE ANY WORK IS DONE.
- 5. ARCHITECT SHALL BE NOTIFIED WHEN TESTING AREA IS FINISHED BEFORE CONTINUING FULL WORK ON FAÇADE. IN CASE FINAL TESTING RESULTS DO NOT MEET DESIRED FINISH, PRODUCTS AND TECHNIQUES TO BE USED COULD/SHALL BE RE-EVALUATED.
- 6. EXTERIOR WALLS OF THE FAÇADE SHALL BE CLEANED FROM ALL MOLD AND MILDEW STAINS USING SPORICIDIN MOLD & MILDEW STAIN REMOVER MRC-101-320, CLEAR BY SPORICIDIN PRODUCTS (WWW.SPORICIDIN.COM), OR EQUIVALENT. PRODUCT SHALL BE APPLIED USING A PROFESSIONAL GRADE FOAM SPRAYER WHICH SHALL BE THOROUGHLY CLEANED FROM ANY PREVIOUSLY USED CHEMICAL PRODUCTS AS PER MANUFACTURER'S RECOMMENDATIONS.
- 7. PRODUCT APPLICATION SHALL BE DONE IN A PROFESSIONAL AND EVEN MANNER SO AS TO ENSURE FULL SURFACE COVERING AND TO AVOID UNEVEN RESULTS. PRODUCT APPLICATION SHALL BE DONE AS PER MANUFACTURER'S RECOMMENDATIONS.
- 12. BEARING AND EXTERIOR WALL STUDS WILL BE CAPPED WITH DOUBLE TOP 8. IN CASE OF AREAS WITH STUBBORN STAINS, PRODUCT SHALL BE REAPPLIED AND MANUFACTURER'S RECOMMENDATIONS SHALL BE FOLLOWED FOR ACHIEVING DESIRED RESULTS. IN CASE SCRUBBING IN NEEDED, ONLY NATURAL OR SYNTHETIC BRISTLE BRUSHED CAN BE USED.
 - 9. HIGH PRESSURE WATER WASHES SHALL NOT BE USED AND BY NO MEANS SHALL THE RECOMMENDED CHEMICAL MIX/PROPORTION OR PRODUCT SETTING TIME BE ALTERED.
 - 10. ALL FAÇADE ELEMENTS NOT REQUIRING CLEANING SHALL BE COVERED AND PROPERLY PROTECTED SO AS TO PREVENT ANY DAMAGE FROM CLEANING/COATING AGENTS.
 - 11. AFTER FINAL CLEANING PRODUCT APLICATION IS DONE AND RECOMMENDED DRYING TIME HAS PASSES, SPORICIDING MOLD RESISTANT COATING MRC 80-5 CLEAR FLAT BY SPORICIDIN PRODUCTS (WWW.SPORICIDIN.COM), OR EQUIVALENT. SHALL BE APPLIE USING AN AIRLESS SPRAYER IN MEDIUM PRESSURE SETTING AND A 0.018 SPRAY TOP, AS PER MANUFACTURER'S RECOMMENDATIONS, TO PREVENT FUTURE MOLD GROWTH.
 - 12. ALL PRODUCTS TO BE USED FOR THE CLEANING/COATING TREATMENTS OF THE FAÇADE SHALL BE MANAGED AND APPLIED FOLLOWING THE MANUFACTURER'S GUIDELINES AND FOR CONTACTING AN AUTHORIZED TECHNICAL REPRESENTATIVE.
 - 13. CONTRACTOR SHALL BE RESPONSIBLE FOR ADEQUATE STORAGE AND DISPOSAL OF PRODUCTS AS PER MANUFACTURER'S GUIDELINES.

IMPORTANT NOTE

G.C. SHALL CONSIDER THAT ON ALL NOTES, THE WORD "OWNER" REFERS TO THE OWNER'S REPRESENTATIVE.




-1

SHPO

STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS. PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS PLANIFICADORES

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que entiendo que dichos planos y especificaciones cumplen con las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción.

Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la "Ley para la Inversión por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se hava producido por desconocimiento o por negligencia ya sea por mí, mis agentes o hacen responsable de cualquier acción judicial y

PROFESSIONAL TEAM:

disciplinaria por la OGPe.


Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

Issue

Drawn by	Reviewed by
GM EM CB LR	VV

SHEET TITLE AND NUMBER:

GENERAL RESTORATION NOTES



ESHP]

SHP




SHPO

STATE HISTORIC
PRESERVATION OFFICE
OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS PLANIFICADORES

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que entiendo que dichos planos y especificaciones cumplen con las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de las Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la "Ley para la Inversión por la Industria Puertorriqueña" y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según eplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados o prestras passonas con mi conocimiento me

hacen responsable de cualquier acción judicial y disciplinaria por la OGPe.

PROFESSIONAL TEAM:


Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

15566	Batt
\triangle	
\triangle	
\triangle	
\triangle	
Drawn by	Reviewed by
GM EM CB LR	VV

SHEET TITLE AND NUMBER:

A-000


CONSTRUCTION BANNER DETAIL



 O



NATIONAL PARK SERVICE




STATE HISTORIC
PRESERVATION OFFICE
OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



arquiteg arquitectos INGENIEROS PLANIFICADORES


AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

ro, Victor M. Villegas Durán, Lic. #11445, certifico que so el profesional que diseñó estos planos y las entiendo que dichos planos y especificaciones cumplen cor las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas glamentadoras o Corporaciones Públicas con jurisdicción Certifico, además, que en la preparación de estos planos v especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversiór por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y

PROFESSIONAL TEAM:

disciplinaria por la OGPe.

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera



SHEET TITLE AND NUMBER:

A-01

RESTORATION FIRST FLOOR PLAN

PHOTO #8801 / REFER TO FLOOR PLAN.



GENERAL CONTRACTOR SHALL REMOVE AND REPLACE EXISTING SINGLE HUNG WOOD WINDOW ON KITCHEN MKD "G" WITH NEW. | WINDOW CURTAINS SHALL BE REMOVED, CLEANED, STORED AND REINSTALLED. | SEE WINDOW DETAILS, SCHEDULE AND NOTES FOR ADDITIONAL IMPORTANT INFORMATION. SEAL ALL PERIMETER.




GENERAL CONTRACTOR SHALL REMOVE AND REPLACE EXISTING WOOD WINDOW MKD "H" WITH NEW ON SERVICE ROOM. | WINDOW CURTAINS SHALL BE REMOVED, CLEANED, STORED AND REINSTALLED. | SEE WINDOW DETAILS, SCHEDULE AND NOTES FOR ADDITIONAL IMPORTANT INFORMATION.



G.C. SHALL REFINISH ALL THE BALUSTERS | BEFORE PROCEEDING, G.C. SHALL TAKE GENERAL AND CLOSE UP IMAGES OF BALUSTERS CURRENT CONDITIONS FOR A/E REVIEW. | ENTIRE RAILING SHALL BE THOROUGHLY SCRAPPED FROM EXISTING PAINT BEFORE REPAINTING. | SEE FINISH NOTES FOR ADDITIONAL INFORMATION. | THIS REPAIR BELONGS TO ALTERNATE B.



NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.




ARQUITECTOS INGENIEROS

MIRAMAR SAN JUAN FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicciór Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversión 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimient o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y disciplinaria por la OGPe.

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera



Drawn by

GM | EM | CB | LR

SHEET TITLE AND NUMBER:


1ST FLOOR

ISSUE FOR BIDDING NOT FOR CONSTRUCTION

PHOTO #1185 / REFER TO FLOOR PLAN.




G.C. SHALL REFINISH WINDOW GRILLE. SOME PORTIONS, MARKED ON THE IMAGES ABOVE, OF THE GRILLE ARE CORRODED, IN WHICH CASE G.C. SHALL REMOVE AND MAKE NEW ALL CORRODED WINDOW GRILLE ELEMENTS. NEW WINDOW GRILLE ELEMENTS SHALL MATCH SHAPE, QUALITY, MATERIAL, FINISH, SIZE AND DIMENSIONS. WINDOW GRILLE SHALL BE WORKED ON IN PLACE, THERE IS NO NEED TO REMOVE ENTIRE GRILLE. G.C. SHALL NOT BREAK OR DETACH WALL PLASTERING. NEW ELEMENTS SHALL BE CONTINUOUSLY WELDED, NO EXCEPTIONS. SEE FINISH NOTES FOR ADDITIONAL INFORMATION.



EXISTING WINDOW GRILLE TO BE REMOVED AND REPLACED BY NEW. NEW WINDOW GRILLE, SHALL BE MADE WITH ALUMINUM AND MATCH EXISTING DESIGN. G.C. SHALL PROVIDE SHOP DRAWING FOR ARCHITECTS APPROVAL BEFORE PROCEEDING. SEE FINISH NOTES FOR ADDITIONAL INFORMATION. NEW GRILLE MUST BE ANCHORED TO THE WALL IN A WAY THAT IS IDENTICAL TO HOW THE ORIGINAL GRILLE IS ANCHORED.



NATIONAL PARK SERVICE




STATE HISTORIC
PRESERVATION OFFICE
OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que entiendo que dichos planos y especificaciones cumplen cor las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la "Ley para la Inversiór por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

No.	Issue		Date
Γ	Irasyn by	D	11

 $\frac{\text{Drawn by}}{\text{GM} \mid \text{EM} \mid \text{CB} \mid \text{LR}} \mid \frac{\text{Rev}}{\text{SM}}$


SHEET TITLE AND NUMBER:

A - 01.2
RESTORATION PHOTOS
1ST FLOOR

PHOTO #8737 / REFER TO FLOOR PLAN.

GENERAL CONTRACTOR SHALL REMOVE AND REPLACE DAMAGED LIGHTING FIXTURE SCONCE. FOR NEW MODEL SPEC REFER TO SHEET A-01 | G.C. SHALL MAKE SURE NO ELECTRICAL DAMAGE EXISTS, AND THAT WHEN THE NEW LIGHTING FIXTURE IS INSTALLED EVERYTHING WORKS PROPERLY. | IF THERE ARE ELECTRICAL ISSUES G.C. SHALL FIX ACCORDINGLY.

PHOTO #8726 / REFER TO FLOOR PLAN.



GENERAL CONTRACTOR SHALL PATCH AND REPAIR COLUMN PLASTER. REFER TO FINISH NOTES FOR ADDITIONAL INSTRUCTIONS. | LEAD-BASED PAINT FOUND ON PAINTED SURFACE ACCORDING TO LBP REPORT. G.C. SHALL BE RESPONSIBLE FOR FOLLOWING PROPER LEAD ABATEMENT PROCEDURE.

PHOTO #8569 / REFER TO FLOOR PLAN.



G.C. SHALL REMOVE ALL SHOWN DAMAGED PORTION OF KITCHEN WALL TILES AND REPLACE WITH NEW. G.C. SHALL REQUEST EXISTING TILES STORED BY OWNER AND USED THOSE TO THIS REPAIR. IN THE CASE THAT MORE TILES ARE NEEDED TO COVERED ALL THE DAMAGED AREA, NEW TILES SHALL BE BY AMERICAN OLEAN MATCHING EXISTING. | CERAMIC TILE GROUT SHALL ALSO MATCH EXISTING. | THIS REPAIR BELONGS TO ALTERNATE A.




PHOTO #8740 / REFER TO FLOOR PLAN.



G.C. SHALL REFINISH WINDOW GRILLE ELEMENTS. WINDOW GRILLE REFINISHING SHALL BE WORKED ON IN PLACE, THERE IS NO NEED TO REMOVE. G.C. SHALL NOT BREAK OR DETACH WALL PLASTERING. SEE FINISH NOTES FOR ADDITIONAL INFORMATION. | THIS REPAIR BELONGS TO ALTERNATE B.


PHOTO #8796 / REFER TO FLOOR PLAN.



GENERAL CONTRACTOR SHALL THOROUGHLY DEEP CLEAN EXTERIOR WOOD BEAMS WITH PRESSURED WATER IN ORDER TO PROPERLY REMOVE ALL THE DIRT AND MOLD. SPECIAL CARE SHALL BE TAKEN WHEN USING PRESSURED WATER SO AS TO NOT DAMAGE THE BEAMS.



NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS. PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



PLANIFICADORES AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN

FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com


el profesional que diseñó estos planos y las entiendo que dichos planos y especificaciones cumplen o y especificaciones se ha cumplido cabalmente con lo por la Industria Puertorriqueña"y con la [Ley Núm. 319 o 15 de mayo de 1938, según enmendada; Ley Núm. 96 o 6 de julio de 1978, según enmendada; según aplique]

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

Drawn by GM | EM | CB | LR

1ST FLOOR



0

 Ω

SHP

SH


IONE

DATA

ARQ



NATIONAL PARK SERVICE



STATE HISTORIC

PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Architect of Record:

Victor M Villegas, A.I.A

arquiteg

ARQUITECTOS INGENIEROS

PLANIFICADORES

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN

OFICINA TEL.723-2031

FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

disciplinaria por la OGPe.

PROFESSIONAL TEAM:

Víctor M. Villegas

Cristina Ballester Gilberto Mendoza Elvin E. Melendez

Laurie S. Rivera

Drawn by Reviewed by GM | EM | CB | LR

SHEET TITLE AND NUMBER:

RESTORATION SECOND FLOOR PLAN & TOWER

NOT FOR CONSTRUCTION

PHOTO #1169 / REFER TO FLOOR PLAN.



GENERAL CONTRACTOR SHALL REMOVE AND REPLACE EXISTING WOOD WINDOW ON KITCHEN MKD "L" WITH NEW. | WINDOW CURTAINS SHALL BE REMOVED, CLEANED, STORED AND REINSTALLED. | SEE WINDOW DETAILS, SCHEDULE AND NOTES FOR ADDITIONAL IMPORTANT INFORMATION.

G.C. SHALL REMOVE AND REPLACE EXISTING DOOR AND FRAME ON WOOD DOOR MKD "33" FOR NEW. | EXISTING DOOR HARDWARE, SHALL BE REMOVED, REFINISHED AND REINSTALLED ON NEW DOOR. | REFER TO DOOR NOTES AND DETAILS FOR ADDITIONAL INFORMATION.

PHOTO #8647 / REFER TO FLOOR PLAN



G.C. SHALL REFINISH BALUSTRADE. | BEFORE PROCEEDING, G.C. SHALL TAKE GENERAL AND CLOSE UP IMAGES OF BALUSTRADE'S CURRENT CONDITIONS FOR A/E REVIEW. | ENTIRE RAILING AND BALUSTERS SHALL BE THOROUGHLY SCRAPPED FROM EXISTING PAINT BEFORE REPAINTING, SEE SPECS. | FOR WOOD REPAIR INSTRUCTIONS SEE SPECS. | THIS REPAIR BELONGS TO ALTERNATE B.


PHOTO #8609 / REFER TO FLOOR PLAN.

PHOTO #8599 / REFER TO FLOOR PLAN.



G.C. SHALL REMOVE ENTIRE CORRODED TOP RAIL AND REPLACE WITH NEW MATCHING EXISTING SHAPE, QUALITY, MATERIAL, FINISH, SIZE AND DIMENSION. | G.C. SHALL MAKE SURE METAL BALUSTERS ARE IN GOOD CONDITIONS, IF ANY BALUSTER IS DAMAGED AND/OR CORRODED, IT SHALL BE REPLACED BY NEW MATCHING EXISTING DESIGN. | SEE FINISH NOTES FOR ADDITIONAL INFORMATION.





STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS

MIRAMAR SAN JUAN FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que so el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Realamentadoras o Corporaciones Públicas con iurisdicció Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

No.	Issue	Date

GM | EM | CB | LR

SHEET TITLE AND NUMBER:

RESTORATION PHOTOS 2ND, 3RD & 4TH FLOOR

PHOTO #8681 / REFER TO FLOOR PLAN.

G.C. SHALL REMOVE AND REPLACE EXISTING DOOR AND FRAME ON WOOD DOOR MKD "39" FOR NEW. | EXISTING DOOR HARDWARE, SHALL BE REMOVED, REFINISHED AND REINSTALLED ON NEW DOOR. | REFER TO DOOR NOTES AND DETAILS FOR ADDITIONAL INFORMATION.

PHOTO #8684 / REFER TO FLOOR PLAN.

PHOTO #1138 / REFER TO FLOOR PLAN.



G.C. SHALL REMOVE AND REPLACE EXISTING DOOR AND FRAME ON WOOD DOOR MKD "38" FOR NEW. | EXISTING DOOR HARDWARE, SHALL BE REMOVED, REFINISHED AND REINSTALLED ON NEW DOOR. | REFER TO DOOR NOTES AND DETAILS FOR ADDITIONAL INFORMATION.


PHOTO #8706 / REFER TO FLOOR PLAN



G.C. SHALL REMOVE AND REPLACE EXISTING METAL RAILING & BALUSTERS FOR NEW. | NEW RAILING & BALUSTERS DESIGN SHALL BE EQUAL IN MATERIAL, QUALITY, SHAPE, SIZE AND DIMENSION TO THE VERTICAL ELEMENTS LOCATED AT THE MAIN STAIR RAILING. | G.C. SHALL PROVIDE SHOP DRAWING BEFORE MANUFACTURING. | LEAD-BASED PAINT FOUND ON METAL RAILING ACCORDING TO LBP REPORT. G.C. SHALL BE RESPONSIBLE FOR FOLLOWING PROPER LEAD ABATEMENT PROCEEDURE.

DAMAGED PORTION OF DECORATIVE TILES SHALL BE CAREFULLY REMOVED (TILE BY TILE), WITHOUT DAMAGING THEM. DAMAGED WALL AREAS TO BE REPAIRED ARE MARKED ON SHEET A-02, THESE ARE LIMITED TO THE PORTION OF THE WALL THAT IS NOT FLAT. | G.C. SHALL EXPLORE WALL DAMAGE, FIX ACCORDINGLY AND REINSTALL CERAMIC TILES. | NEW GROUT SHALL MATCH EXISTING GROUT. | THIS REPAIR BELONGS TO ALTERNATE A.| SEE SPECS. | LEAD-BASED PAINT FOUND ON CERAMIC WALL TILES & PAINTED SURFACE ACCORDING TO LBP REPORT. G.C. SHALL BE RESPONSIBLE FOR FOLLOWING PROPER LEAD ABATEMENT PROCEEDURE.





STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS

MIRAMAR SAN JUAN FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

ro, Victor M. Villegas Durán, Lic. #11445, certifico que sc el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Realamentadoras o Corporaciones Públicas con iurisdicció Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique conozco que cualquier declaración falsa o falsificaci o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me responsable de cualquier acción judicial y

PROFESSIONAL TEAM:


Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

No.	Issue	Date
D	rown by	ID 11

GM | EM | CB | LR


SHEET TITLE AND NUMBER: **RESTORATION PHOTOS**

2ND, 3RD & 4TH FLOOR



0

NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS PLANIFICADORES

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que so el profesional que diseñó estos planos y las entiendo que dichos planos y especificaciones cumplen con las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversión por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y disciplinaria por la OGPe.

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

\triangle	
\triangle	
\triangle	
\triangle	
\triangle	
Drawn by	Reviewed by
$CM \mid EM \mid CD \mid ID$	X 7X 7

SHEET TITLE AND NUMBER:

PHOTO #1132 / REFER TO FLOOR PLAN.



G.C. SHALL INSTALL NEW COPPER GUTTER AND DOWNSPOUTS AND CONNECT THEM TO THE EXISTING SYSTEM THAT LEADS TO THE EXIST. CISTERN. | REFER TO ELEVATIONS AND ROOF IN ORDER TO PROPERLY LOCATE GUTTERS AND DOWNSPOUTS. | FINAL LOCATION OF GUTTERS AND DOWNSPOUTS SHALL BE DISCUSSED WITH OWNER AND ARCHITECT BEFORE PROCEEDING. | WHEN INSTALLATION OCCURS, G.C. NEEDS TO BE CAREFUL IN PROTECTING ROOF TILES. IF SOME MAY BREAK, G.C. SHALL SUBSTITUTE ACCORDINGLY. | SEE ALSO SHEETS A-04 & A-05.

PHOTO #1229 / REFER TO FLOOR PLAN.

G.C. SHALL INSTALL EXISTING WEATHERVANE. WEATHERVANE SHALL BE RESTORED PRIOR TO INSTALLATION. TO BE DISCUSSED WITH ARCHITECT BEFORE PROCEEDING.


PHOTO #1176 / REFER TO FLOOR PLAN.



G.C. SHALL THOROUGHLY CLEAN AND REMOVE ALL THE EXISTING ROOF VEGETATION. | CLEANING ROOF IS PART OF ALTERNATE B. | G.C. SHALL THOROUGHLY WASH ROOF TILES BY HAND VERY CAREFULLY TO NOT DAMAGE ANY MORE ROOF TILES. | G.C. SHALL APPLY ROOF TILE ADHESIVE RT600, TERRACOTTA COLOR BY OSI, OR EQUIVALENT, IN ORDER TO REPAIR ALL BROKEN DAMAGED ROOF TILES, THAT STILL HAVE AVAILABLE FITTING PIECES. | IF SOME ROOF TILES ARE BROKEN AND DO NOT HAVE ANY AVAILABLE PIECES, G.C. SHALL RECREATE BROKEN PORTION. | SEE FINISH NOTES.




NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



arquiteg **ARQUITECTOS INGENIEROS PLANIFICADORES**

MIRAMAR SAN JUAN FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversión por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y disciplinaria por la OGPe.

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

No.	Issue	Date
\triangle		
	Drawn by	Reviewed by

GM | EM | CB | LR

SHEET TITLE AND NUMBER: RESTORATION PHOTOS

ALTERNATE A

G.C. SHALL CONSIDER AS PART OF ALTERNATE A OF INTERIOR REPAIRS THE REPLACEMENT OF MISSING KITCHEN BACKSPLASH TILE. THIS ALTERNATE ALSO INCLUDES THE REPAIR OF THE MAIN STAIRCASE WALL AND THE CAREFUL REMOVAL AND REINSTALLATION OF THE WALL TILE. G.C. SHALL REPAIR THE PORTION OF THE WALL THAT HAS BEEN AFFECTED BY WATER FILTRATIONS, NOTICEABLY SHOWING A BUMP WHEREAS THE WALL THAT IS UNAFFECTED REMAINS VERTICAL. G.C. SHALL CONSIDER ALSO AS PART OF THIS ALTERNATE THE REPAIR OF THE FIREPLACE FACADE. SEE SPECS.

G.C. SHALL REFINISH WINDOW GRILLES CORRESPONDING TO WINDOWS "A", "I" AS MARKED ON SHEET A-01. SEE SPECS. G.C. IS ALSO RESPONSIBLE FOR REFINISHING THE WOODEN BALUSTRADES ON THE SECOND FLOOR BALCONY AND ON DINNING ROOM. G.C. SHALL BE RESPONSIBLE FOR CLEANING AND REMOVING VEGETATION ON THE ENTIRE ROOF AND ROOF TILES.


IMPORTANT NOTE:

G.C. SHALL CONSIDER PAINTING ALL EXTERIOR EXISTING WINDOWS AND DOORS. ALL WINDOWS AND DOORS THAT ARE TO BE NEW OR REFINISHED SHALL ALSO BE PAINTED.

NOTE:


SHALL CONSIDER ALL COMPONENTS FOR PROPER 6" COPPER GUTTER WITH 3 X 4 DOWNSPOUTS INSTALLATIONS SUCH AS: MITERS AT CORNERS, ELBOWS, DOWNSPOUT, GUTTER HIDDEN HANGERS, ENDCAPS, GUTTER OUTLETS, SLIP JOINT CONNECTOR, FASTENERS AND FUNNEL. SUBMIT SHOP DRAWINGS FOR ARCHITECT'S APPROVAL.

ELEMENTS SHOWN IN BLUE SHALL BE NEW. SEE SPECS.






NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



INGENIEROS **PLANIFICADORES**


AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversión por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y

PROFESSIONAL TEAM:

disciplinaria por la OGPe.

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera



GM | EM | CB | LR


SHEET TITLE AND NUMBER:

RESTORATION ELEVATION

ISSUE FOR BIDDING NOT FOR CONSTRUCTION V.M.V. DATE:JUNE 19, 2023

RESTORATION ELEVATION C

scale: $\frac{1}{4}$ "=1'-0" (if printed on 24"x36")



TORAT

 Ω

R 된

0

0


ROYECTOS

ESHPF

SHP

DATA/ACTIVOS/RESTAURACIONE

NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



INGENIEROS **PLANIFICADORES**

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com


Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la 'Ley para la Inversión por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o empleados, o por otras personas con mi conocimiento, me

PROFESSIONAL TEAM:

hacen responsable de cualquier acción judicial y

disciplinaria por la OGPe.

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera





GM | EM | CB | LR

SHEET TITLE AND NUMBER:

VV

RESTORATION ELEVATION






(if printed on 24"x36") A-06

scale: N.T.S

(if printed on 24"x36") \setminus A-06

(if printed on 24"x36") **A-06**



DOOR SCHEDULE

-													
		DOOR					FRAME						
			SIZE		MATERIAL	CL ACC	MATERIAL		DETAIL MKD		HARDWARE SET No.	REMARKS	
	MKD	WIDE	HEIGHT	THICK	MATERIAL	GLASS	MATERIAL	JAMB	JAMB HEAD SILL		SLINU.		
	1	EX	ISTING DOC)R	WOOD OR WOOD/GLASS		WOOD				EXISTING	THOROUGHLY CLEAN ALL EXTERIOR DOOR & HARDWARE.	
	THRU↓		\downarrow		\downarrow	\downarrow \downarrow \downarrow			\downarrow	\downarrow			
	32	EXISTING DOOR			WOOD		WOOD				EXISTING		
* MEM	33	4'-0"	7'-0"	1-3/4"	WOOD / GLASS	1/4" CLEAR	WOOD				MATCH EXISTING	NEW WOOD DOOR TO MATCH EXISTING DESIGN. CLEAN & REUSE HARDWARE.	
	34)	EXISTING DOOR			WOOD		WOOD				EXISTING		
	35)	EXISTING DOOR			WOOD		WOOD				EXISTING		
	36)	EXISTING DOOR			WOOD		WOOD				EXISTING		
	37)	EXISTING DOOR)R	WOOD		WOOD				EXISTING		
	38)	EX	ISTING DOC)R	WOOD / GLASS	EXISTING	WOOD				EXISTING		
*NEW	39	4'-0"	7'-0"	1-3/4"	WOOD / GLASS	1/4" CLEAR	WOOD				MATCH EXISTING	NEW WOOD DOOR TO MATCH EXISTING DESIGN. CLEAN & REUSE HARDWARE.	

* DIMENSIONS TO BE RECTIFIED BY GENERAL CONTRACTOR BEFORE BIDDING

	WIN	NDOW SCHEDULE											
Ī				1	WINDOW			FRAME					
	WIN. No.		SIZE	I	MATERIAL	TVDE	GLASS	MATERIAL	TYPE	HARDWARE SET No.	NOTE		
		WIDE	HEIGHT	THICK	IVIATERIAL	ITPE	GLASS	IVIATERIAL	ITPE	021110.			
	$\langle A \rangle$	EXISTING WINDOW		WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.			
	$\langle B \rangle$	EXISTING WINDOW		WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.			
	(C)	EX	ISTING WIND	OW	WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.		
	D	EX	ISTING WIND	OW	WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.		
	E	EX	ISTING WIND	OW	WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.		
	F	EX	ISTING WIND	OW	WOOD		EXISTING	WOOD	WOOD		THOROUGHLY CLEAN WINDOW & HARDWARE.		
NEW	G	6'-0"	4'-10"	1-3/4"	WOOD	SH	1/4" CLEAR	WOOD		AS PER MANUFACT.	MATCH EXISTING DESIGN. MAHOGANY PREMIUM GRADE.		
	$\langle H \rangle$	EX	ISTING WIND	OW	WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.		
		EX	ISTING WIND	OW	WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.		
*NEW	J	3'-5"	5'-6"	1-3/4"	WOOD	СМТ	1/4" CLEAR	WOOD		AS PER MANUFACT.	MATCH EXISTING DESIGN. MAHOGANY PREMIUM GRADE.		
	⟨ĸ⟩	EX	ISTING WIND	OW	WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.		
NEW	(L)	3'-3"	5'-0"	1-3/4"	WOOD	SH	1/4" CLEAR	WOOD		AS PER MANUFACT.	MATCH EXISTING DESIGN. MAHOGANY PREMIUM GRADE.		
	$\langle M \rangle$	EXISTING WINDOW		WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.			
	N	EXISTING WINDOW		WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.			
	(o)	EXISTING WINDOW		WOOD		EXISTING	WOOD			THOROUGHLY CLEAN WINDOW & HARDWARE.			

DOOR AND WINDOW NOTES

SINGLE HUNG WDO. DETAIL

(if printed on 24"x36") \A-06

- 1. ALL PROPOSED DOORS & WINDOWS SHALL BE ADAPTED TO EXISTING WALL OPENINGS.
- 2. BEFORE WOODWORKING, MANUFACTURING CONTRACTOR SHALL SUBMIT THREE (3) WOOD FINISHED SAMPLES FOR THE A/E OFFICE'S
- 3. WOODWORKING CONTRACTOR MUST BE A MEMBER OF AWI AND SHALL PREPARE DETAILED SHOPDRAWINGS OF ALL DIFFERENT CONDITIONS ON DOORS & WINDOWS FOR THE ARCHITECT'S APPROVAL BEFORE MANUFACTURING. THIS REQUIREMENT SHALL BE STRICTLY ENFORCED.
- 4. CONTRACTOR SHALL SUBMIT MOCK-UPS OF ALL WOODWORK TO BE PERFORMED FOR TYPICAL DOORS, WINDOWS, AND FRAMES FOR ARCHITECT'S APPROVAL BEFORE MANUFACTURING.
- 5. ALL CARPENTRY FRAME CORNER JOINTS IN WINDOWS AND DOORS SHALL MITERED AT ANGLES OF 45 DEGREES. 6. ALL EXTERIOR WINDOWS SHALL BE PROVIDED WITH PEMKO SILICON SEALS MOD. S88W, OR EQUIVALENT, INSTALLED AT JAMS AND
- 7. WOOD WINDOWS AND WOOD FRAMES SHALL BE FINISHED WITH GLIDDEN MAHOGANY STAIN, OR EQUIVALENT, AND 2 COATS OF SATIN CLEAR
- SAMPLE PREPARATION. 8. ALL LAMINATED GLASS TO BE USED SHALL HAVE COLOR NEUTRAL DOUBLE SIDED ANTI-REFLECTIVE COATING WITH A <1.0% REFLECTANCE.

SEALER UNLESS OTHERWISE INDICATED. COLOR OF AVAILABLE TINTS SHALL BE SUBMITTED TO THE A/E OFFICE FOR APPROVAL BEFORE

- 9. EXISTING WINDOW AND DOORS HARDWARE ACCESSORIES SHALL BE REMOVED, CLEANED AND, IF NEEDED, REPAIRED FOR REUSE.
- CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AND STORING THESE UNTIL NEEDED.
- 10. CONTRACTOR SHALL SUBMIT SAMPLES AND LITERATURE OF NEW HARDWARE FOR THE A/E APPROVAL BEFORE ORDERING.
- 11. ALL NEW WOOD DOORS AND WINDOWS SHALL BE MAHOGANY PREMIUM GRADE.
- 12. G.C. SHALL TAKE GENERAL AND DETAILED PHOTOGRAPHS OF ALL THE WINDOWS AND DOORS THAT ARE INSTRUCTED TO BE REMOVED FOR NEW. ITS IMPORTANT TO TAKE DETAILED PHOTOS OF THE DOOR AND WINDOW HARDWARE (HINGES, DOOR MECHANISM, DOOR LEVER, LOCK, ETC). BEFORE REMOVING FROM EXISTING LOCATION.
- 13. NEW WOOD DOORS AND WINDOWS FRAMES SHALL BE FINISHED WITH PAINT AS PER SPEC. G.C SHALL SUBMIT TO A/E OFFICE FOR APPROVAL BEFORE SAMPLE PREPARATION.
- 14. ALL EXISTING DOORS AND WINDOWS SHALL BE REFINISHED; ON THE EXTERIOR SIDE DOORS SHALL BE RE-PAINTED AS PER SPECIFIED PAINT IF
- LEAD PAINT IS NOT PRESENT AS PER ZYMMETRY LEAD LABORATORY REPORT. G.C. SHALL PROVIDE THREE (3) DIFFERENT COLOR SAMPLES ON DOORS 1' X 3' FOR ARCHITECTS EVALUATION.
- 15. WINDOWS SASH SYSTEM FOR WINDOWS THAT ARE INSTRUCTED TO BE NEW, SHALL BE REPLACED FOR NEW AS PER SPEC.
- 16. SH MEANS SINGLE HUNG WINDOW TYPE; CMT MEANS CASEMENT WINDOW TYPE AND JL MEANS JALOUSIE WINDOWS TYPE. 17. ALL EXTERIOR EXISTING WOOD WINDOWS AND DOORS SURFACE SHALL BE COMPLETELY PREPARE FOLLOWING THE SPEC BEFORE FINAL
- 18. GENERAL CONTRACTOR SHALL THOROUGHLY CLEAN ALL EXISTING EXTERIOR WINDOW, DOOR AND HARDWARE 19. GENERAL CONTRACTOR SHALL MATCH EXISTING MOLDING ON NEW WINDOWS AND DOORS.

SHEET TITLE AND NUMBER:


Reviewed by


DOORS & WINDOWS SCHEDULE

Drawn by

GM | EM

ISSUE FOR BIDDING NOT FOR CONSTRUCTION V.M.V. DATE: JUNE 19, 2023





STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



PLANIFICADORES AVE. FERNADEZ JUNCOS 751

MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las entiendo que dichos planos y especificaciones cumplen con las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos v especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004,

según enmendada, conocida como la 'Ley para la Inversión por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o hacen responsable de cualquier acción judicial y disciplinaria por la OGPe.

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

FINISH NOTES:

. EXISTING WOOD RESTORATION

IT IS THE INTENT THAT THE G.C. FOLLOW THE PROCEDURE BELOW FOR ALL WOODEN ELEMENTS INDICATED TO BE RESTORED ON THE CONSTRUCTION DRAWINGS WITH LIQUID WOOD BY ABATRON, OR EQUIVALENT. THE G.C. SHALL USE THESE NOTES AS A GENERAL INSTRUCTION, HOWEVER, MANUFACTURER INSTRUCTIONS ALWAYS GOVERN. MANUFACTURER INSTRUCTIONS CAN BE ACCESSED THROUGH THIS LINK: https://www.loghelp.com/images/LiquidWood-WoodEpox-Instructions.pdf

DUE TO CONTRACTORS BEING RESPONSIBLE TO CAREFULLY INSPECT THE PROPERTY AND VALIDATE THE DAMAGES SHOWN ON DWGS PRIOR TO PROVIDING THEIR BID, HE SHALL BE RESPONSIBLE TO REPAIR ALL OTHER DAMAGED WOOD PLANKS THAN THOSE MARKED IN THE CONSTRUCTION DRAWINGS, G.C IS RESPONSIBLE FOR RESTORING THOSE AS WELL AT THEIR COST. THIS IS ONLY APPLICABLE IN THE SAME GENERAL AREA OF THE RESTORATION WORK BEING DONE. GC SHALL BE RESPONSIBLE TO ASK IN WRITING IF QUESTION ARISE DURING INSPECTION AND BIDDING.

G.C. MUST PROVIDE A MINIMUM OF THREE (3) ONE SQUARE FEET IDENTICAL SAMPLES OF FINISHED RESTORED WOOD ELEMENT PRIOR TO PROGRESSING WITH THE ENTIRE WORK. A/E WILL RETAIN ONE OF THESE SAMPLES.

WOOD RESTORATION MATERIALS SHALL BE USED AS PER MFR RECOMMENDATIONS.

- A. PREPARATION INSTRUCTIONS:
- a. SURFACE ADHESION MAY BE IMPAIRED BY IMPROPERLY PREPARED SURFACES, WHICH MUST BE CLEANED AND DRY. OILS, GREASE, WAX, FAT, SOAP, PAINT, LUBRICANTS, LOOSE MATTER, AND MOST KINDS OF SOIL PREVENT ADHESION AND PENETRATION.
- DRY AFFECTED WOOD MEMBER COMPLETELY. IF COMPLETE DRYING IS NOT POSSIBLE IN PLACE, THE MEMBER MUST BE REMOVED AND KEPT IN A COOL DRY PLACE UNTIL DRY. IF THIS PRECAUTION IS NOT TAKEN, THE EPOXY CAN ACTUALLY TRAP MOISTURE IN WOOD FIBERS AND ACCELERATE THE DECAY PROCESS.
- OLD PAINT SHOULD BE REMOVED. IT CAN BE SCRAPED, SANDED OR STRIPPED. STRIPPER RESIDUE SHOULD BE REMOVED. OIL, GREASE AND OTHER CONTAMINANTS CAN BE REMOVED WITH DETERGENTS, SOLVENTS OR OTHER AGENTS. MOISTURE AND WATER DIMINISH PENETRATION AND ADHESION. MOISTURE CONTENT SHOULD BE BELOW 17%. WOOD CAN BE DRIED WITH HEAT OR VENTILATION. ANOTHER METHOD TO ACCCELERATE DRYING IS BRUSHING ACETONE (CAUTION: FLAMMABLE) ON THE WET SURFACE. THIS SOLVENT BLENDS WITH WATER AND ACCELERATES ITS EVAPORATION.
- ORGANIZATION AND CLEANLINESS ARE KEYS TO PROPER EPOXY REPAIR. HAVE ALL MATERIALS AT HAND BEFORE THE MIXING PROCESS BEGINS. LABEL ALL CAPS AND LIDS SO THAT A CAP OR LID IS NOT PLACED ON THE WRONG CONTAINER OR IT WILL BE STUCK THERE FOREVER. PUTTING ALL MATERIALS ASSOCIATED WITH THE OTHER ON THE RIGHT HELPS KEEP THINGS SEPARATED. PROTECT ALL ADJACENT SURFACES FROM SPILLS WITH PLASTIC SHEETING. IF ANY EPOXY HAPPENS TO SPILL, WIPE IT UP IMMEDIATELY BEFORE IT SETS OR IT WILL NOT COME UP.
- B. EXECUTION:
- a. REMOVE ANY ROTTEN/ LOOSE WOOD MATERIAL IN THE AREA TO BE RESTORED.
- b. DRILL 1/4" OR 3/16" HOLES IN AFFECTED WOOD TO RECEIVE EPOXY CONSOLIDANT WILL LEAK OUT FROM BEHIND. WHEN ON A VERTICAL SURFACE, ANGLE THE HOLES SO EPOXY WILL NOT LEAK BACK OUT.
- c. FOLLOWING MANUFACTURER'S INSTRUCTIONS, MIX A SMALL AMOUNT OF THE CONSOLIDANT COMPONENTS IN EQUAL PARTS, THE RESIN AND THE HARDENER, TOGETHER. AVOID SHALLOW OR TOO LARGE COTAINERS. USE A SEPARATE MEASURING TOOL TO SCOOP FROM THE RESIN AND THE

HARDNER TO AVOID CONTAMINATION. STIR THE MIXTURE THOROUGHLY BY HAND, ALWAYS WEARING GLOVES, OR WITH A THIN STICK.

- d. CAREFULLY POUR THE CONSOLIDANT INTO THE PRE-DRILLED HOLES. THE AIM IS TO COMPLETELY SATURATE THE WOOD. MOVE FROM HOLE TO HOLE REFILLING UNTIL THE WOOD CAN HOLD NO MORE. MORE THAN ONE APPLICATION MAY BE NEEDED.
- AFTER THE CONSOLIDANT HAS CURED, THE VOIDS IN THE SURFACE CAN BE FILLED WITH EPOXY FILLER. IF THE VOIDS ARE LARGE, FILLER CAN BE
- APPLIED IN SUCCESSION, 1" OF DEPTH AT A TIME. THIS CUTS DOWN ON THE POSSIBILITY OF PROBLEMS ASSOCIATED WITH HEAT BUILD-UP. MIXING OF THE TWO-PART EPOXY FILLER IS SIMILAR TO THE CONSOLIDANT. WHEN MIXED, THE FILLER HAS THE CONSISTENCY OF A GLAZING COMPOUND AND CAN BE WORKED WITH A PUTTY KNIFE. THE SURFACE OF THE FILLER SHOULD BE BUILT UP SLIGHTLY ABOVE OF THE WOOD
- g. WAIT AT LEAST 24 HOURS AFTER HARDENING AND SAND LIGHTLY BEFORE PAINTING OR STAINING.

SURFACE TO ALLOW FOR PLANING AND SANDING SMOOTH AFTER IT HAS CURED.

- G.C. SHALL ENSURE THAT SURFACE IS PAINTED AND/OR STAINED TO ACHIEVE A COLOR MATCH WITH THE EXISTING FLOOR. THE FINISHED PRODUCT MUST MATCH THE EXISTING, INCLUDING EMULATING THE EXISTING JOINTS IN ORDER FOR THE WORK TO PASS INCONSPICUOUSLY.
- APPLY COPPER GREEN WOOD PRESERVATIVE (https://www.homedepot.com/p/Copper-Green-1-gal-Wood-Preservative-Copper1/100203025),OR EQUIVALENT, TO ALL EXISTING REPAIR & NON REPAIRED WOOD ELEMENTS AFTER THE REPAIRS HAS BEEN FINISHED. APPLY USING A MIST
- C. WOOD REPAIR MATERIALS:

USE LIQUIDWOOD, OR EQUIVALENT, FOR FILLING VOIDS IN DAMAGED WOODS, LIQUIDWOOD CONSISTS OF 2 CLEAR LIQUIDS: THE RESIN (A), AND THE HARDENER (B). WHEN A AND B ARE MIXED BY SIMPLE STIRRING, A BLEND IS FORMED WITH UNUSUAL PROPERTIES TO IMPREGNATE AND RESTORE WOOD AND OTHER POROUS MASSES. LIQUIDWOOD IS BRUSHED OR POURED ON THE SURFACE WHERE IT MUST BE ABSORBED. THE MORE POROUS THE WOOD, THE MORE RESIN IT WILL ABSORB, AND THE GREATER THE IMPROVEMENT, LIQUIDWOOD IMPREGNATES THE WOOD FIBERS AND HARDENS INTO A WATER-AND INSECT-RESISTANT, DISTORTION-FREE, HIGH-STRENGTH MASS IN HOURS OR MINUTES. THE HARDENED MASS CAN BE SAWED, PLANED, ROUTED, CARVED, DRILLED, SANDED, GLUED AND PAINTED.

USE WOOD EXPOX BY ABATRON, OR EQUIVALENT, FOR STRUCTURAL RECONSTRUCTION OF WOOD. USE WOOD EPOX IS A LIGHT-WEIGHT STRUCTURAL ADHESIVE PUTTY SYSTEM AND WOOD SUBSTITUTE CONSISTING OF 2 COMPONENTS: RESIN PASTE (A) AND HARDENER PASTE (B). WHEN A AND B ARE MIXED, THE BLEND HARDENS WITHIN 1-2 HOURS INTO A LIGHTER-THAN-WATER NON-SHRINKING, TOUGH ADHESIVE MASS WITH HIGH DIMENSIONAL STABILITY, CHEMICAL, WATER, HEAT AND WEATHER RESISTANCE. ITS APPEARANCE IS A LIGHT NEUTRAL COLOR THAT CAN BE CHANGED, WHILE MIXING, WITH STAINS, DYES OR PIGMENTS. IT HAS A NO-SLUMP PASTE CONSISTENCY THAT ALLOWS IT TO BE APPLIED LIKE PUTTY TO FILL GAPS, HOLES, OR TO BUILD UP VIRTUALLY ANY THICKNESS AND SHAPE. BOTH PRODUCTS ARE PRODUCED BY ABATRON, INC. PLEASE SELECT THE FOLLOWING LINK FOR THE WOOD REPAIR MATERIALS:

https://www.abatron.com/product/wood-restoration-kit/.

. REPAIRED CERAMIC WALL TILE

REPAIRED OR REPLACED CERAMIC WALL TILES AT KITCHEN SHALL MATCH EXISTING.

DECORATIVE WALL TILES THAT HAVE BEEN REMOVED ACCORDING TO IMAGE 1138 ON SHEET A-02.2 OF THE CONSTRUCTION DRAWINGS SHALL BE CAREFULLY REINSTALLED "IN KIND". SPECIAL ATTENTION MUST BE HAD, AS THE PATTERN DURING REINSTALLMENT SHALL BE THE SAME AS WAS EXISTING. IN CASE ANY TILES ARE DAMAGED DURING THE WORK, THE G.C. SHALL BE RESPONSIBLE FOR THEIR REPLACEMENT WHICH SHALL MATCH THE EXACT CHARACTERISTICS OF THE ORIGINAL TILE.

G.C. SHALL ENSURE SURFACE IS PREPARED PRIOR TO INSTALLING THE TILE. NO TILE SHALL BE INSTALLED IF SURFACE HAS WATER FILTRATIONS.

3. PAINT- EXISTING EXTERIOR WALL

COMPLETE EXTERIOR WALL SURFACES SHALL BE PAINTED. PAINT COLOR SHALL BE SELECTED BY THE ARCHITECT.

SURFACE PREPARATION SHALL BE MADE ACCORDING TO TECHNICAL SPECS. G.C. IS RESPONSIBLE FOR VERIFYING THE LEAD REPORT SUBMITTED AS PART OF THE BIDDING DOCUMENTATION TO ENSURE THAT THE EXTERIOR WALL SURFACES ARE FREE OF LEAD PRIOR TO COMMENCING THE WORK. IF G.C. FINDS IN THE REPORT THE SURFACE CONTAINS THE HAZARDOUS MATERIAL, PROPER MITIGATION PROCEDURES SHALL BE FOLLOWED.

IF THE EXISTING EXTERIOR WALL IS WOOD OR PLASTER, IT SHALL BE SPRAY PAINTED WITH SATIN GLIDDEN HIGH ENDURANCE PLUS EXTERIOR PAINT + PRIMER, OR APPROVED EQUIVALENT. ALL EXTERIOR PARAPETS, IF ANY, SHALL BE PAINTED ON BOTH SIDES (EXTERIOR & INTERIOR).

GENERAL CONTRACTOR AT HIS EXPENSE SHALL MAKE AT LEAST (10) TEN DIFFERENT 10"X8"SAMPLES OF SELECTED COLORS ON WALLS FOR ARCHITECT'S EVALUATION. CONTRACTOR SHALL REQUEST THE ARCHITECT COLOR AND WALLS WERE SAMPLES ARE REQUESTED.

4. PAINT - EXISTING INTERIOR WALL & CEILING

PAINT SHALL BE APPLIED ACCORDING TO CONSTRUCTION DRAWINGS. PAINT COLOR SHALL BE SELECTED BY THE ARCHITECT.

SURFACE PREPARATION SHALL BE MADE ACCORDING TO TECHNICAL SPECS. G.C. IS RESPONSIBLE FOR VERIFYING THE LEAD REPORT SUBMITTED AS PART OF THE BIDDING DOCUMENTATION TO ENSURE THAT THE INTERIOR WALL SURFACES ARE FREE OF LEAD PRIOR TO COMMENCING THE WORK. IF G.C. FINDS IN THE REPORT THE SURFACE CONTAINS THE HAZARDOUS MATERIAL, PROPER MITIGATION PROCEDURES SHALL BE FOLLOWED.

ALL WALLS & PLASTER CEILINGS, UNLESS OTHERWISE SPECIFIED, SHALL BE SPRAY PAINTED EGGSHELL GLIDDEN ONE COAT INTERIOR PAINT + PRIMER, OR APPROVED EQUIVALENT. WOOD CEILINGS SHALL BE PAINTED WITH PAINT SUITABLE FOR WOOD.

GENERAL CONTRACTOR AT HIS EXPENSE SHALL MAKE AT LEAST (10) TEN DIFFERENT 10"X8" SAMPLES OF SELECTED COLORS ON WALLS AND CEILINGS FOR ARCHITECT'S EVALUATION. CONTRACTOR SHALL REQUEST THE ARCHITECT COLOR AND WALLS WERE SAMPLES ARE REQUESTED.

PAINT - EXISTING EXTERIOR METAL ELEMENTS

CONTRACTOR MUST PREPARE ALL METAL SURFACES BY CLEANING AND APPLYING RUST OLEUM MATHYS METAL CLADDING PRIMER, OR EQUIVALENT,

SURFACE PREPARATION SHALL BE MADE ACCORDING TO TECHNICAL SPECS. G.C. IS RESPONSIBLE FOR VERIFYING THE LEAD REPORT SUBMITTED AS PART OF THE BIDDING DOCUMENTATION TO ENSURE THAT THE EXTERIOR METAL ELEMENTS ARE FREE OF LEAD PRIOR TO COMMENCING THE WORK. IF G.C. FINDS IN THE REPORT THE SURFACE CONTAINS THE HAZARDOUS MATERIAL, PROPER MITIGATION PROCEDURES SHALL BE FOLLOWED.

AFTER THE PRIMER, IT SHALL BE SPRAY PAINTED WITH SATIN GLIDDEN HIGH ENDURANCE PLUS EXTERIOR PAINT + PRIMER, OR APPROVED EQUIVALENT. G.C. SHALL USE AN AIRLESS SPRAY PAINTER TO ACHIEVE THE CORRECT FINISH, USING MANUFACTURER RECOMMENDATIONS.

CONT. FINISH NOTES:

6. PAINT AND REFINISHING OF WOOD DOORS/WINDOWS/BALUSTER/RAILING

SURFACE PREPARATION SHALL BE MADE ACCORDING TO TECHNICAL SPECS. G.C. IS RESPONSIBLE FOR VERIFYING THE LEAD REPORT SUBMITTED TO THEM AS PART OF THE BIDDING DOCUMENTATION TO ENSURE THAT THE EXTERIOR WALL SURFACES ARE FREE OF LEAD PRIOR TO COMMENCING THE WORK. IF G.C. ENCOUNTERS THE SURFACE CONTAINS THE HAZARDOUS MATERIAL, PROPER MITIGATION PROCEEDURES SHALL BE FOLLOWED.

WOOD SURFACES OF DOORS, WINDOWS, AND BALUSTERS SHALL BE REFINISHED ACCORDING TO THE CONSTRUCTION DRAWINGS. HOWEVER, ALL EXTERIOR WOOD ELEMENTS SHALL BE PAINTED EVEN IF NOT REFINISHED.

DOORS/ WINDOWS/ BALUSTERS SHALL BE SANDED AND CLEANED IN PREPARATION FOR REPAINTING. PAINT COLOR SHALL BE SELECTED BY THE

THE EXTERIOR WOODEN ELEMENT SHALL BE SPRAY PAINTED WITH SATIN GLIDDEN HIGH ENDURANCE PLUS EXTERIOR PAINT + PRIMER, OR APPROVED EQUIVALENT.

A SAMPLE AREA SHALL BE REFINISHED PRIOR TO PROGRESSING WITH THE WORK FOR ARCHITECT APPROVAL

CARE SHALL BE TAKEN TO PROTECT ALL MATERIALS FROM THE NEGATIVE EFFECTS OF TEMPERATURE, RELATIVE HUMIDITY, AND HANDLING. THE G.C. SHALL BE RESPONSIBLE TO PROTECT MATERIALS FOR CARE AND MOISTURE CONSIDERATIONS BEFORE, DURING, AND AFTER INSTALLATION.

G.C. OR THEIR SUBCONTRACTOR IN CHARGE OF WOODWORKING MUST FOLLOW AWI STANDARDS. https://www.awinet.org/standards/standards-overview

WHEN WORKING WITH WOOD BALUSTRADE, G.C. SHALL FOLLOW ANSI/AWI SMA 0643-2021 -WOOD STAIR, HANDRAIL, AND GUARD SYSTEMS STANDARDS. 7. PAINT & NEW WOOD BALUSTRADES

ALL NEW WOODEN BALUSTRADES SHALL BE OF MAHOGANY WOOD.

ALL NEW WOODEN ELEMENTS SHALL BE SPRAY PAINTED WITH SATIN GLIDDEN HIGH ENDURANCE PLUS EXTERIOR PAINT + PRIMER, OR APPROVED

A SAMPLE AREA SHALL BE PAINTED PRIOR TO PROGRESSING WITH THE WORK FOR ARCHITECT APPROVAL.

CARE SHALL BE TAKEN TO PROTECT ALL MATERIALS FROM THE NEGATIVE EFFECTS OF TEMPERATURE, RELATIVE HUMIDITY, AND HANDLING. THE G.C. SHALL BE RESPONSIBLE TO PROTECT MATERIALS FOR CARE AND MOISTURE CONSIDERATIONS BEFORE, DURING, AND AFTER INSTALLATION. 8. NEW COPPER GUTTER & ACCESSORIES

EXISTING GUTTER SHALL BE REMOVED IN ACCORDANCE WITH THE CONSTRUCTION DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE PORTIONS OF THE GUTTER THAT WILL BE REMOVED TO BE AS INSTRUCTED IN THE CONSTRUCTION DRAWINGS.

CONTRACTOR SHALL USE GUTTERSUPPLY TYPE -K GUTTER 6"COPPER, SERIAL NO. COKGX6XC16X16oz, OR EQUIVALENT / LENGTH TO BE AS SHOWN ON CONSTRUCTION DRAWINGS. ALL GUTTERS SHALL INCLUDE GUTTERSUPPLY'S K-STYLE GUTTER SCREEN: 6K COPPER DROP-IN / 3FT. SCREEN / OR

G.C. SHALL USE THE FOLLOWING COMPONENTS WHEN INSTALLING A COPPER GUTTER FOR A ROOF FROM GUTTERSUPPLY MANUFACTURER, OR EQUIVALENT: OUTLET WIDE FLANGE, SERIAL NO. COKOX34CXWF, 3X4 REC. OUTLET-WIDE FLANGE, COPPER. / OFFSET CONNECTOR -2"FROM WALL, SERIAL NO. COOFS34C15X, 3X4 OFFSET (2"), COPPER 16oz. / HIDDEN HANGER, SERIAL NO. BRKHHC6B060, 6K HIDDEN HANGER W/ CLIP, BRASS / END CAP, SERIAL NO. COLHE6XC16X, 6K HIGHBACK LEFT END CAP, 16 oz COPPER, RIGHT. / DOWNSPOUT, SERIAL NO. CODSX34C1620, 3X4, 20FT, COPPER 16oz / DOWNSPOUT ELBOW TYPE-B, SERIAL NO. COBEX34C16X, 3X4, COPPER 16 oz / DOWNSPOUT ELBOW TYPE-A, SERIAL NO. COAEX341645, 3X4, COPPER 45 deg / CORNER MITTER CONNECTOR, SERIAL NO. COOBM6XCXXX / 6K OUTSIDE BOX MITTER, COPPER / BRIGHTON DOWNSPOUT BRACKET, SERIAL NO. CODSSBRIG34, 3X4 BRIGHTON DS STRAP, COPPER.

G.C. SHALL USE THE FOLLOWING COMPONENTS WHEN INSTALLING A COPPER GUTTER FOR A ROOF FROM AQUABARREL MANUFACTURER, OR EQUIVALENT: FUNNELS TYPE-Y, SERIAL NO. BO7MN1DCPP, 3X4X10-1/2 WIDE, 8

9. CLAY ROOF TILE RESTORATION

ALL EXISTING ROOF VEGETATION IS TO BE REMOVED WITHOUT AFFECTING THE INTEGRITY OF THE TILES.

BROKEN ROOF TILES ARE TO BE REPAIRED USING OSI RT600 10-LF OZ TERRACOTTA (IDH 1810372) ROOF TILE CONSTRUCTION ADHESIVE, OR EQUIVALENT. THIS PROCESS WILL BE DONE IF THE PORTION OF THE TILE THAT WAS BROKEN OFF IS FOUND. THIS BROKEN PORTION OF THE TILE WILL BE JOINED TO THE REMAINING TILE. PRODUCT SHALL BE USED FOLLOWING MANUFACTURER RECOMMENDATIONS.

IF A PORTION OF THE TILE IS MISSING, FILL AREA USING REINFORCEMENT MESH AND CEMENT PLASTER.

TILES THAT ARE FILLED USING REINFORCEMENT MESH AND CEMENT PLASTER SHALL BE STAINED TO MATCH THE COLOR OF THE EXISTING TILE.

IF ANY NEW TILES ARE TO BE USED IN THE RESTORATION, THESE SHALL BE SUBMITTED FOR THE ARCHITECT'S EVALUATION BEFORE PROGRESSING WITH THE WORK.

AS PART OF ALTERNATE E, AFTER ROOF TILE RESTORATION WORK IS COMPLETED, G.C. SHALL USE ECOSEAL CONCRETE TILE ROOF WATERPROOFING SYSTEM, OR EQUIVALENT. G.C. SHALL FOLLOW MANUFACTURER RECOMMENDATIONS.WATERPROOFED AREAS SHALL BE FINISHED WITH PAINT TO MATCH HE COLOR OF THE ORIGINAL TILE. G.C. SHALL ENSURE THAT THE PAINT IS APPROVED BY WATERPROOFING MANUF. AND IS COMPATIBLE WITH THE WATERPROOFING MATERIAL

10. ALUMINUM GRILLE RESTORATION

ALUMN. GRILLES SHALL BE RESTORED AS SPECIFIED IN THE CONSTRUCTION DRAWINGS.

GRILLE FINISH/COLOR MUST MATCH EXISTING.

ANY NEW MATERIAL TO BE USED IN THE RESTORATION SHALL BE SUBMITTED FOR THE ARCHITECT'S EVALUATION BEFORE.

G.C. SHALL RESTORE A SMALL PORTION OF THE GRILLE AND IS EXPECTED TO PRESENT IT TO THE ARCHITECT FOR APPROVAL PRIOR TO PROGRESSING

SUBMITTAL NOTES:

- 1. CONTRACTOR SHALL DELIVER TO THE DESIGNATED INSPECTOR AND ARCHITECT, PRIOR TO OR AT THE PRE-CONSTRUCTION CONFERENCE. A PRELIMINARY SUBMITTALS SCHEDULE (SUBMITTAL LOG) OF ALL REQUIRED SUBMITTALS, SHOP DRAWINGS, SAMPLES, TECHNICAL DATA FOR FABRICATED MATERIALS AND EQUIPMENT SPECIFICATIONS FOR A/E APPROVAL.
- SUBMITTAL LOG SHALL INCLUDE (BUT NOT LIMITED TO) PROJECT'S NAME AND NUMBER, REVISION DATE, SUBMITTAL'S NUMBER, TITLE OR DESCRIPTION, DATE DELIVERED, DATE RECEIVED, DATE REJECTED, DATE APPROVED AND COMMENTS, IF ANY. IN ORDER TO FACILITATE ARCHIVING AND DOCUMENTS ADMINISTRATION, THE STANDARDIZATION OF THE SUBMITTALS NAMES AND IDENTIFICATION NUMBERS IS RECOMMENDED.
- 3. G.C. SHALL INCLUDE IN SUBMITTAL LOG THE ANTICIPATED INITIAL PRESENTATION DATE OF EACH
- 4. SUBMITTALS SHALL BE NUMBERED ACCORDING TO SUBMITTAL LOG.
- CONTRACTOR SHALL REVISE, COMMENT, APPROVED, SIGN AND SEAL ALL SUBMITTALS BEFORE DELIVERY FOR INSPECTOR AND A/E REVISION. NO SUBMITTAL WILL BE CONSIDERED IF IT COMES WITHOUT CONTRACTOR'S SIGN AND SEAL, CONFIRMING THAT HE OR SHE HAS REVIEWED THE SUBMITTAL AND THAT THE SUBMITTED ITEM OR ITEMS ARE IN ACCORDANCE WITH THE CONTRACT
- THE DESIGNATED INSPECTOR BY THE OWNER HAS THE RESPONSIBILITY TO REVISE AND COMMENT ON ALL SUBMITTAL CONTENT TO VERIFY THAT THE INFORMATION INCLUDED IS COMPLETE AND PRECISE BEFORE DELIVERING IT FOR A/E APPROVAL. NO SUBMITTAL WILL BE CONSIDERED BY A/E IF IT COMES WITHOUT INSPECTOR'S REVISION.
- 7. CONTRACTOR SHALL CAREFULLY CONTROL HIS PROCUREMENTS OPERATIONS TO ENSURE THAT EACH INDIVIDUAL SUBMITTAL IS MADE ON OR BEFORE THE CONTRACTOR'S SCHEDULED SUBMITTAL DATE SHOWN ON THE APPROVED SUBMITTAL LOG.
- GENERAL CONTRACTOR IS REQUIRED TO ALLOW SUFFICIENT TIMING FOR SUBMISSION, REVIEW, SHIPMENT AND MANUFACTURING OF ALL PRODUCTS, MATERIALS AND/OR EQUIPMENT. PRODUCTS AND/OR MATERIALS UNAVAILABILITY OR STOCK SHORTER DO NOT RELIEVE THE GENERAL CONTRACTOR FROM COMPLYING WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.
- SUBSTITUTIONS OF MATERIALS BASED ON THE SOLE REASON OF SHORTER ARRIVAL TIME WILL NOT BE CONSIDERED BY THE A/E REGARDLESS OF THE TIME INCREASE THIS MAY CAUSE PENALTIES FOR THE CONTRACTOR. GENERAL CONTRACTOR SHALL PLAN TIMING OF SUBMITTALS DELIVERY WITH ALL SUB-CONTRACTORS AND THEIR SUPPLIERS.
- angle 10. $\,$ all submittals shall be received according to the agreement between the contractor \langle AND THE GOVERNMENT AGENCY. IT WILL BE THE ARCHITECT'S OFFICE PREROGATIVE TO ACCEPT OR REJECT ALL OR ANY SUBMITTAL CONTAINING SPECIFIED EQUIVALENT PRODUCTS. CONTRACTOR SHALL PROVIDE AND INSTALL MATERIALS ACCORDING TO CONSTRUCTION DOCUMENTS /1 SPECIFICATIONS.
- 11. SUBMITTALS SHALL INCLUDE ITEMS SUCH AS: CONTRACTOR'S, MANUFACTURER'S OR FABRICATOR'S DRAWINGS (SHOP DRAWINGS), DESCRIPTIVE LITERATURE INCLUDING (BUT NOT LIMITED TO) CATALOG CÙTS, DIAGRAMS, OPERATING CHARTS OR CURVES, TEST REPORTS, SAMPLES, CERTIFICATIONS, WARRANTIES, AND OTHER SUCH REQUIRED INFORMATION.
- 12. G.C. IS RESPONSIBLE FOR THE SUBMITTALS TO BE WITH MARKS, NOTES AND INDICATIONS, THAT PROPERLY IDENTIFIES ALL THE INFORMATION RELATED TO THE SUBMITTED PRODUCT AND OR MATERIAL, SUCH AS BUT NOT LIMITED TO MODEL, SIZE, PERFORMANCE, AND FINISHES.
- 13. A/E WILL NOT CONSIDER SUBMITTALS WITH INCOMPLETE INFORMATION NECESSARY TO IDENTIFY THE SUBMITTED PRODUCT. INCLUDING, BUT NO LIMITED TO PRODUCT'S: MODEL, NUMBER, SERIES, ACCESSORIES, COLOR, FINISH AND OTHER CHARACTERISTICS THAT VARIES THE PRODUCT
- 14. AT A MINIMUM G.C. SHALL PROVIDE SUBMITTALS (SAMPLE, SHOP DRAWING, AND/OR DATA SHEET)
- 14.1. ALL NEW MATERIALS THAT WILL BE INSTALLED; 14.1.1. SAMPLE AND SHOP DRAWING OF THE CROWN MOLDINGS, FLOOR BASES, WALL TRIMS, AND
 - DOOR CASINGS.
- 14.1.2. WOOD SIDING PANNELS
- 14.1.3. FLOORS AND CEILINGS 14.1.4. LIGHTING FIXTURES
- 14.1.5. GUARDRAILS AND HANDRAILS
- 14.1.6. BATHROOMS ACCESSORIES 14.1.7. BATHROOMS EQUIPMENTS
- 14.1.8. STAIRS 14.1.9. DRY WALL PANELS
- 14.1.10. PAINTS
- 14.1.11. TILES 14.1.12. HARDWARE
- 14.1.13. DOORS & WINDOWS 14.1.14. MILLWORK
- 14.1.15. WATER PROOFING MEMBRANES 14.1.16. OTHERS
- 15. CONSTRUCTION DRAWINGS SHALL NOT BE DIRECTLY USED AS PART OF ANY SUBMITTAL OR SHOP DRAWINGS. CONTRACTOR SHALL PRODUCE OR DEVELOP ORIGINAL SHOP DRAWINGS FOR THIS PROJECT. IN ANY CASE ELECTRONIC DWG OR DXF FILES WILL BE PROVIDED BY ARCHITECTS TO
- 16. ALL SAMPLES, MATERIAL INFORMATION AND SHOP DRAWINGS SHALL BE PREPARED SPECIFICALLY FOR THIS PROJECT. SHOP DRAWINGS SHALL BE DRAWN TO SCALE, INCLUDING DIMENSIONS AND DETAILS, SHOWING ADJACENT CONSTRUCTION AND RELATED WORK. NOTE ANY SPECIAL COORDINATION REQUIRED. NOTE ANY DEVIATIONS FROM REQUIREMENTS OF CONTRACT DOCUMENTS.
- 17. THE A/E REVIEW OF SUBMITTALS WILL BE ONLY FOR THE LIMITED PURPOSE OF CHECKING FOR CONFORMANCE WITH INFORMATION GIVEN IN THE CONSTRUCTION DOCUMENTS AND SEE IF THEY CONFORM TO THE DESIGN INTENT. IT IS THE CONTRACTOR'S RESPONSIBILITY FOR DETERMINING THE ACCURACY OF MEASUREMENTS AND COMPLETENESS OF DETAILS, VERIFYING QUANTITIES AND CHECKING FABRICATION OR INSTALLATION PROCEDURES. THE A/E REVIEW WILL NOT RELIEVE THE CONTRACTOR OF HIS OR HER RESPONSIBILITIES UNDER THE CONTRACT DOCUMENTS.
- 18. ADDITIONAL SUBMITTALS MAY BE REQUIRED TO THOSE SPECIFIED WHEN DEEMED NECESSARY TO ADEQUATELY DESCRIBE THE WORK COVERED IN THE TECHNICAL SPECIFICATIONS, IT MAY INCLUDE SAMPLES, SHOP DRAWINGS AND/OR TECHNICAL DATA, WITH NO CONTRACT COST CHANGE.
- 19. ALL MATERIALS SHALL BE INSTALLED IN STRICT ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS.
- 20. ANYTIME A SAMPLE IS REQUIRED, G.C. SHALL SUBMIT A TOTAL OF (3) SAMPLES. (1) IS TO BE SUBMITTED TO THE ARCHITECT, (1) IS TO BE SUBMITTED TO THE STATE HISTORIC PRESERVATION OFFICE, AND (1) IS TO BE KEPT AT THE PROJECT SITE.
- 21. ALL SUBMITTALS SHALL BE SUBMITTED ELECTRONICALLY VIA EMAIL TO ARQUITECTOVILLEGAS@ARQUITEG.COM AND ARQ.BALLESTER@ARQUITEG.COM
- 22. A/E = ARCHITECT/ENGINEER


IMPORTANT NOTE

G.C. SHALL CONSIDER THAT ON ALL NOTES, THE WORD "OWNER" REFERS TO THE OWNER'S REPRESENTATIVE.

G.C.MAY USE A SUBSTITUTE PRODUCT AS LONG AS IT IS EQUIVALENT TO & MATCHES THE CHARACTERISTICS OF ALL SPECIFIED PRODUCTS SPECIFIED ON SHEET A-07. G.C. SHALL SUBMIT ALL PROPOSED SUBSTITUTE PRODUCTS TO ARCHITECT FOR APPROVAL PRIOR ORDER.



NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO BARRANQUITAS, PUERTO RICO

> Architect of Record: Victor M Villegas, A.I.A

Registration No. 11445 PR.



INGENIEROS PLANIFICADORES AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-203 FAXCIMIL (787) 722-5031

arquitectospr@arquiteg.com Yo, Victor M. Villegas Durán, Lic. #11445, certifico que sc el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico que entiendo que dichos planos y especificaciones cumplen co las disposiciones aplicables del Reglamento Conjunto y la disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción Certifico, además, que en la preparación de estos planos

v especificaciones se ha cumplido cabalmente con lo

dispuesto en la Ley Núm. 14 de 8 de enero de 2004. por la Industria Puertorriqueña"y con la [Ley Núm. 319 c 15 de mayo de 1938, seaún enmendada: Lev Núm. 96 d 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se hava producido por desconocimient o por negligencia ya sea por mí, mis agentes o

PROFESSIONAL TEAM:

hacen responsable de cualquier acción judicial y

disciplinaria por la OGPe.

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

Issue NOTES UPDATE 06/19/23 Drawn by Reviewed by

SHEET TITLE AND NUMBER:

VV

GM | EM | CB | LR

FINISHES & SUBMITTAL NOTES

ISSUE FOR BIDDING NOT FOR CONSTRUCTION

BY: V.M.V. DATE:JUNE 19, 2023

IONE 00

NOTE:

G.C.MAY USE A SUBSTITUTE PRODUCT AS LONG AS IT IS
EQUIVALENT TO & MATCHES THE CHARACTERISTICS OF ALL
SPECIFIED PRODUCTS SPECIFIED ON SHEET A-07. G.C. SHALL
SUBMIT ALL PROPOSED SUBSTITUTE PRODUCTS TO ARCHITECT FOR
APPROVAL PRIOR ORDER.

LEAD - BASED PAINT GENERAL NOTES:

- LEAD-BASED COATINGS WERE IDENTIFIED ON SUBSTRATES OF THIS PROPERTY BY ZIMMETRY ENVIRONMENTAL.

 PROJECT MAY INCLUDE ENCAPSULATION ABATEMENT OF LEAD-BASED PAINT, REMOVAL AND DISPOSAL OF BUILDING

 MATERIALS COATED WITH LEAD-BASED PAINT, AND DISTURBANCE OF LEAD-BASED PAINT USING LEAD-SAFE WORK

 PRACTICES.
- RELATED PROJECT DOCUMENTS:


 A. LEAD-BASED PAINT SURVEY REPORT BY ZIMMETRY ENVIRONMENTAL.
- B. SPECIFICATION SECTION 02 83 19 LEAD BASED PAINT ABATEMENT.
- 3. THE CONTRACTOR SHALL BE AWARE OF ALL DIVISION 02 SPECIFICATION REQUIREMENTS.
- . THE LOCATIONS OF IDENTIFIED LEAD-BASED PAINT ARE PRESENTED ON SURVEY REPORT. ACTUAL REMOVAL LOCATION AND QUANTITIES TO BE REMOVED MAY VARY BASED ON THE PROJECT SCOPE OF WORK. G.C SHALL
- 5. THE CONTRACTOR SHALL BE AWARE OF ALL CONDITIONS OF THE PROJECT AND IS RESPONSIBLE FOR VERIFYING QUANTITIES AND LOCATIONS OF ALL WORK TO BE PERFORMED. FAILURE TO DO SO SHALL NOT RELIEVE THE CONTRACTOR OF ITS OBLIGATION TO FURNISH ALL LABOR AND MATERIALS NECESSARY TO PERFORM THE WORK.
- ALL WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE PROJECT DOCUMENTS AND ALL GOVERNING CODES, RULES, AND REGULATIONS. WHERE CONFLICTS OCCUR BETWEEN THE PROJECT DOCUMENTS AND APPLICABLE CODES, RULES, AND REGULATIONS, THE MORE STRINGENT SHALL APPLY.
- 7. BEFORE STARTING THE WORKS, THE CONTRACTOR MUST SUBMIT TO THE OWNER'S REPRESENTATIVE AND THE A/E,
 A DETAILED NARRATIVE OF THE STEPS AND METHODS OF THE WHOLE PROCESS THAT WILL BE FOLLOWED FOR THE
 ABATMENT, TOGETHER WITH IT, A SCHEDULE FOR THE PERFORMANCE OF THE WORK.
- . BEFORE ORDERING, THE ENVIRONMENTAL CONTRACTOR MUST SUBMIT THE MATERIALS THAT THEY PROPOSE TO USE FOR ENCAPSULATION.
- . ONCE THE CONTRACTOR HAS SUBMITTED HIS WORK PLAN AND APPROVAL OF THE MATERIALS TO BE USED, HE MUST PREPARE A 3' x 3' SAMPLE OF HOW THE FINAL WORK WOULD LOOK LIKE. THE CONTRACTOR MUST BEAR IN MIND THAT WE ARE WORKING ON PROJECTS OF HISTORICAL VALUE AND THEREFORE MUST BE CAREFUL NOT TO CAUSE DAMAGE TO THE INTEGRITY OF THE SUBSTRATE MATERIALS, WHETHER THEY ARE WOOD, METALS OR CEMENTITIOUS MATERIALS.
- IO. ACTIVITIES IMPACTING HAZARDOUS MATERIALS INCLUDING BUT NOT LIMITED TO WORK AREA PREPARATION, GROSS REMOVAL ACTIVITIES, CLEANING ACTIVITIES, WASTE REMOVAL, ETC. MAY NEED TO BE PERFORMED DURING 'OFF-HOURS'.
- 1. MULTIPLE MOBILIZATIONS MAY BE REQUIRED TO PERFORM THE WORK IDENTIFIED IN THIS PROJECT. THE CONTRACTOR SHALL COORDINATE AND SCHEDULE ALL WORK WITH THE OWNER OR DESIGNATED OWNER'S REPRESENTATIVE.
- 12. THE CONTRACTOR MUST MAINTAIN CURRENT LICENSES PURSUANT TO ALL LOCAL, STATE, AND FEDERAL REQUIREMENTS ASSOCIATED WITH THIS PROJECT.
- 13. ALL WORK INCLUDING, BUT NOT LIMITED TO, PHASING, SCHEDULING, AND SEQUENCING SHALL BE COORDINATED WITH THE OWNER AND THE OWNER'S REPRESENTATIVE(S).
- 14. OTHER COATINGS WHICH CONTAIN LEAD AT CONCENTRATIONS LOWER THAN THE UNITED STATES ENVIRONMENTAL PROTECTION AGENCY (EPA) DEFINITION OF LBP ARE PRESENT WITHIN THE CONTRACT WORK AREAS. THESE COATINGS MAY BE REFERRED TO AS LEAD—CONTAINING PAINT OR PAINT CONTAINING LEAD. DISTURBANCE OF LEAD CONTAINING PAINT CAN RESULT IN LEAD—EXPOSURE TO WORKERS AND OCCUPANTS. REFER TO THE ENVIRONMENTAL SURVEY FOR LEAD—BASED PAINT REPORT BY ANALYTICAL ENVIRONMENTAL SERVICES INTERNATIONAL, INC. DATED AUGUST 2020 FOR ADDITIONAL DETAILS ON THE TYPE AND LOCATION OF LEAD—CONTAINING PAINT. DISTURBANCE OF LEAD—CONTAINING PAINT SHALL BE PERFORMED IN ACCORDANCE WITH THE UNITED STATES OCCUPATIONAL HEALTH AND SAFETY ADMINISTRATION (OSHA) LEAD IN CONSTRUCTION STANDARD 29 CFR 1926.62 AND ALL OTHER APPLICABLE OSHA HEALTH AND SAFETY REGULATIONS.

LEAD - BASED PAINT ABATEMENT:

- 1. PROJECT DESCRIPTION A LEAD-BASED STUDY PREPARED FOR THIS PROPERTY BY ZIMMETRY ENVIRONMENTAL INDICATES THAT THE PROPERTY HAS LEAD-BASED PAINT ON MANY ELEMENTS. THE GENERAL CONTRACTOR SHOULD BE FAMILIAR WITH SUCH STUDY WHICH HAS BEEN INCLUDED IN THE TECHNICAL SPECIFICATIONS OF THE PROJECT
- BACKGROUND -THROUGHOUT THE LAST DECADES THESE BUILDING HAVE BEEN SUBJECTED TO SEVERAL RENOVATIONS AND IMPROVEMENTS. MANY OF THE CONSTRUCTION MATERIALS USED IN THE EARLY PHASES OF CONSTRUCTION AND REMODELING PROJECTS USED LEAD CONTAINING MATERIALS, SUCH AS CERAMIC, WALL PAINT, BATHROOM APPLIANCES AND OTHERS. TO PROCEED WITH THE INTENDED RENOVATION, THE CG SHALL ABATE THESE MATERIALS FOLLOWING FEDERAL AND STATE GUIDELINES.
- 3. PROJECT SAFETY REQUIREMENTS -TO MINIMIZE ANY HAZARD POTENTIAL TO THE HEALTH AND SAFETY OF GENERAL CONTRACTOR, SUBCONTRACTOR AND SITE PERSONNEL, BE IT REGULAR OR INCIDENTAL, AN ON-SITE HEALTH AND SAFETY PROTOCOLS WILL BE ALWAYS REQUIRED.
- 4. ALSO, SAFETY MEETINGS ARE A MUST, EITHER AT LEAST ON A WEEKLY BASIS OR WHEN A NEW TASK IS TO BE COMMENCED, AN INCIDENT HAS OCCURRED OR IS SUSPECTED TO OCCUR OR WHENEVER SITE AND WEATHER CONDITIONS MIGHT REQUIRE READDRESSING ANY POTENTIAL HAZARDS. THESE MEETINGS INCLUDE BUT ARE NOT LIMITED TO ESTABLISH SAFETY PROTOCOL, PERSONAL PROTECTIVE EQUIPMENT REQUIREMENTS, PPE'S AVAILABILITY AS WELL AS OPERATING CONDITIONS.
- 5. SPECIFIC WORK PLAN AND SPACE LAYOUT FOR ABATEMENT. LEAD ABATEMENT SHALL FALLS WITHIN NESHAP REGULATIONS.
- 6. TO ACHIEVE ABATEMENT AND BEFORE STARTING, THE ENVIRONMENTAL SUB-CONTRACTOR MUST SUBMIT TO THE OWNER'S REPRESENTATIVE AND THE A/E, A DETAILED NARRATIVE OF THE STEPS AND METHODS OF THE WHOLE PROCESS THAT WILL BE FOLLOWED FOR THE ABATMENT, TOGETHER WITH IT, A SCHEDULE FOR THE PERFORMANCE OF THE WORK.
- 7. LEAD—BASED ABATEMENT PERMIT THE SPECIFIC WORK PLAN WILL BE PART OF OTHER DOCUMENTATION THAT SHALL BE PRESENTED TO THE PRDNER (PUERTO RICO DEPARTMENT OF NATURAL AND ENVIRONMENTAL RESOURCES) DETAILING ALL THE WORK PRACTICES, AND GUIDELINES THE GC. WILL FOLLOW BEFORE, DURING AND AFTER THE PROJECT'S EXECUTION. IT WILL CONTAIN ALL CREDENTIALS OF THE SUPERVISION, LABORS, HYGIENISTS, LABORATORIES, TRANSPORTERS, PROJECT DESIGNERS, AND LANDFILL FACILITIES AS WELL AS A COPY OF THE ENVIRONMENTAL REPORT WITH THE FINDINGS REGARDING THIS PROJECT. THESE WILL BE SUBMITTED ALONG A PERMIT SUBMITTAL FORM FOR DNER'S EVALUATION AND APPROVAL.
- 8. COMMUNICATIONS A HAZARD COMMUNICATION PROGRAM WILL BE IN FORCE DURING THE PROJECT DURATION. SUCH PROGRAM INCLUDES BUT IS NOT LIMITED TO RIGHT TO KNOW ACT, MSDS OF HANDLING SUBSTANCES, LABELING, CLASSIFICATION, RISK ASSESSMENT AND OTHER COMMUNICATION DEEM NECESSARY TO PROVIDE THE WORKER AND ALL ASSOCIATED ENTITIES A CLEAR UNDERSTANDING OF THE RISK INVOLVED AND THE CORRECTIVE ACTIONS IN CASE OF ANY UNFORESEEN INCIDENT.
- 9. ALL PROJECT PERSONNEL SHOULD KNOW WHAT THE PHYSICAL, CHEMICAL, AND BIOLOGICAL CHARACTERISTICS OF THE HANDLED MATERIALS ARE. ANY POSSIBLE REACTIVITY, INFLAMMABILITY, AND EXPLOSIVELY (IF APPLICABLE) SHALL BE PROPERLY ADDRESSED PRIOR TO ANY CONTACT OR HANDLING OF SUCH MATERIALS. THESE HAZARDS COMMUNICATIONS SHALL BE PLACED IN CLEAR VIEW OF ALL INVOLVED PARTIES, EITHER IN A RIGHT TO KNOW STATION OR ON POSTERS STATING THESE RISKS. ALL PERSONNEL TO BE HANDELING THE HARZADOUS MATERIALS HAVE TO BE DULY LICENSED AND EXPERIENCED HANDLING SUCH MATERIALS AS WELL AS UNDERSTANDING ALL POTENTIAL HAZARDS, INCLUDING BUT NOT LIMITED TO WORKING ON OUTDOOR CONDITIONS, HAND SIGNALING, SOUND SIGNALING, AND
- 10. VISUAL SIGNALING. THE HOT ZONES MUST BE VISUALLY ISOLATED BY BARRICADING WITH AVAILABLE RESOURCES. ALL SAFETY MEETINGS WILL ADDRESS THESE ISSUES CONSTANTLY. HOT ZONES, SUPPORT ZONES, AS WELL AS CHECK POINTS WILL BE CLEARLY MARKED AND IDENTIFIED. ALTHOUGH THE PROJECT HAS A LIMITED AREA, MEANING THAT THE TRANSITION FROM ONE AREA TO THE NEXT IS RELATIVELY SHORT IT ENHANCES THE NEED FOR SUCH CLEAR DEMARCATIONS.
- 11. OTHER SPECIFICS THE AREAS WILL EXHAUST ITS AIR THROUGH A VACUUM WITH HEPA FILTER THAT WILL STORE ANY DEBRIS WITHIN ITS CANISTER. ALSO, ALL FILTERED WASTEWATERS WILL BE POURED INTO THE NEAREST DRAIN AS APPROVED IN THE SUBMITTED PERMIT.
- 12. DECONTAMINATION THE DECONTAMINATION WILL CONSIST IN WEARING A DOUBLE DISPOSABLE SUIT. WITHIN THE MINI ENCLOSURE THE EMPLOYEE WILL REMOVE OUTER SUIT BEFORE EXITING, A DECON ATTENDANT WILL PROCEED TO VACUUM THE INNER SUIT WHILE THE EMPLOYEE IS STILL WEARING IT. AFTER THAT SUIT IS VACUUMED, THEN THE EMPLOYEE CAN REMOVE THE SUIT AND CONTINUE WITH UNDERNEATH STREET GARMENTS. IF THERE IS ANY GENERATED WATERS IT WILL BE FILTERED WITH A TWO-STAGE 5- AND 25-MICRON FILTERING SYSTEM.
- 13. GENERATED WASTE ALL WASTE WILL BE DOUBLE-BAGGED IN 6 MIL LABELED POLY BAGS SEALED WITH A GOOSENECK-TYPE TIGHT WITH DUCT TAPE. THESE BAGS WILL BE TAKEN OUT THROUGH THE DECON UNIT, BEING THE ONLY ENTRANCE AND EXIT TO AND FROM THE BATHROOM. THESE BAGS WILL BE PUT IN WHEELED BUGGY THROUGH THE CORRIDOR UP TO THE CLOSED DUMPSTER PARKED NEAR BUT OUTSIDE THE BUILDING, PREFERABLY IN THE PARKING SPACES ACCESSING THE BASEMENT. TCLP SAMPLING OF THIS WASTE WILL BECOLLECTED AND ANALYZED TO DETERMINE FINAL WASTE SITE. NORMALLY RESULTS NON-HAZARDOUS AND WILL BE TRANSPORTED TO A LEGAL LANDFILL FOR FINAL DISPOSAL. THIS PROCESS WILL ACCOMPANY BY A DULY APPROVED STATE AND DOT MANIFEST.
- 14. FINAL CLEARANCE THESE AREAS AS WELL AS OUTSIDE IMMEDIATE AREA WILL BE SAMPLED FOR FINAL CLEARANCE. FOR OUTDOORS, FINAL CLEARANCE MUST COMPLY WITH 400 PPM FOR LEAD. COMPLIANCE WITH PARAMETER WILL ENABLE RB CONSTRUCTION TO CONTINUE WITH RENOVATION ACTIVITIES.
- 15. PROJECT DOCUMENTATION ALL ACTIVITIES DESCRIBED ABOVE WILL BE DOCUMENTED WITH PHOTOGRAPHIC PROGRESS AND FINAL CONDITIONS, ENTRY LOGS, SAFETY MEETINGS AGENDA, SAMPLING DATA AND DAILY LOGS. THIS SERVES AS THE GENERATORS' COMPLIANCE WITH FEDERAL AND STATE REGULATIONS AND WILL FORM PART OF FINAL REPORT.



NATIONAL PARK SERVICE



STATE HISTORIC
PRESERVATION OFFICE
OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS, PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



PLANIFICADORES

AVE. FERNADEZ JUNCOS 751

MIRAMAR SAN JUAN

OFICINA TEL.723-2031

FAXCIMIL (787) 722-5031

arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que soy el profesional que diseñó estos planos y las entiendo que dichos planos y especificaciones cumplen con las disposiciones aplicables del Reglamento Conjunto y las disposiciones aplicables de los Reglamentos y Códigos de Construcción Viaentes de las Agencias. Juntas Reglamentadoras o Corporaciones Públicas con jurisdicción. Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la "Ley para la Inversión por la Industria Puertorriqueña"y con la [Ley Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se hava producido por desconocimiento o por negligencia ya sea por mí, mis agentes o

PROFESSIONAL TEAM:

disciplinaria por la OGPe.

empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y

> Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

No.	Issue		Date
	Drawn by	<u>R</u>	Reviewed by
	GM EM		VV

SHEET TITLE AND NUMBER:

A-07_1

LEAD BASED PAINT ABATEMENT NOTES

딥

S

0

LANOS

 \vdash

 \mathbf{H}

 \Box

 \sim

0

 \mathcal{O}

0

田 C

 \circ

WATER PIPING BELOW GRADE TO BE TYPE "K" COPPER AND WATER PIPING ABOVE GRADE TO BE TYPE "L" HARD DRAWN COPPER. SIZE IS AS INDICATED DRAWINGS.

3. SOLDER USED IN ANY POTABE OR DOMESTIC WATER SYSTEM MUST BE LEAD-FREE.

4. ALL WATER SUPPLY LINES ARE TO BE SEPARATED A MINIMUM OF 1'-0" FROM SANITARY LINES.

5. ALL WASTE, SANITARY AND STORM DRAINAGE LINES 4" IN DIAMETER AND LARGED SHALL BE PVC SDR 35 AND SCHEDULE 40 FOR 3" AND SMALLIER.

6. LONG SWEEP BENDS OR LONG SWEEP FITTINGS SHALL BE PROVIDED AT THE BASE OF ALL STACKS.

7. FIXTURES, FITTINGS, ACCESSORIES, MATERIALS AND ALL PLUMBING PRODUCTS SHALL BE AS PER SPECIFICATIONS ON THESE DRAWINGS. EQUAL OR SIMILAR SHALL BE ONLY ACCEPTED IF PREVIOUSLY APPROVED BY THE ARCHITECT/ENGINEER.

8. ALL FIXTURES SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER SPECIFICATIONS.

THE PLUMBING WORK SHAUL BE IN ACCORDANCE WITH THE LATEST LOCAL BUILDING CODE, THE INTERNATIONAL PLUMBING CODE, THE HEALTH DEPARTMENT AND THE SPECIFICATIONS ISSUED FOR THE PROJECT.

10. SIZES SHOWN IN FIXTURE SCHEDULE ARE MINIMUM AND SHALL BE INCREASED AS NECESSARY TO COMPLY WITH CODE REQUIREMENTS OR AS SHOWN ON DRAWINGS.

11. BEFORE STARTING CONSTRUCTION, THE PLUMBING CONTRACTOR SHALL VERIFY THE EXACT LOCATION AND ELEVATIONS OF EXISTING PIPE LINES TO REMAIN IN USE . ANY SIGNIFICANT DISCREPANCY WITH THE INFORMATION SHOWN ON THESE DRAWINGS SHALL BE NOTIFIED TO THE ARCHITECT/ENGINEER FOR REVISION.

WATER FILTRATION SYSTEM

CONTRACTOR SHALL FURNISH & INSTALL THE FOLLOWING EQUIPMENT (OR EQUIVALENT):

1. PENTAIR WATER SOLUTIONS WHOLE HOUSE WATER FILTER SYSTEM + UV: PC1000-PUV-14-P, OR EQUIVALENT. A LICENSED PLUMBING CONTRACTOR SHALL INSTALL THIS EQUIPMENT AS PER MANUF.

2. PT600 CLASS D / 28"X28" MDPE SILT TRAP / FOX MDPE SILT BASKET / (2) 4" PIPE OUTLETS & CLASS D HEAVY DUTY GALV. GRATE BY FOX ENVIRONMENTAL SYSTEMS, OR EQUIVALENT.

PUMP ROOM ENTRACE NOTE

CONTRACTOR SHALL FURNISH & INSTALL AN ALUMINUM SWING DOOR MEASURING 72"X30" IN THE ENTRANCE TO THE PUMP ROOM. THE DOOR IS PRECEDED BY A LOWER LEVEL, MEASURING APPROX. 36 S.F., THAT THE REST OF THE SPACES AND IS SURROUNDED BY A CONCRETE WALL. THE G.C. SHALL MAKE A REINF. CONCRETE FLOOR IN THIS AREA WITH A ROUND CENTER DRAIN AND PVC TUBE DIRECTING

WATER OUT OF THE AREA.

12. A LICENSED PLUMBING CONTRACTOR SHALL PROVIDE ALL NECESSARY SERVICES AND/OR CONNECTIONS REQUIRED FOR THE PLUMBING FIXTURES AND EQUIPMENT SHOWN ON PLANS AND FIXTURES SCHEDULE.

13. A LICENSED PLUMBING CONTRACTOR SHALL PROVIDE ALL NECESSARY ROUGHING-IN AND INSTALL THE PLUMBING FIXTURES AS INDICATED ON THESE DRAWINGS.

14. THE PROPOSED WATER DISTRIBUTION SYSTEM MUST BE TESTED TO A HYDROSTATIC PRESSURE OF 125 PSI AND PROVED TIGHT AT THIS PRESSURE FOR FOUR CONSECUTIVE HOURS BEFORE PIPES ARE CONCEALED AND PRIOR TO ANY FIXTURE INSTALATION.


15. OTHER QUALIFIED MANUFACTURERS' PRODUCTS CAN BE SUBMITTED FOR APPROVAL TO THE ARCHITECT OR ENGINEER ALONG WITH A COMPARATIVE TABLE SHOWING CHARACTERISTICS OF THE SPECIFIED AND PROPOSED PRODUCT.

16. G.C. SHALL REMOVE ALL WATER FROM CISTERN, CLEAN EMPTY TANK WITH PRESSURE WATER. AFTER CLEANING WITH PRESSURED WATER, APPLY CLOROX & ENSURE NO MOLD TO REMAIN. PRIOR TO REFILLING WITH WATER, G.C. SHALL INSPECT TANK FOR CONCRETE FISSURED THAT COULD LEAD TO WATER FILTRATIONS. IF RELEVANT FISSURES ARE FOUND. G.C. SHALL REPAIR PRIOR TO REFILLING TANK WITH POTABLE WATER.


17. G.C. SHALL SUBMIT DRAWINGS SHOWING NEW EQUIPMENT LOCATIONS AND INSTALLATION DETAILS FOR ARCHITECT REVIEW PRIOR TO COMMENCING THE WORK.

18. G.C. SHALL BE RESPONSIBLE FOR ELECTRIFYING THE WATER PUMP.

19. THE EXISTING CISTERN, PRESSURE TANK AND WATER PUMP WERE DISCONNECTED BY OWNER TO USE A SEPARATE FRESHWATER SYSTEM. G.C. SHALL REMOVE SYSTEM THE OWNER INSTALLED AND RECONNECT ORIGINAL FRESHWATER SYSTEM.



scale: N.T.S (if printed on 24"x36")



DIRECTION OF FLOW

PIPING TYPES

GATE VALVE

----- COLD WATER PIPE

DISTERN & PUMP NOTES

1. CONTRACTOR SHALL FURNISH & INSTALL THE FOLLOWING EQUIPMENT (OR EQUAL). (EQUIPMENT BY: UNIVERSAL EQUIPMENT SALES & SERVICE CORP.)

PRESSURE TANK —AMERICAN WATER HEATER EXPORT PUMP TANKS — MODEL ADX-86, 86 GAL. CAP. PRESSURIZED TANK. WATER PUMP - WAYNE MODEL: SWS100, 1HP / SHALLOW WELL JET PUMP / CORROSION RESISTANT ALL CAST IRON MOTOR HOUSING.

SIMPLEX DOMESTIC CONTROL PANEL FOR 1 H.P. PUMPS, NEMA 4 ENCLOSURE, 1/60/240 VOLTS INCLUDING 120 VOLTS CONTROL AND MAGNETIC STARTERS WITH OVERLOAD PROTECTION, H-O-A SELECTOR SWITCHES, PILOT & RUNNING LIGHTS, AUTO ALTERNATION, HIGH LEVEL ALARM AND LOW WATER CUTOFF WITH LIGHT AND HORN. AT 1st LEVEL GARAGE CLOSET.

2. CONTRACTOR SHALL PROVIDE ALL NECESSARY ISOLATION VALVES, PRESSURE INDICATORS, PRESSURE REGULATORS, FLOAT VALVES, CHECK VALVES, LEVEL AND PRESSURE SENSORS AS REQUIRED FOR THE PROPER OPERATION OF THE SYSTEM

2 3/4" CHECK VALVE

1 FLOMATIC 2" "Y" STRAINER WITH SS PERF. SCREEN 2 3/4" DIA. RUBBER FLEXIBLE CONNECTION SCREW TYPE

PIPING	FICATIONS:	.C. TYPE SDR-35 .T.M. 3034	.C. D.W.V. SCH. 40 .T.MD-2665	PPER PIPE TYPE "K" .T.M B -88 - 60a	VANIZED PIPE 1. 40 A.S.T.MA- 120	PPER PIPE TYPE "L" .T.MB- 88-51	
SERVICE	LOCATION	— > \(\)	□ < > < < > < < > < < < < < > < < < < < <	COF A.S.	GAI	COF A.S.	
WATER	ABOVE GROUND					•	
	THRU CONCRETE SLAB						


EQUIPMENT NOTE

G.C. SHALL REMOVE AND DISPOSE OF ALL EXISTING EQUIPMENT THAT IS TO BE REPLACED WITH NEW.

ALTERNATE F

G.C. SHALL RESTORE EXISTING CISTERN AND REPLACE FRESHWATER SYSTEM ACCORDING TO SPECIFICATIONS ON SHEET P-01. WORKS SHALL INCLUDE, BUT ARE NOT LIMITED TO, CLEANING AND PAINTING PUMP ROOM, CLEANING THE CISTERN, INSTALLING NEW DOOR AND REINF. CONCRETE FLOORING IN ENTRANCE AREA, AND A NEW WATER FILTRATION SYSTEM.

PARK NATIONAL PARK SERVICE



STATE HISTORIC PRESERVATION OFFICE OFFICE OF THE GOVERNOR

EL CORTIJO

BARRANQUITAS. PUERTO RICO

Architect of Record: Victor M Villegas, A.I.A Registration No. 11445 PR.



ARQUITECTOS INGENIEROS PLANIFICADORES

AVE. FERNADEZ JUNCOS 751 MIRAMAR SAN JUAN OFICINA TEL.723-2031 FAXCIMIL (787) 722-5031 arquitectospr@arquiteg.com

Yo, Victor M. Villegas Durán, Lic. #11445, certifico que so el profesional que diseñó estos planos y las especificaciones complementarias. También, certifico qu entiendo que dichos planos y especificaciones cumplen con disposiciones aplicables de los Reglamentos y Códigos de Construcción Vigentes de las Agencias, Juntas Certifico, además, que en la preparación de estos planos y especificaciones se ha cumplido cabalmente con lo dispuesto en la Ley Núm. 14 de 8 de enero de 2004, según enmendada, conocida como la "Lev para la Inversió por la Industria Puertorriqueña" y con la ÎLey Núm. 319 de 15 de mayo de 1938, según enmendada; Ley Núm. 96 de 6 de julio de 1978, según enmendada; según aplique]. Reconozco que cualquier declaración falsa o falsificación de los hechos que se haya producido por desconocimiento o por negligencia ya sea por mí, mis agentes o

empleados, o por otras personas con mi conocimiento, me hacen responsable de cualquier acción judicial y

PROFESSIONAL TEAM:

Víctor M. Villegas Cristina Ballester Gilberto Mendoza Elvin E. Melendez Laurie S. Rivera

Issue

NEW SHEET	06/19/23
	_
	_
	_
Drawn by	Reviewed by
GM EM CB LR	VV

Date

SHEET TITLE AND NUMBER:

FRESHWATER SYSTEM DETAILS

ISSUE FOR BIDDING NOT FOR CONSTRUCTION V.M.V. DATE:JUNE 19, 2023

ELEMENTS SHOWN IN BLUE SHALL BE NEW. SEE SPECS.

ALL DIMENSIONS MUST BE VERIFIED ON SITE. EXACT LOCATION TO BE VERIFIED ON SITE.